

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Ganjam	Gram Panchayat	Khandadeuli

Work Code	OD/354/3373/117751/412006/00017499 (Repair and maintenance of AWC Building at Khandadeuli III)						
Project Category	Building						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Ganjam	Proposal Date	04-11-2024
Date of Commencement	22-08-2025	Date of Completion	04-11-2025
Scheme Name	Maintenance and Repair of Govt Residential Building	Scheme Component Name	Maintenance & Repair of Govt. Residential Buildings
Project Sub-Category	AWC	Project Type	Repair and Maintenance
Name of Executant	SUNITA BEHERA		

Administrative Approval Details

Approval No.	OD/354/3373/117751/412006/00017499/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3373/117751/412006/00017499/TS
Fund Sanction No.	10662
Fund Sanction Amount (in Rs.)	45000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Painting (AR0901dik) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces (outer surface)(For repair and maintenance) . - Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge(For repair and maintenance).</p>	-	92.754	Sqm
i	Highly-Skilled	0.054838709677419	5.0865096774194	-
ii	Un-Skilled	0.054838709677419	5.0865096774194	-
2	<p>Painting (AR0920k) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)(For Repair and maintenance) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)</p>	-	92.754	Sqm
i	Highly-Skilled	0.05508	5.10889032	-

	ii	Un-Skilled	0.06528	6.05498112	-
3		Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	17.202	Sqm
	i	Highly-Skilled	0.18817204301075	3.236935483871	-
	ii	Un-Skilled	0.17204301075269	2.9594838709677	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Highly-Skilled	13.43233548129	612	8220.5893145497
1	Un-Skilled	14.100974668387	462	6514.6502967948
Total:				14735.239611345