

ESTIMATION DPR							
State	Odisha	District	Bargarh	Block	Jharbandh	Gram Panchayat	Amthi

Work Code	OD/347/3318/116498/379926/00042815 (Repair & Maintenance Baitali UP School)						
Project Category	Building						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Jharbandh	Proposal Date	-
Date of Commencement	30-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Primary School Building
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant	SARITA PING		

Administrative Approval Details

Approval No.	OD/347/3318/116498/379926/00042815/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	27871
Fund Sanction Amount (in Rs.)	666878

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	11.844	240.77592	35482.737735
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	6.12075	539.100832	35482.737735

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	5.5815	5403.62493296	35482.737735
---	---	-----	--------	---------------	--------------

4	<p>R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	Cum	1.728	6054.3890742457	35482.737735
---	---	-----	-------	-----------------	--------------

5	<p>R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)</p>	Cum	0.85625	6811.2111993874	35482.737735
---	---	-----	---------	-----------------	--------------

6	<p>R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	Cum	0.975	14110.142461566	35482.737735
---	---	-----	-------	-----------------	--------------

7	<p>R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)</p>	Cum	0.51375	12718.673302776	35482.737735
---	---	-----	---------	-----------------	--------------

8	<p>R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	Cum	0.6591	12356.273478636	35482.737735
---	--	-----	--------	-----------------	--------------

9	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	Qntl	6	8414.3255742	35482.737735
---	---	------	---	--------------	--------------

10	<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	2.1717	5116.426581728	35482.737735
----	---	-----	--------	----------------	--------------

11	<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	4.33425	5149.756581728	35482.737735
12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	Sqm	64.1	190.4947590028	35482.737735

13	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	Sqm	35.7225	169.7772103992	35482.737735
14	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	36.2375	244.017356632	35482.737735

15	<p>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	Sqm	9.855	357.7390587992	35482.737735
16	<p>Concrete (AR0317) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge. (new work)</p>	Sqm	14.9075	354.2021438392	35482.737735

17	<p>Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	Sqm	114.43	1538.993153071	35482.737735
----	--	-----	--------	----------------	--------------

18	<p>Painting (AR0918fk) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) . - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).</p>	Sqm	450	89.13803985	35482.737735
19	<p>Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.</p>	Sqm	115.47	230.35420628603	35482.737735

20	<p>Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	Qntl	10.464	15757.807111087	35482.737735
21	<p>Roofing (AR1132) : Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge</p>	Sqm	17.6375	520.79998361032	35482.737735

22	Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	Sqm	450	78.8505283	35482.737735
----	---	-----	-----	------------	--------------

Total Amount (in Rs.): 653259.21655309

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.844	Cum
i	Un-Skilled	0.516	6.111504	-

2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.12075	Cum
i	Un-Skilled	0.1236	0.7565247	-
3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.5815	Cum
i	Skilled	0.18	1.00467	-
ii	Un-Skilled	3.9	21.76785	-

4	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	1.728	Cum
i	Un-Skilled	1.3333	2.3039424	-
ii	Skilled	0.175	0.3024	-
iii	Semi-Skilled	0.1323	0.2286144	-

5	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	0.85625	Cum
i	Un-Skilled	1.3333	1.141638125	-
ii	Skilled	0.35	0.2996875	-
iii	Semi-Skilled	0.3073	0.263125625	-

6	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	0.975	Cum
i	Un-Skilled	1.3333	1.2999675	-
ii	Skilled	5.33875	5.20528125	-
iii	Semi-Skilled	5.29605	5.16364875	-

7	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.51375	Cum
i	Un-Skilled	1.3333	0.684982875	-
ii	Skilled	2.34375	1.2041015625	-
iii	Semi-Skilled	2.30105	1.1821644375	-

8	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	0.6591	Cum
i	Un-Skilled	1.3333	0.87877803	-
ii	Skilled	3.15525	2.079625275	-
iii	Semi-Skilled	3.11255	2.051481705	-

9	R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	6	Qntl
i	Un-Skilled	0.8	4.8	-
ii	Highly-Skilled	0.3	1.8	-
iii	Semi-Skilled	0.044	0.264	-

10	Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	2.1717	Cum
i	Un-Skilled	2.96	6.428232	-
ii	Skilled	1.05	2.280285	-
iii	Highly-Skilled	0.35	0.760095	-

11	<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	4.33425	Cum
	i Un-Skilled	2.96	12.82938	-
	ii Skilled	1.05	4.5509625	-
	iii Highly-Skilled	0.35	1.5169875	-
12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	64.1	Sqm

	i	Un-Skilled	0.17	10.897	-
	ii	Skilled	0.14	8.974	-
13		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	35.7225	Sqm
	i	Un-Skilled	0.12	4.2867	-
	ii	Skilled	0.14	5.00115	-
14		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	36.2375	Sqm
	i	Un-Skilled	0.24	8.697	-

	ii	Skilled	0.16	5.798	-
15		Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	9.855	Sqm
	i	Un-Skilled	0.36	3.5478	-
	ii	Highly-Skilled	0.13	1.28115	-
16		Concrete (AR0317) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (new work)	-	14.9075	Sqm
	i	Un-Skilled	0.36	5.3667	-
	ii	Highly-Skilled	0.1	1.49075	-

17	<p>Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	114.43	Sqm
i	Highly-Skilled	0.325	37.18975	-
ii	Un-Skilled	0.325	37.18975	-
iii	Semi-Skilled	0.76	86.9668	-

18	<p>Painting (AR0918fk) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) . - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).</p>	-	450	Sqm
i	Un-Skilled	0.06528	29.376	-
ii	Highly-Skilled	0.05508	24.786	-
19	<p>Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.</p>	-	115.47	Sqm
i	Highly-Skilled	0.18817204301075	21.728225806452	-
ii	Un-Skilled	0.17204301075269	19.865806451613	-

20	Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	10.464	Qntl
i	Un-Skilled	6.3976377952756	66.944881889764	-
ii	Semi-Skilled	1.9685039370079	20.59842519685	-
iii	Skilled	3.9370078740157	41.196850393701	-
iv	Highly-Skilled	3.4448818897638	36.047244094488	-
21	Roofing (AR1132) : Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-	17.6375	Sqm
i	Un-Skilled	0.21505376344086	3.7930107526882	-
ii	Highly-Skilled	0.16129032258065	2.8447580645161	-

22	Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	450	Sqm
i	Highly-Skilled	0.052	23.4	-
ii	Un-Skilled	0.062	27.9	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	276.86744872406	462	127912.76131052
1	Skilled	77.897013481201	562	43778.121576435
2	Semi-Skilled	116.71826011435	512	59759.749178547
3	Highly-Skilled	152.84496046546	612	93541.115804859
Total: 324991.74787036				

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	11.844	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	6.12075	Cum
i)	<p>BRM029 : Sand for filling and road blinding</p>	1	6.12075	1 Cum
3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.5815	Cum
i)	<p>BRM340 : Cement</p>	2.29	12.781635	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.48	2.67912	1 Cum

iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	5.35824	1 Cum.
4	R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	1.728	Cum
i)	BRM340 : Cement	3.4733	6.0018624	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.7776	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.62208	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.93312	1 Cum.

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.00692064	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.326592	1Mtr.
5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	0.85625	Cum
i)	BRM340 : Cement	3.4733	2.974013125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.3853125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.30825	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.462375	1 Cum.

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0114309375	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	0.5394375	1Mtr.
6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	0.975	Cum
i)	BRM340 : Cement	3.4733	3.3864675	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.43875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.351	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.5265	1 Cum.

v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	4.30911	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.040490775	1Cum.
7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.51375	Cum
i)	BRM340 : Cement	3.4733	1.784407875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.2311875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.18495	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.277425	1 Cum.

v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	1.936580625	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.038086085625	1Cum.
8	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	0.6591	Cum
i)	BRM340 : Cement	3.4733	2.28925203	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.296595	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.237276	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.355914	1 Cum.

v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	4.10065656	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.03309815652	1Cum.
9	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	6	Qntl
i)	BRM162 : Binding Wire.	0.8	4.8	1 Kg.
ii)	BRM341 : Steel	1.05	6.3	1 Qntl.
10	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	2.1717	Cum
i)	BRM340 : Cement	0.672	1.4593824	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.608076	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	760.095	1000 Nos
11	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance \pm 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	4.33425	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	4.33425	1 Cum
ii)	BRM340 : Cement	0.672	2.912616	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.21359	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	350	1516.9875	1000 Nos

12	Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	64.1	Sqm
i)	BRM340 : Cement	0.0372	2.38452	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.48075	1 Cum
13	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge.	-	35.7225	Sqm
i)	BRM340 : Cement	0.0358	1.2788655	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.5358375	1 Cum

14	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	36.2375	Sqm
i)	BRM340 : Cement	0.043	1.5582125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.652275	1 Cum
15	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	9.855	Sqm
i)	BRM340 : Cement	0.0858	0.845559	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.11826	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	0.226665	1 Cum.

16	<p>Concrete (AR0317) :.2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in-charge. (new work)</p>	-	14.9075	Sqm
i)	BRM340 : Cement	0.1208	1.800826	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0169	0.25193675	1 Cum
iii)	BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	0.25193675	1 Cum.
17	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	114.43	Sqm

i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	114.43	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	114.43	1 Sqm
iii)	BRM340 : Cement	0.1375	15.734125	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.71645	1 Cum
18	Painting(AR0918fk) :.Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) . - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).	-	450	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	56.25	1 Ltr
19	Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	115.47	Sqm
i)	BRM137 : Red oxide Primer	0.054	6.23538	1 Litre
ii)	BRM141 : Enamel paint	0.125	14.43375	1 Litre

20	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-		10.464	Qntl
i)	BRM341 : Steel	1		10.464	1 Qntl.
21	Roofing (AR1132) :.Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-		17.6375	Sqm
i)	BRM149 : G.C.I. Sheet 0.30mm thick	1		17.6375	1 Sqm
22	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-		450	Sqm
i)	BRM142 : Distemper	0.25		112.5	1 Kg.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	6.12075	1 Cum	401.41	2456.9302575
2	BRM340	57.19174433	1 Qntl.	637.012	36431.827439142
3	BRM028	10.38574025	1 Cum	409.04	4248.18319186
4	BRM044	5.35824	1 Cum.	1289.29	6908.3252496

5	BRM060	1.703556	1 Cum.	1750.76	2982.51770256
6	BRM052	2.555334	1 Cum.	1682.65	4299.7327551
7	BRM104	0.130026594645	1Cum.	58573.086	7616.0589104287
8	BRM092	0.8660295	1Mtr.	229.106	198.412554627
9	BRM084	8.40976656	1Mtr	250.166	2103.837661249
10	BRM094	1.936580625	1Mtr.	240.106	464.98462754625
11	BRM162	4.8	1 Kg.	90.1	432.48
12	BRM341	16.764	1 Qntl.	6204.917	104019.228588
13	BRM005	2277.0825	1000 Nos	6.4484	14683.538793
14	BRMMR0025	4.33425	1 Cum	33	143.03025
15	BRM057	0.226665	1 Cum.	1393.83	315.93247695
16	BRM064	0.25193675	1 Cum.	1191.31	300.1347696425
17	BRM131	114.43	1 Sqm.	667.2266671	76350.747516253
18	BRMMR0027	114.43	1 Sqm	8.5	972.655
19	BRM255	56.25	1 Ltr	195.09732	10974.22425
20	BRM137	6.23538	1 Litre	143.00732	891.7049829816
21	BRM141	14.43375	1 Litre	205.64732	2968.26200505
22	BRM149	17.6375	1 Sqm	317.579032	5601.3001769
23	BRM142	112.5	1 Kg.	70.40732	7920.8235
Total: 293284.87265839					

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.844	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.12075	Cum
i)	BRM029 : Sand for filling and road blinding	1	6.12075	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.5815	Cum
i)	BRM340 : Cement	2.29	12.781635	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	2.67912	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	5.35824	1 Cum.

4	<p>R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	1.728	Cum
i)	BRM340 : Cement	3.4733	6.0018624	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.7776	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.62208	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.93312	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.00692064	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	0.001591488	1Mtr.

5	R.C.C. Work (AR0404Ab) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	0.85625	Cum
i)	BRM340 : Cement	3.4733	2.974013125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.3853125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.30825	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.462375	1 Cum.
v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0114309375	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	0.0026286875	1Mtr.

6	<p>R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	-	0.975	Cum
i)	BRM340 : Cement	3.4733	3.3864675	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.43875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.351	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.5265	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	0.04420525	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.040490775	1Cum.

7	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.51375	Cum
i)	BRM340 : Cement	3.4733	1.784407875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.2311875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.18495	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.277425	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	0.0254522025	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.038086085625	1Cum.

8	<p>R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	-	0.6591	Cum
i)	BRM340 : Cement	3.4733	2.28925203	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.296595	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.237276	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.355914	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	0.0505259469	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.03309815652	1Cum.

9	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	6	Qntl
i)	BRM341 : Steel	1.05	6.3	1 Qntl.
10	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	2.1717	Cum
i)	BRM340 : Cement	0.672	1.4593824	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.608076	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	760.095	1000 Nos

11	<p>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	4.33425	Cum
i)	BRM340 : Cement	0.672	2.912616	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.21359	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1516.9875	1000 Nos
12	<p>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	64.1	Sqm
i)	BRM340 : Cement	0.0372	2.38452	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.48075	1 Cum

13	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	35.7225	Sqm
i)	BRM340 : Cement	0.0358	1.2788655	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.5358375	1 Cum
14	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp. and as per direction of Engineer-in-charge.	-	36.2375	Sqm
i)	BRM340 : Cement	0.043	1.5582125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.652275	1 Cum
15	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	9.855	Sqm
i)	BRM340 : Cement	0.0858	0.845559	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.11826	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	0.226665	1 Cum.
16	Concrete (AR0317) :2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge. (new work)	-	14.9075	Sqm
i)	BRM340 : Cement	0.1208	1.800826	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0169	0.25193675	1 Cum
iii)	BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	0.25193675	1 Cum.

17	<p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	114.43	Sqm
i)	<p>BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	114.43	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	15.734125	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	1.71645	1 Cum

18	<p>Painting(AR0918fk) :.Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) . - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).</p>	-	450	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	56.25	1 Ltr
19	<p>Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.</p>	-	115.47	Sqm
i)	BRM137 : Red oxide Primer	0.054	6.23538	1 Litre
ii)	BRM141 : Enamel paint	0.125	14.43375	1 Litre
20	<p>Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	-	10.464	Qntl
i)	BRM341 : Steel	1	10.464	1 Qntl.

21	Roofing (AR1132) :.Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-	17.6375	Sqm
i)	BRM149 : G.C.I. Sheet 0.30mm thick	1	17.6375	1 Sqm
22	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	450	Sqm
i)	BRM142 : Distemper	0.25	112.5	1 Kg.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	6.12075	1 Cum	75.25	460.5864375
2	BRM028	10.38574025	1 Cum	75.25	781.5269538125
3	BRM044	5.35824	1 Cum.	279.5	1497.62808
4	BRM060	1.703556	1 Cum.	279.5	476.143902
5	BRM052	2.555334	1 Cum.	279.5	714.215853
6	BRM057	0.226665	1 Cum.	279.5	63.3528675
7	BRM064	0.25193675	1 Cum.	279.5	70.416321625
Total: 4063.8704154375					

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Display Citizen Board @ Rs. 3000	Rs. 3000

2	Any Other Lumpsum @ 1%	Rs. 6532.5921655309
Total Addition Component Amount (in Rs.): 9532.5921655309		

Total Net Amount (in Rs.): 662791.80871862