

BILLING DPR							
State	Odisha	District	Deogarh	Block	Tileibani	Gram Panchayat	Suguda
<b>Work Code</b>	OD/351/3348/117233/382783/00014371 (Repair & Maintanance of Apurba High school, Suguda)						
<b>Project Category</b>	Building						
<b>Financial Year</b>	2022-23		<b>Execution Level</b>		PS		
<b>Executing Agency</b>	Panchayat Samiti, Tileibani		<b>Bill Status</b>		Final Bill		
<b>Proposal Date</b>	-		<b>Date of Commencement</b>		22-09-2025		
<b>Date of Completion</b>	21-11-2025		<b>Scheme Name</b>		Asset Management School and Mass Education Department		
<b>Scheme Component Name</b>	Self/Personal Deposit		<b>Project Sub-Category</b>		Others		
<b>Project Type</b>	Repair and Maintenance		<b>Name of Executant</b>				

### Administrative Approval Details

<b>Approval No.</b>	OD/351/3348/117233/382783/00014371/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/351/3348/117233/382783/00014371/TS
<b>Fund Sanction No.</b>	2546
<b>Fund Sanction Amount (in Rs.)</b>	91500

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
1	<b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	Cum	3.9645	6138.16213048	1855.607064675
2	<b>Concrete (AR0307a) : Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	Cum	2.973375	7324.95286176	1855.607064675

3	<b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	Sqm	16.25	262.422746616	1855.607064675
4	<b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	Cum	4.5	240.77592	1855.607064675
5	<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	Cum	0.9	433.101332	1855.607064675
6	<b>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b> - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	Cum	1.8	5312.688260264	1855.607064675
7	<b>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure</b> - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	Cum	3.90625	5346.018260264	1855.607064675
8	<b>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside</b> - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	Sqm	16.25	185.1168248096	1855.607064675
9	<b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)</b> - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	Sqm	32.5	71.83753306751	1855.607064675
10	<b>Painting (AR0918Ai) : Finishing wall one coat with weather coat</b> - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	Sqm	32.5	57.09560199	1855.607064675

**Total Amount (in Rs.): 89496.42594309**

## LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.9645	Cum
i	Skilled	0.18	0.71361	-
ii	Un-Skilled	3.9	15.46155	-
2	<b>Concrete (AR0307a) : Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	2.973375	Cum
i	Un-Skilled	4.6	13.677525	-
ii	Skilled	0.68	2.021895	-
3	<b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	16.25	Sqm
i	Un-Skilled	0.24	3.9	-
ii	Skilled	0.16	2.6	-
4	<b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	4.5	Cum
i	Un-Skilled	0.516	2.322	-
5	<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	0.9	Cum
i	Un-Skilled	0.1236	0.11124	-

6	<b>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b> - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance $\pm 8$ percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	1.8	Cum
i	Un-Skilled	2.96	5.328	-
ii	Skilled	1.05	1.89	-
iii	Highly-Skilled	0.35	0.63	-
7	<b>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure</b> - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance $\pm 8$ percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	3.90625	Cum
i	Un-Skilled	2.96	11.5625	-
ii	Skilled	1.05	4.1015625	-
iii	Highly-Skilled	0.35	1.3671875	-
8	<b>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside</b> - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	16.25	Sqm
i	Un-Skilled	0.12	1.95	-
ii	Skilled	0.14	2.275	-
9	<b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)</b> - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	32.5	Sqm
i	Highly-Skilled	0.053763440860215	1.747311827957	-
ii	Un-Skilled	0.053763440860215	1.747311827957	-
10	<b>Painting (AR0918Ai) : Finishing wall one coat with weather coat</b> - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	32.5	Sqm
i	Un-Skilled	0.043	1.3975	-
ii	Highly-Skilled	0.036	1.17	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

1	Skilled	13.6020675	562	7644.361935
2	Un-Skilled	57.457626827957	462	26545.423594516
3	Highly-Skilled	4.914499327957	612	3007.6735887097
				<b>Total: 37197.459118226</b>

## MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>3.9645</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	9.078705	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1.90296	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	3.80592	1 Cum.
2	<b>Concrete (AR0307a) :.Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	<b>2.973375</b>	Cum
i)	<b>BRM057</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	2.6760375	1 Cum.
ii)	<b>BRM340</b> : Cement	3.23	9.60400125	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.33801875	1 Cum
3	<b>Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	<b>16.25</b>	Sqm
i)	<b>BRM340</b> : Cement	0.043	0.69875	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	0.2925	1 Cum

4	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	4.5	Cum
5	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	0.9	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	0.9	1 Cum
6	<b>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance $\pm 8$ percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	1.8	Cum
i)	<b>BRM340</b> : Cement	0.672	1.2096	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	0.504	1 Cum
iii)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	630	1000 Nos
7	<b>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance $\pm 8$ percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	3.90625	Cum
i)	<b>BRMMR0025</b> : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	3.90625	1 Cum
ii)	<b>BRM340</b> : Cement	0.672	2.625	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1.09375	1 Cum
iv)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	1367.1875	1000 Nos
8	<b>Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside -</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	16.25	Sqm
i)	<b>BRM340</b> : Cement	0.0358	0.58175	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	0.24375	1 Cum

9	<b>Painting(AR0901d) :Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</b>	-	32.5	Sqm
i)	<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.084	2.73	1 Ltr
10	<b>Painting(AR0918Ai) :Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.</b>	-	32.5	Sqm
i)	<b>BRM255 : Weather Coat (I.S.I.)</b>	0.075	2.4375	1 Ltr

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM340</b>	23.79780625	1 Qntl.	548.122	13044.101157363
2	<b>BRM028</b>	5.37497875	1 Cum	1063.41	5715.8061525375
3	<b>BRM044</b>	3.80592	1 Cum.	1726.96	6572.6716032
4	<b>BRM057</b>	2.6760375	1 Cum.	1816.9	4862.09253375
5	<b>BRM029</b>	0.9	1 Cum	331.46	298.314
6	<b>BRM005</b>	1997.1875	1000 Nos	6.1539	12290.49215625
7	<b>BRMMR0025</b>	3.90625	1 Cum	33	128.90625
8	<b>BRM253</b>	2.73	1 Ltr	159.33732	434.9908836
9	<b>BRM255</b>	2.4375	1 Ltr	195.09732	475.5497175
<b>Total: 43822.9244542</b>					

## ROYALTY STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meurement Qty)	Unit
1	<b>Concrete (AR0303) :Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</b>	-	3.9645	Cum
i)	<b>BRM340 : Cement</b>	2.29	9.078705	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.48	1.90296	1 Cum
iii)	<b>BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)</b>	0.96	3.80592	1 Cum.

2	<b>Concrete (AR0307a) :.Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.	-	<b>2.973375</b>	Cum
i)	<b>BRM057</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	2.6760375	1 Cum.
ii)	<b>BRM340</b> : Cement	3.23	9.60400125	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.33801875	1 Cum
3	<b>Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	<b>16.25</b>	Sqm
i)	<b>BRM340</b> : Cement	0.043	0.69875	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	0.2925	1 Cum
4	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>4.5</b>	Cum
5	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>0.9</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	0.9	1 Cum
6	<b>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance $\pm 8$ percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	<b>1.8</b>	Cum
i)	<b>BRM340</b> : Cement	0.672	1.2096	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	0.504	1 Cum
iii)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	630	1000 Nos

7	<b>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	<b>3.90625</b>	Cum
i)	<b>BRM340</b> : Cement	0.672	2.625	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1.09375	1 Cum
iii)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	1367.1875	1000 Nos
8	<b>Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside -</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	<b>16.25</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0358	0.58175	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	0.24375	1 Cum
9	<b>Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) -</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	<b>32.5</b>	Sqm
i)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.084	2.73	1 Ltr
10	<b>Painting(AR0918Ai) :.Finishing wall one coat with weather coat -</b> Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	<b>32.5</b>	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.075	2.4375	1 Ltr

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM028</b>	5.37497875	1 Cum	560.25	3011.3318446875
2	<b>BRM044</b>	3.80592	1 Cum.	156.5	595.62648
3	<b>BRM057</b>	2.6760375	1 Cum.	156.5	418.79986875
4	<b>BRM029</b>	0.9	1 Cum	40.25	36.225
5	<b>BRM005</b>	1997.1875	1000 Nos	0.04025	80.386796875
<b>Total: 4142.3699903125</b>					

#### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Display Citizen Board @ Rs. 1000	Rs. 1000

2	Contingency @ Rs. 1000	Rs. 1000
<b>Total Addition Component Amount (in Rs.): 2000</b>		

#### DEDUCTION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Contingency @ Rs. 1000	Rs. 1000
2	Royalty @ Rs. 1132.18029375	Rs. 1132.18029375
3	Additional Royalty @ Rs. 2840.3626525	Rs. 2840.3626525
4	EMF @ Rs. 56.6090146875	Rs. 56.6090146875
5	DMF @ Rs. 113.218029375	Rs. 113.218029375
6	Empty Gunny Bag (Cement x Gunny Bag Rate : 0 x 3.945) @ 205.14	Rs. 205.14
7	Labour Cess @ 1%	Rs. 914.9642594309
8	Any Other Lumpsum Bill @ 1%	Rs. 914.9642594309
<b>Total Deduction Component Amount (in Rs.): 7177.4385091743</b>		

**Total Net Amount (in Rs.): 84318.987433916**