

BILLING DPR

State	Odisha	District	Sundargarh	Block	Lathikata	Gram Panchayat	Balanda
--------------	--------	-----------------	------------	--------------	-----------	-----------------------	---------

Work Code	OD/373/3583/121676/384577/00026962 (Maintenance of RO Plant of Balanda)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Lathikata	Bill Status	Final Bill
Proposal Date	06-02-2023	Date of Commencement	15-07-2025
Date of Completion	22-07-2025	Scheme Name	5th SFC Grant in Aid
Scheme Component Name	Maintenance of Capital Assets	Project Sub-Category	Primary Health Centre
Project Type	Repair and Maintenance	Name of Executant	

Administrative Approval Details

Approval No.	OD/373/3583/121676/384577/00026962/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3583/121676/384577/00026962/TS
Fund Sanction No.	11826
Fund Sanction Amount (in Rs.)	300000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
1	Site Clearance (AR1406) : Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above - Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres and as per direction of Engineer-in-Charge.	Cum	4.66782	1560.117508	18739.322346785
2	Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	Cum	17.8117745	5064.548463796	18739.322346785

3	R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	Qntl	1.127149	8957.2519428	18739.322346785
4	Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	Sqm	86.8672	170.0317965744	18739.322346785
5	Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	Sqm	55.92	244.321891024	18739.322346785
6	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	Cum	16.41822	581.258232	18739.322346785
7	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	Cum	2.0522775	5404.43876672	18739.322346785
8	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	Cum	1.65151	6833.91296864	18739.322346785
9	Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	Sqm	17.8992	1009.2779514242	18739.322346785

10	Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	Sqm	3.909	1201.4387809346	18739.322346785
11	Flooring (AR0816j) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	Sqm	3.48145	991.5642035216	18739.322346785
12	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	Cum	0.77582	12670.290189778	18739.322346785
13	Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	Sqm	86.8672	156.87608395791	18739.322346785
14	Painting (AR0922a) : Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	Sqm	55.92	147.85942005791	18739.322346785
15	Painting (AR0903a) : Painting two coats of enamel paint with a coat of wood primer in inner surface paint (Inside) - Painting two coats of enamel paint with a coat of wood primer in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)	Sqm	3.381	234.33478366323	18739.322346785
16	Dismantling (AR1603) : Dismantling brick or stone masonry under 3m. - Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.	Cum	13.37082	1401.5088339223	18739.322346785

Total Amount (in Rs.): 245411.60691543

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Site Clearance (AR1406) : Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above - Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres and as per direction of Engineer-in-Charge.	-	4.66782	Cum
i	Un-Skilled	2.8	13.069896	-
ii	Skilled	0.2	0.933564	-
iii	Semi-Skilled	0.12	0.5601384	-
2	Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	17.8117745	Cum
i	Un-Skilled	2.96	52.72285252	-
ii	Skilled	1.05	18.702363225	-
iii	Highly-Skilled	0.35	6.234121075	-
3	R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	1.127149	Qntl
i	Un-Skilled	0.8	0.9017192	-
ii	Highly-Skilled	0.3	0.3381447	-
iii	Semi-Skilled	0.044	0.049594556	-
4	Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	86.8672	Sqm
i	Un-Skilled	0.12	10.424064	-
ii	Skilled	0.14	12.161408	-

5	Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	55.92	Sqm
i	Un-Skilled	0.24	13.4208	-
ii	Skilled	0.16	8.9472	-
6	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.41822	Cum
i	Un-Skilled	0.1236	2.029291992	-
7	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.0522775	Cum
i	Skilled	0.18	0.36940995	-
ii	Un-Skilled	3.9	8.00388225	-
8	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	1.65151	Cum
i	Un-Skilled	4.6	7.596946	-
ii	Skilled	0.68	1.1230268	-
9	Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	17.8992	Sqm
i	Un-Skilled	0.216	3.8662272	-
ii	Highly-Skilled	0.216	3.8662272	-

10	Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	3.909	Sqm
i	Un-Skilled	0.216	0.844344	-
ii	Highly-Skilled	0.216	0.844344	-
iii	Semi-Skilled	0.55	2.14995	-
11	Flooring (AR0816j) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	3.48145	Sqm
i	Un-Skilled	0.216	0.7519932	-
ii	Highly-Skilled	0.216	0.7519932	-
iii	Semi-Skilled	0.55	1.9147975	-
12	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.77582	Cum
i	Un-Skilled	1.3333	1.034400806	-
ii	Skilled	2.34375	1.818328125	-
iii	Semi-Skilled	2.30105	1.785200611	-
13	Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	86.8672	Sqm
i	Un-Skilled	0.11776344086022	10.229780369892	-
ii	Highly-Skilled	0.10776344086022	9.3611083698925	-

14	Painting (AR0922a) : Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	55.92	Sqm
i	Highly-Skilled	0.10576344086022	5.9142916129032	-
ii	Un-Skilled	0.11576344086022	6.4734916129032	-
15	Painting (AR0903a) : Painting two coats of enamel paint with a coat of wood primer in inner surface paint (Inside) - Painting two coats of enamel paint with a coat of wood primer in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)	-	3.381	Sqm
i	Highly-Skilled	0.18817204301075	0.63620967741935	-
ii	Un-Skilled	0.17204301075269	0.58167741935484	-
16	Dismantling (AR1603) : Dismantling brick or stone masonry under 3m. - Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.	-	13.37082	Cum
i	Un-Skilled	3.0035335689046	40.159706713781	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	172.11107328393	462	79515.315857176
2	Skilled	44.0553001	562	24759.0786562
3	Semi-Skilled	6.459681067	512	3307.356706304
4	Highly-Skilled	27.946439835215	612	17103.221179152
Total:				124684.97239883

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Site Clearance (AR1406) :.Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above - Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres and as per direction of Engineer-in-Charge.	-	4.66782	Cum

2	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	17.8117745	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	17.8117745	1 Cum
ii)	BRM340 : Cement	0.672	11.969512464	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	4.98729686	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	6234.121075	1000 Nos
3	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	1.127149	Qntl
i)	BRM162 : Binding Wire.	0.8	0.9017192	1 Kg.
ii)	BRM341 : Steel	1.05	1.18350645	1 Qntl.
4	Plastering (AR1004) :.12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	86.8672	Sqm
i)	BRM340 : Cement	0.0358	3.10984576	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.303008	1 Cum
5	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	55.92	Sqm
i)	BRM340 : Cement	0.043	2.40456	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.00656	1 Cum
6	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.41822	Cum
i)	BRM029 : Sand for filling and road blinding	1	16.41822	1 Cum

7	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.0522775	Cum
i)	BRM340 : Cement	2.29	4.699715475	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	0.9850932	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1.9701864	1 Cum.
8	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	1.65151	Cum
i)	BRM340 : Cement	3.23	5.3343773	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.7431795	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.486359	1 Cum.
9	Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	17.8992	Sqm
i)	BRM174 : White Cement.	0.0076	0.13603392	1Qntl
ii)	BRM340 : Cement	0.1074	1.92237408	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.3758832	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	17.8992	1 Sqm.
10	Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	3.909	Sqm
i)	BRMMR0027 : Wax Polish	1	3.909	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	3.909	1 Sqm.
iii)	BRM340 : Cement	0.2737	1.0698933	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.050817	1 Cum

11	Flooring (AR0816j) :.Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	3.48145	Sqm
i)	BRM134 : Chequered Tiles.	1	3.48145	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	3.48145	1 Sqm
iii)	BRM340 : Cement	0.2737	0.952872865	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.04525885	1 Cum
12	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.77582	Cum
i)	BRM340 : Cement	3.4733	2.694655606	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.349119	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.2792952	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.4189428	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	2.92445349	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.05751425197	1Cum.
13	Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	86.8672	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	10.8584	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	7.2968448	1 Ltr
14	Painting(AR0922a) :.Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	55.92	Sqm
i)	BRM142 : Distemper	0.25	13.98	1 Kg.
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	4.69728	1 Ltr

15	Painting(AR0903a) :.Painting two coats of enamel paint with a coat of wood primer in inner surface paint (Inside) - Painting two coats of enamel paint with a coat of wood primer in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)	-	3.381	Sqm
i)	BRM141 : Enamel paint	0.125	0.422625	1 Litre
ii)	BRM138 : Wood Primer	0.075	0.253575	1 Litre
16	Dismantling (AR1603) :.Dismantling brick or stone masonry under 3m. - Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.	-	13.37082	Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRMMR0025	17.8117745	1 Cum	33	587.7885585
2	BRM340	34.15780685	1 Qntl.	571.948	19536.489312244
3	BRM028	9.84621561	1 Cum	483.09	4756.6082990349
4	BRM005	6234.121075	1000 Nos	6.1539	38364.157683442
5	BRM162	0.9017192	1 Kg.	90.1	81.24489992
6	BRM341	1.18350645	1 Qntl.	6640.408	7858.9656986316
7	BRM029	16.41822	1 Cum	478.15	7850.371893
8	BRM044	1.9701864	1 Cum.	1310.32	2581.574643648
9	BRM056	1.486359	1 Cum.	1711.69	2544.18583671
10	BRM174	0.13603392	1Qntl	2035.488	276.89541175296
11	BRM131	17.8992	1 Sqm.	662.5466113	11859.054304981
12	BRMMR0027	7.39045	1 Sqm	8.5	62.818825
13	BRM130	3.909	1 Sqm.	462.5466113	1808.0947035717
14	BRM134	3.48145	1 Sqm.	254.75	886.8993875
15	BRM060	0.2792952	1 Cum.	1705.07	476.217866664
16	BRM052	0.4189428	1 Cum.	1697.36	711.096751008
17	BRM094	2.92445349	1Mtr.	325.714	952.53544404186
18	BRM104	0.05751425197	1Cum.	58658.694	3373.7109069471
19	BRM255	10.8584	1 Ltr	195.14488	2118.961164992
20	BRM252	11.9941248	1 Ltr	125.85488	1509.519137409
21	BRM142	13.98	1 Kg.	70.45488	984.9592224
22	BRM141	0.422625	1 Litre	205.69488	86.93179866
23	BRM138	0.253575	1 Litre	155.43488	39.414399696
Total:					109308.49614975

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Site Clearance (AR1406) :.Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above - Dismantling of Prestressed / Reinforced cement concrete grade M-20 & above including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres and as per direction of Engineer-in-Charge.	-	4.66782	Cum
2	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	17.8117745	Cum
i)	BRM340 : Cement	0.672	11.969512464	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	4.98729686	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	6234.121075	1000 Nos
3	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	1.127149	Qntl
i)	BRM341 : Steel	1.05	1.18350645	1 Qntl.
4	Plastering (AR1004) :.12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	86.8672	Sqm
i)	BRM340 : Cement	0.0358	3.10984576	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.303008	1 Cum
5	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	55.92	Sqm
i)	BRM340 : Cement	0.043	2.40456	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.00656	1 Cum
6	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.41822	Cum

i)	BRM029 : Sand for filling and road blinding	1	16.41822	1 Cum
7	Concrete (AR0303) :Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.0522775	Cum
i)	BRM340 : Cement	2.29	4.699715475	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	0.9850932	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1.9701864	1 Cum.
8	Concrete (AR0307) :Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	1.65151	Cum
i)	BRM340 : Cement	3.23	5.3343773	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.7431795	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.486359	1 Cum.
9	Other Building Items. (AR1901B) :Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	17.8992	Sqm
i)	BRM174 : White Cement.	0.0076	0.13603392	1Qntl
ii)	BRM340 : Cement	0.1074	1.92237408	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.3758832	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	17.8992	1 Sqm.
10	Flooring (AR0816) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Enginer-in-charge.	-	3.909	Sqm
i)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	3.909	1 Sqm.
ii)	BRM340 : Cement	0.2737	1.0698933	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.050817	1 Cum

11	Flooring (AR0816j) :.Fixing Chequred Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequred Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequred tiles including rubbing and polishing, cost of precast tiles complete as per direction of Enginer-in-charge.	-	3.48145	Sqm
i)	BRM340 : Cement	0.2737	0.952872865	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.013	0.04525885	1 Cum
12	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.77582	Cum
i)	BRM340 : Cement	3.4733	2.694655606	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.349119	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.2792952	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.4189428	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	0.03843567444	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.05751425197	1Cum.
13	Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	86.8672	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	10.8584	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	7.2968448	1 Ltr
14	Painting(AR0922a) :.Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	55.92	Sqm
i)	BRM142 : Distemper	0.25	13.98	1 Kg.
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	4.69728	1 Ltr
15	Painting(AR0903a) :.Painting two coats of enamel paint with a coat of wood primer in inner surface paint (Inside) - Painting two coats of enamel paint with a coat of wood primer in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)	-	3.381	Sqm
i)	BRM141 : Enamel paint	0.125	0.422625	1 Litre

ii)	BRM138 : Wood Primer	0.075	0.253575	1 Litre
16	Dismantling (AR1603) :.Dismantling brick or stone masonry under 3m. - Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.	-	13.37082	Cum

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	9.84621561	1 Cum	75.25	740.9277246525
2	BRM005	6234.121075	1000 Nos	0.040271	251.05428981132
3	BRM029	16.41822	1 Cum	40.25	660.833355
4	BRM044	1.9701864	1 Cum.	279.5	550.6670988
5	BRM056	1.486359	1 Cum.	149.5	222.2106705
6	BRM060	0.2792952	1 Cum.	279.5	78.0630084
7	BRM052	0.4189428	1 Cum.	279.5	117.0945126
Total: 2620.8506597638					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Display Citizen Board @ Rs. 3000	Rs. 3000
2	Any Other Lumpsum @ Rs. 51162	Rs. 51162
Total Addition Component Amount (in Rs.): 54162		

DEDUCTION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Royalty @ Rs. 1677.571325975	Rs. 1677.571325975
2	Additional Royalty @ Rs. 691.64363489257	Rs. 691.64363489257
3	EMF @ Rs. 83.87856629875	Rs. 83.87856629875
4	DMF @ Rs. 167.7571325975	Rs. 167.7571325975
5	Empty Gunny Bag (Cement x Gunny Bag Rate : 0 x 3.945) @ 284.04	Rs. 284.04
6	Labour Cess @ 1%	Rs. 2995.7360691543
7	Any Other Lumpsum Bill @ 1.5%	Rs. 4493.6041037314
Total Deduction Component Amount (in Rs.): 10394.23083265		

Total Net Amount (in Rs.): 289179.37608278