

BILLING DPR							
State	Odisha	District	Angul	Block	Chhendipada	Gram Panchayat	Durgapur

Work Code	OD/344/3279/115640/404301/00047569 (IMP AT ROAD FROM AMBALASAHI TO DURGAPUR)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Chhendipada	Bill Status	Final Bill
Proposal Date	-	Date of Commencement	08-08-2025
Date of Completion	09-09-2025	Scheme Name	5th SFC Grant in Aid
Scheme Component Name	Maintenance of Capital Assets	Project Sub-Category	CC Road
Project Type	Repair and Maintenance	Name of Executant	

Administrative Approval Details

Approval No.	OD/344/3279/115640/404301/00047569/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/344/3279/115640/404301/00047569/TS
Fund Sanction No.	5261
Fund Sanction Amount (in Rs.)	500000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	Cum	47.6713328	240.77592	138105.34397181
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	Cum	26.75796016	1273.057732	138105.34397181

3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	Cum	39.58122304	6639.00933368	138105.34397181
4	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	Sqm	102.1933	216.23489289764	138105.34397181
5	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	Cum	17.12600064	8064.07443716	138105.34397181
Total Amount (in Rs.): 468525.74753998					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	47.6713328	Cum
i	Un-Skilled	0.516	24.5984077248	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.75796016	Cum
i	Un-Skilled	0.1236	3.307283875776	-
3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	39.58122304	Cum
i	Skilled	0.18	7.1246201472	-
ii	Un-Skilled	3.9	154.366769856	-

4	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	102.1933	Sqm
i	Semi-Skilled	0.05	5.109665	-
ii	Skilled	0.05	5.109665	-
5	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	17.12600064	Cum
i	Un-Skilled	4.6	78.779602944	-
ii	Skilled	0.68	11.6456804352	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	261.05206440058	462	120606.05375307
2	Skilled	23.8799655824	562	13420.540657309
3	Semi-Skilled	5.109665	512	2616.14848
Total:				136642.74289037

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	47.6713328	Cum
2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.75796016	Cum
i)	BRM029 : Sand for filling and road blinding	1	26.75796016	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	39.58122304	Cum

i)	BRM340 : Cement	2.29	90.6410007616	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	18.9989870592	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	37.9979741184	1 Cum.
4	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	102.1933	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.272856111	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	12.8763558	1Mtr.
5	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.	-	17.12600064	Cum
i)	BRM340 : Cement	3.23	55.3169820672	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.706700288	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.413400576	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	26.75796016	1 Cum	933.85	24987.921095416
2	BRM340	145.9579828288	1 Qntl.	538.472	78594.28692979
3	BRM028	26.7056873472	1 Cum	938.79	25071.032224678
4	BRM044	37.9979741184	1 Cum.	2087.16	79307.85166096
5	BRM104	0.272856111	1Cum.	58573.086	15982.024455229
6	BRM092	12.8763558	1Mtr.	229.106	2950.0503719148
7	BRM056	15.413400576	1 Cum.	2488.53	38356.709735393
Total:					265249.87647338

ROYALTY STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	47.6713328	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.75796016	Cum
i)	BRM029 : Sand for filling and road blinding	1	26.75796016	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	39.58122304	Cum
i)	BRM340 : Cement	2.29	90.6410007616	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	18.9989870592	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	37.9979741184	1 Cum.
4	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	102.1933	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.272856111	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0627466862	1Mtr.
5	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.	-	17.12600064	Cum
i)	BRM340 : Cement	3.23	55.3169820672	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.706700288	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	15.413400576	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	26.75796016	1 Cum	269.5	7211.27026312
2	BRM028	26.7056873472	1 Cum	269.5	7197.1827400704
3	BRM044	37.9979741184	1 Cum.	550	20898.88576512
4	BRM056	15.413400576	1 Cum.	550	8477.3703168
Total: 43784.70908511					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
--------	-----------	-----------------

1	Display Citizen Board @ Rs. 4000	Rs. 4000
2	Any Other Lumpsum @ Rs. 19000	Rs. 19000
3	Contingency @ Rs. 5000	Rs. 5000
4	Provision for survey investigation and quality control @ Rs. 3474	Rs. 3474
		Total Addition Component Amount (in Rs.): 31474

DEDUCTION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Contingency @ Rs. 5000	Rs. 5000
2	Royalty @ Rs. 8814.706373024	Rs. 8814.706373024
3	Additional Royalty @ Rs. 33647.796756133	Rs. 33647.796756133
4	EMF @ Rs. 440.7353186512	Rs. 440.7353186512
5	DMF @ Rs. 881.4706373024	Rs. 881.4706373024
6	Empty Gunny Bag (Cement x Gunny Bag Rate : 111 x 3.945) @ 1155.885	Rs. 1155.885
7	Labour Cess @ 1%	Rs. 4999.9974753998
		Total Deduction Component Amount (in Rs.): 54940.59156051

Total Net Amount (in Rs.): 445059.15597947