

BILLING DPR							
State	Odisha	District	Ganjam	Block	Beguniapada	Gram Panchayat	Beruanbadi
<b>Work Code</b>	OD/354/3365/117597/411727/00017545 (REPAIR AND MAINTANANCE OF AWC BUILDING AT BERUNBADI 2)						
<b>Project Category</b>	Building						
<b>Financial Year</b>	2024-25		<b>Execution Level</b>		PS		
<b>Executing Agency</b>	Panchayat Samiti, Beguniapada		<b>Bill Status</b>		Final Bill		
<b>Proposal Date</b>	03-12-2024		<b>Date of Commencement</b>		03-06-2025		
<b>Date of Completion</b>	05-07-2025		<b>Scheme Name</b>		Asset Management Women and Child Development Department		
<b>Scheme Component Name</b>	Self/Personal Deposit		<b>Project Sub-Category</b>		AWC		
<b>Project Type</b>	Repair and Maintenance		<b>Name of Executant</b>				

### Administrative Approval Details

<b>Approval No.</b>	OD/354/3365/117597/411727/00017545/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/354/3365/117597/411727/00017545/TS
<b>Fund Sanction No.</b>	11574
<b>Fund Sanction Amount (in Rs.)</b>	45000

### LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</b>	-	190.9175	Sqm
i	Highly-Skilled	0.053763440860215	10.26438172043	-
ii	Un-Skilled	0.053763440860215	10.26438172043	-
2	<b>Painting (AR0901ai) : Priming one coat in outer surface with primer of approved quality over woodwork - Priming one coat in outer surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</b>	-	91.085	Sqm
i	Highly-Skilled	0.053763440860215	4.8970430107527	-
ii	Un-Skilled	0.053763440860215	4.8970430107527	-

3	<b>Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) -</b> Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	155.3775	Sqm
i	Highly-Skilled	0.052	8.07963	-
ii	Un-Skilled	0.062	9.633405	-
4	<b>Painting (AR0918gk) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work(Outside)(For repair and maintenance) . -</b> Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).	-	72.68	Sqm
i	Un-Skilled	0.12011870967742	8.7302278193548	-
ii	Highly-Skilled	0.10991870967742	7.9888918193548	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Highly-Skilled	31.229946550538	612	19112.727288929
2	Un-Skilled	33.525057550538	462	15488.576588348
<b>Total:</b>				<b>34601.303877277</b>