

BILLING DPR							
State	Odisha	District	Koraput	Block	Jeypore	Gram Panchayat	Barniput
Work Code	OD/363/3470/119781/429076/00029888 (Repair and Maintenance of CC Road from RD Road to Kadamguda)						
Project Category	Road						
Financial Year	2024-25		Execution Level		PS		
Executing Agency	Panchayat Samiti, Jeypore		Bill Status		Final Bill		
Proposal Date	16-12-2024		Date of Commencement		11-08-2025		
Date of Completion	06-09-2025		Scheme Name		5th SFC Grant in Aid		
Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES		Project Sub-Category		CC Road		
Project Type	Repair and Maintenance		Name of Executant				

Administrative Approval Details

Approval No.	OD/363/3470/119781/429076/00029888/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3470/119781/429076/00029888/TS
Fund Sanction No.	1528
Fund Sanction Amount (in Rs.)	220000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	17.18	Cum
i	Un-Skilled	0.516	8.86488	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.97	Cum
i	Un-Skilled	0.1236	3.333492	-

3	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	72	Sqm
i	Semi-Skilled	0.05	3.6	-
ii	Skilled	0.05	3.6	-
4	R.C.C. Work (AR0401) : R.C.C work - 'Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)	-	11.784	Cum
i	Un-Skilled	4.6	54.2064	-
ii	Skilled	0.68	8.01312	-
5	miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	152.1	Sqm

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	66.404772	462	30679.004664
2	Semi-Skilled	3.6	512	1843.2
3	Skilled	11.61312	562	6526.57344
Total:				39048.778104