

BILLING DPR							
State	Odisha	District	Sambalpur	Block	Jamankira	Gram Panchayat	Jamankira
Work Code	OD/371/3560/121318/381932/00036652 (Repair And Maintainance Of Market Complex, Jamankira)						
Project Category	Building						
Financial Year	2023-24		Execution Level		PS		
Executing Agency	Panchayat Samiti, Jamankira		Bill Status		Final Bill		
Proposal Date	-		Date of Commencement		16-09-2025		
Date of Completion	01-11-2025		Scheme Name		5th SFC Grant in Aid		
Scheme Component Name	Maintenance of Capital Assets		Project Sub-Category		Market Complex		
Project Type	Repair and Maintenance		Name of Executant				

Administrative Approval Details

Approval No.	OD/371/3560/121318/381932/00036652/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/371/3560/121318/381932/00036652/TS
Fund Sanction No.	12437
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Dismantling (AR1612) : Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	51	Sqm
i	Un-Skilled	0.21505376344086	10.967741935484	-
2	Dismantling (AR1616) : Dismantling G.C.I. or A.C. sheet roofing - Dismantling G.C.I. or A.C. sheet roofing after carefully removing the bolts and nuts including stacking of he materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	25.5	Sqm
i	Un-Skilled	0.16129032258065	4.1129032258065	-
ii	Skilled	0.026881720430108	0.68548387096774	-
3	Dismantling (AR1620) : Dismantling and removing 2.5 cm thick grading concrete from roof - Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	78.2	Sqm
i	Un-Skilled	0.24193548387097	18.91935483871	-

4	Concrete (AR0317) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (new work)	-	78.2	Sqm
i	Un-Skilled	0.36	28.152	-
ii	Highly-Skilled	0.1	7.82	-
5	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.06	Cum
i	Skilled	0.18	0.5508	-
ii	Un-Skilled	3.9	11.934	-
6	Flooring (AR0817abk) : Fixing Vitrified floor tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster(For repair and maintenance). - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados, skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles(For repair and maintenance).	-	60.6	Sqm
i	Highly-Skilled	0.325	19.695	-
ii	Un-Skilled	0.325	19.695	-
iii	Semi-Skilled	0.76	46.056	-
7	Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	21	Sqm
i	Highly-Skilled	0.18817204301075	3.9516129032258	-
ii	Un-Skilled	0.17204301075269	3.6129032258065	-
8	Roofing (AR1132i) : Supplying, fitting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.40mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-	30.6	Sqm
i	Un-Skilled	0.21505376344086	6.5806451612903	-
ii	Highly-Skilled	0.16129032258065	4.9354838709677	-

9	Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	346.1	Sqm
i	Un-Skilled	0.11776344086022	40.75792688172	-
ii	Highly-Skilled	0.10776344086022	37.29692688172	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	144.73247526882	462	66866.403574194
2	Skilled	1.2362838709677	562	694.79153548387
3	Highly-Skilled	73.699023655914	612	45103.802477419
4	Semi-Skilled	46.056	512	23580.672
				Total: 136245.6695871