

BILLING DPR							
State	Odisha	District	Ganjam	Block	Buguda	Gram Panchayat	Arakhapur
Work Code	OD/354/3368/117654/410446/00062811 (Maintenance & Improvement of CC Road from GP Office to Malatipathapur)						
Project Category	Road						
Financial Year	2021-22		Execution Level		PS		
Executing Agency	Panchayat Samiti, Buguda		Bill Status		Final Bill		
Proposal Date	-		Date of Commencement		06-11-2025		
Date of Completion	18-11-2025		Scheme Name		5th SFC Grant in Aid		
Scheme Component Name	Maintenance and improvement of Road infrastructure		Project Sub-Category		CC Road		
Project Type	Repair and Maintenance		Name of Executant				

Administrative Approval Details

Approval No.	OD/354/3368/117654/410446/00062811/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3368/117654/410446/00062811/TS
Fund Sanction No.	12614
Fund Sanction Amount (in Rs.)	147984

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0122Ai16) : Earthwork in all kinds of soil within 50m lead, with four extra lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth - Earthwork in all kinds of soil within 50m lead, with four extra lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	4.8668	Cum
i	Un-Skilled	0.637534	3.1027504712	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.79	Cum
i	Un-Skilled	0.1236	2.075244	-

3	Concrete (AR0304) : Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal - Cement concrete (1:4:8) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.8668	Cum
i	Un-Skilled	3.9	18.98052	-
ii	Skilled	0.18	0.876024	-
4	miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	150.75	Sqm
5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	55.2	Sqm
i	Semi-Skilled	0.05	2.76	-
ii	Skilled	0.05	2.76	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	24.1585144712	462	11161.233685694
2	Skilled	3.636024	562	2043.445488
3	Semi-Skilled	2.76	512	1413.12
Total:				14617.799173694