

BILLING DPR							
State	Odisha	District	Sundargarh	Block	Lahunipara	Gram Panchayat	Lahunipara
Work Code	OD/373/3582/121669/384869/00063254 (REPAIR AND MAINTENANCE OF VETERINARY DISPENSARY LAHUNIPARA)						
Project Category	Building						
Financial Year	2025-26		Execution Level		PS		
Executing Agency	Panchayat Samiti, Lahunipara		Bill Status		Final Bill		
Proposal Date	22-09-2025		Date of Commencement		21-11-2025		
Date of Completion	26-11-2025		Scheme Name		Asset Management Fishery and Animal Resources Development Department		
Scheme Component Name	Self/Personal Deposit		Project Sub-Category		Veterinary Dispensary		
Project Type	Repair and Maintenance		Name of Executant				

Administrative Approval Details

Approval No.	OD/373/3582/121669/384869/00063254/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3582/121669/384869/00063254/TS
Fund Sanction No.	4209
Fund Sanction Amount (in Rs.)	150000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	8.25	Cum
i	Un-Skilled	0.516	4.257	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.1775	Cum
i	Un-Skilled	0.1236	0.887139	-

3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.8925	Cum
i	Skilled	0.18	1.42065	-
ii	Un-Skilled	3.9	30.78075	-
4	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	5.456	Cum
i	Un-Skilled	4.6	25.0976	-
ii	Skilled	0.68	3.71008	-
5	R.C.C. Work (AR0410f) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor in ground floor R.C.C. walls and fins including attached pilasters	-	10.01	Sqm
i	Semi-Skilled	0.56485355648536	5.6541841004184	-
ii	Skilled	0.56485355648536	5.6541841004184	-
6	Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	185.535	Sqm
i	Un-Skilled	0.11776344086022	21.84924	-
ii	Highly-Skilled	0.10776344086022	19.99389	-
7	Painting (AR0901d) : Fourth Floor - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	185.535	Sqm
i	Highly-Skilled	0.060511226344086	11.22695037975	-
ii	Un-Skilled	0.060511226344086	11.22695037975	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	94.09867937975	462	43473.589873444
2	Skilled	10.784914100418	562	6061.1217244351
3	Semi-Skilled	5.6541841004184	512	2894.9422594142
4	Highly-Skilled	31.22084037975	612	19107.154312407

Total: 71536.808169701