

BILLING DPR							
State	Odisha	District	Khordha	Block	Chilika	Gram Panchayat	Biribadi
Work Code	OD/362/3462/119639/408144/00064058 (Maintenance and Improvement of CC Road from RD Road to Biribadi High School East Side,Biribadi GP.)						
Project Category	Road						
Financial Year	2022-23		Execution Level		PS		
Executing Agency	Panchayat Samiti, Chilika		Bill Status		Final Bill		
Proposal Date	-		Date of Commencement		13-11-2025		
Date of Completion	15-11-2025		Scheme Name		5th SFC Grant in Aid		
Scheme Component Name	Maintenance and improvement of Road infrastructure		Project Sub-Category		CC Road		
Project Type	Repair and Maintenance		Name of Executant				

Administrative Approval Details

Approval No.	OD/362/3462/119639/408144/00064058/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/362/3462/119639/408144/00064058/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	19.46931211712	Cum
i	Un-Skilled	0.516	10.046165052434	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	16.749670368	Cum
i	Un-Skilled	0.1236	2.0702592574848	-

3	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	19.2563392608	Sqm
i	Semi-Skilled	0.05	0.96281696304	-
ii	Skilled	0.05	0.96281696304	-
4	Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	25.94092986624	Cum
i	Un-Skilled	3.9	101.16962647834	-
ii	Skilled	0.18	4.6693673759232	-
5	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	15.21098076288	Cum
i	Un-Skilled	4.6	69.970511509248	-
ii	Skilled	0.68	10.343466918758	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	183.2565622975	462	84664.531781446
2	Semi-Skilled	0.96281696304	512	492.96228507648
3	Skilled	15.975651257722	562	8978.3160068395
Total:				94135.810073362