

BILLING DPR							
State	Odisha	District	Bhadrak	Block	Bonth	Gram Panchayat	Purusandha

Work Code	OD/348/3325/116678/394304/00064889 (MAINTAINCE OF CC ROAD FROM PANDA GADHIA CHHAKA PURUSANDHA NODAL SCHOOL TO PADHI SAHI OF VILLAGE PURUSANDHA)		
Project Category	Road		

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Bonth	Bill Status	Final Bill
Proposal Date	-	Date of Commencement	18-11-2025
Date of Completion	28-11-2025	Scheme Name	5th SFC Grant in Aid
Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES	Project Sub-Category	CC Road
Project Type	Repair and Maintenance	Name of Executant	

Administrative Approval Details

Approval No.	OD/348/3325/116678/394304/00064889/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/348/3325/116678/394304/00064889/TS
Fund Sanction No.	250000
Fund Sanction Amount (in Rs.)	250000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.845413648	Cum
i	Un-Skilled	0.516	1.468233442368	-
2	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.702507976	Cum
i	Un-Skilled	0.1236	0.7048299858336	-

3	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.789739304	Cum
i	Skilled	0.18	1.40215307472	-
ii	Un-Skilled	3.9	30.3799832856	-
4	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	45.64974711	Sqm
i	Semi-Skilled	0.05	2.2824873555	-
ii	Skilled	0.05	2.2824873555	-
5	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	24.9977595552	Cum
i	Un-Skilled	4.6	114.98969395392	-
ii	Skilled	0.68	16.998476497536	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	147.54274066772	462	68164.746188487
2	Skilled	20.683116927756	562	11623.911713399
3	Semi-Skilled	2.2824873555	512	1168.633526016
Total:				80957.291427902