

BILLING DPR

State	Odisha	District	Ganjam	Block	Surada	Gram Panchayat	Bhagabanpur
--------------	--------	-----------------	--------	--------------	--------	-----------------------	-------------

Work Code	OD/354/3385/275061/410907/00065262 (Repair and maintenance of UPS Gunduribadi)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Surada	Bill Status	1st Bill
Proposal Date	-	Date of Commencement	25-11-2025
Date of Completion	-	Scheme Name	Asset Management School and Mass Education Department
Scheme Component Name	Self/Personal Deposit	Project Sub-Category	Elementary School
Project Type	Repair and Maintenance	Name of Executant	

Administrative Approval Details

Approval No.	OD/354/3385/275061/410907/00065262/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3385/275061/410907/00065262/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	150000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.	-	3.8875125	Cum
i	Un-Skilled	4.6	17.8825575	-
ii	Skilled	0.68	2.6435085	-
2	Other Building Items. (AR1901B) : Fifth Floor - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	55.8985	Sqm
i	Un-Skilled	0.2756768175	15.409920583024	-

ii	Highly-Skilled	0.2756768175	15.409920583024	-
3	Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	8.0035	Sqm
i	Highly-Skilled	0.325	2.6011375	-
ii	Un-Skilled	0.325	2.6011375	-
iii	Semi-Skilled	0.76	6.08266	-
4	Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	24.075	Sqm
i	Highly-Skilled	0.18817204301075	4.5302419354839	-
ii	Un-Skilled	0.17204301075269	4.141935483871	-
5	Painting (AR0918cb) : Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	244.0435	Sqm
i	Un-Skilled	0.11776344086022	28.73940227957	-
ii	Highly-Skilled	0.10776344086022	26.29896727957	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	68.774953346465	462	31774.028446067
2	Skilled	2.6435085	562	1485.651777
3	Highly-Skilled	48.840267298078	612	29890.243586423
4	Semi-Skilled	6.08266	512	3114.32192
Total:				66264.24572949