

BILLING DPR							
State	Odisha	District	Kendujhar	Block	Hatadihi	Gram Panchayat	Mareigaon
Work Code	OD/361/3449/119400/387195/00039924 (Repairing of Floor and Colouring of veterinary Dispensary)						
Project Category	Building						
Financial Year	2023-24	Execution Level	PS				
Executing Agency	Panchayat Samiti, Hatadihi	Bill Status	Final Bill				
Proposal Date	19-10-2024	Date of Commencement	24-07-2025				
Date of Completion	30-07-2025	Scheme Name	Asset Management Fishery and Animal Resources Development Department				
Scheme Component Name	Self/Personal Deposit	Project Sub-Category	Veterinary Dispensary				
Project Type	New Work	Name of Executant					

Administrative Approval Details

Approval No.	OD/361/3449/119400/387195/00039924/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3449/119400/387195/00039924/TS
Fund Sanction No.	5815
Fund Sanction Amount (in Rs.)	25000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	miscellaneous(ARM122) :.Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge. - Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.	-	130.0642	Sqm
i)	BRMM122 : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting)	1	130.0642	Sqm
2	Painting(AR0918hk) :.Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside)(For repair and maintenance). - Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).	-	130.0642	Sqm

i)	BRM255 : Weather Coat (I.S.I.)	0.125	16.258025	1 Ltr
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	11.747734193548	1 Ltr

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRMM122	130.0642	Sqm	5.12	665.928704
2	BRM255	16.258025	1 Ltr	195.03787	3170.9305664068
3	BRM253	11.747734193548	1 Ltr	159.27787	1871.1540796746
					Total: 5708.0133500813