

**BILLING DPR**

<b>State</b>	Odisha	<b>District</b>	Nayagarh	<b>Block</b>	Bhapur	<b>Gram Panchayat</b>	Bijipur
--------------	--------	-----------------	----------	--------------	--------	-----------------------	---------

<b>Work Code</b>	OD/367/3523/120594/406113/00055961 (Major Repairing of Door of Girls & Boys Toilet , Smart Class Roof grading, electrification of RCS High School, Bijipur)
<b>Project Category</b>	Building

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Bhapur	<b>Bill Status</b>	Final Bill
<b>Proposal Date</b>	-	<b>Date of Commencement</b>	27-10-2025
<b>Date of Completion</b>	11-01-2026	<b>Scheme Name</b>	Asset Management School and Mass Education Department
<b>Scheme Component Name</b>	Self/Personal Deposit	<b>Project Sub-Category</b>	Secondary School
<b>Project Type</b>	Repair and Maintenance	<b>Name of Executant</b>	

**Administrative Approval Details**

<b>Approval No.</b>	OD/367/3523/120594/406113/00055961/AS
---------------------	---------------------------------------

**Technical Sanction Details**

<b>Technical Sanction No.</b>	OD/367/3523/120594/406113/00055961/TS
<b>Fund Sanction No.</b>	8559
<b>Fund Sanction Amount (in Rs.)</b>	150000

**MATERIAL STATEMENT**

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Dismantling (AR1621) :.First floor -</b> Removing old grading plaster from roof slab, cleaning the surface,lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	<b>197.87</b>	Sqm
2	<b>Iron Work(AR1704) :.Iron Doors and windows fixing -</b> Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	<b>2.205</b>	Qntl
i)	<b>BRM341 : Steel</b>	1	2.205	1 Qntl.
3	<b>Concrete (AR0317) :.First floor -</b> 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (new work)	-	<b>197.87</b>	Sqm

i)	<b>BRM340</b> : Cement	0.1208	23.902696	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0169	3.344003	1 Cum
iii)	<b>BRM064</b> : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	3.344003	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM341</b>	2.205	1 Qntl.	6204.157	13680.166185
2	<b>BRM340</b>	23.902696	1 Qntl.	587.627	14045.869542392
3	<b>BRM028</b>	3.344003	1 Cum	430.15	1438.42289045
4	<b>BRM064</b>	3.344003	1 Cum.	1256.41	4201.43880923
<b>Total:</b>					<b>33365.897427072</b>