

BILLING DPR							
State	Odisha	District	Ganjam	Block	Surada	Gram Panchayat	Lathipada
<b>Work Code</b>	OD/354/3385/118033/410878/00065059 (Improve of P.S at Tinikhandia)						
<b>Project Category</b>	Building						
<b>Financial Year</b>	2021-22		<b>Execution Level</b>		PS		
<b>Executing Agency</b>	Panchayat Samiti, Surada		<b>Bill Status</b>		1st Bill		
<b>Proposal Date</b>	-		<b>Date of Commencement</b>		22-12-2025		
<b>Date of Completion</b>	-		<b>Scheme Name</b>		5th SFC Grant in Aid		
<b>Scheme Component Name</b>	Maintenance of Primary School Building		<b>Project Sub-Category</b>		Elementary School		
<b>Project Type</b>	Upgradation or Improvement		<b>Name of Executant</b>				

### Administrative Approval Details

<b>Approval No.</b>	OD/354/3385/118033/410878/00065059/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/354/3385/118033/410878/00065059/TS
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	100000

### MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Dismantling (AR1612) :.Dismantling and removing 2.5 cm. thick artificial stone flooring -</b> Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	<b>55.055</b>	Sqm
2	<b>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	<b>3.4409375</b>	Cum
i)	<b>BRM340 : Cement</b>	3.23	11.114228125	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	1.548421875	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	3.09684375	1 Cum.
3	<b>Other Building Items. (AR1901B) :Vitrified Tile 600mmx600mm Plain Ivory</b> - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	<b>55.055</b>	Sqm
i)	<b>BRM174</b> : White Cement.	0.0076	0.418418	1Qntl
ii)	<b>BRM340</b> : Cement	0.1074	5.912907	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	1.156155	1 Cum
iv)	<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	55.055	1 Sqm.
4	<b>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)</b> - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	<b>6.504</b>	Sqm
i)	<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	6.504	1 Sqm.
ii)	<b>BRMMR0027</b> : Wax Polish	1	6.504	1 Sqm
iii)	<b>BRM340</b> : Cement	0.1375	0.8943	1 Qntl.
iv)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	0.09756	1 Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM340</b>	17.921435125	1 Qntl.	604.387	10831.482410893
2	<b>BRM028</b>	2.802136875	1 Cum	407.34	1141.4224346625
3	<b>BRM056</b>	3.09684375	1 Cum.	1737.73	5381.4782896875
4	<b>BRM174</b>	0.418418	1Qntl	2053.857	859.370738226
5	<b>BRM131</b>	61.559	1 Sqm.	663.9538891	40872.337459107
6	<b>BRMMR0027</b>	6.504	1 Sqm	8.5	55.284
<b>Total: 59141.375332576</b>					