

**BILLING DPR**

<b>State</b>	Odisha	<b>District</b>	Jajpur	<b>Block</b>	Rasulpur	<b>Gram Panchayat</b>	Routrapur
--------------	--------	-----------------	--------	--------------	----------	-----------------------	-----------

<b>Work Code</b>	OD/356/3402/118485/401141/00070121 (Improvement/Repair & maintenance of CC road from Dhaneswar Tripathy house to Tuka Singh house at Routrapur.)
<b>Project Category</b>	Road

<b>Financial Year</b>	2020-21	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Rasulpur	<b>Bill Status</b>	1st Bill
<b>Proposal Date</b>	-	<b>Date of Commencement</b>	29-12-2025
<b>Date of Completion</b>	-	<b>Scheme Name</b>	5th SFC Grant in Aid
<b>Scheme Component Name</b>	MAINTENANCE OF ROADS AND BRIDGES	<b>Project Sub-Category</b>	CC Road
<b>Project Type</b>	Repair and Maintenance	<b>Name of Executant</b>	

**Administrative Approval Details**

<b>Approval No.</b>	OD/356/3402/118485/401141/00070121/AS
---------------------	---------------------------------------

**Technical Sanction Details**

<b>Technical Sanction No.</b>	OD/356/3402/118485/401141/00070121/TS
<b>Fund Sanction No.</b>	8054
<b>Fund Sanction Amount (in Rs.)</b>	165000

**MATERIAL STATEMENT**

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaicion and direction of Engineer-in charge.</b>	-	<b>22.218884</b>	Cum
i)	<b>BRM340 : Cement</b>	3.23	71.76699532	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	9.9984978	1 Cum
iii)	<b>BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve &amp; retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)</b>	0.9	19.9969956	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM340</b>	71.76699532	1 Qntl.	568.667	40811.521927638

2	<b>BRM028</b>	9.9984978	1 Cum	417.99	4179.272095422
3	<b>BRM056</b>	19.9969956	1 Cum.	2092.07	41835.114584892
					<b>Total: 86825.908607952</b>