

| BILLING DPR | | | | | | | |
|------------------------------|--|----------|-----------------------------|-------|----------------------|----------------|-----------|
| State | Odisha | District | Sonepur | Block | Sonepur | Gram Panchayat | Hardokhol |
| Work Code | OD/372/3570/121477/419558/00013492 (Repair & Maintenance of Pr. School Building at Majhimunda) | | | | | | |
| Project Category | Building | | | | | | |
| Financial Year | 2020-21 | | Execution Level | | PS | | |
| Executing Agency | Panchayat Samiti, Sonepur | | Bill Status | | Final Bill | | |
| Proposal Date | 27-10-2021 | | Date of Commencement | | 19-12-2024 | | |
| Date of Completion | 20-01-2025 | | Scheme Name | | 5th SFC Grant in Aid | | |
| Scheme Component Name | Maintenance of Primary School Building | | Project Sub-Category | | Elementary School | | |
| Project Type | New Work | | Name of Executant | | | | |

Administrative Approval Details

| | |
|---------------------|---------------------------------------|
| Approval No. | OD/372/3570/121477/419558/00013492/AS |
|---------------------|---------------------------------------|

Technical Sanction Details

| | |
|--------------------------------------|---------------------------------------|
| Technical Sanction No. | OD/372/3570/121477/419558/00013492/TS |
| Fund Sanction No. | 19600 |
| Fund Sanction Amount (in Rs.) | 100000 |

ROYALTY STATEMENT

| Sl.No. | Activity Name/Material | Qty/unit (B=Analysis Basic Qty/Header Unit) | Quantity (Meaurement Qty) | Unit |
|--------|--|---|---------------------------|--------|
| 1 | Dismantling (AR1612) :.Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge. | - | 52.35 | Sqm |
| 2 | Other Building Items. (AR1901Ba) :.Vitrified Tile 600mmx600mm Coloured /Printed - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge. | - | 57.015 | Sqm |
| i) | BRM132 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Coloured / Printed series(Homogeneous) | 1 | 57.015 | 1 Sqm. |
| ii) | BRM174 : White Cement. | 0.0076 | 0.433314 | 1Qntl |

| | | | | |
|------|---|--------|----------------|---------|
| iii) | BRM340 : Cement | 0.1074 | 6.123411 | 1 Qntl. |
| iv) | BRM028 : Screened and washed sharp sand for mortar | 0.021 | 1.197315 | 1 Cum |
| 3 | Painting(AR0918f) :.Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside) - Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside) | - | 83.16 | Sqm |
| i) | BRM255 : Weather Coat (I.S.I.) | 0.125 | 10.395 | 1 Ltr |
| 4 | Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. | - | 2.51895 | Cum |
| i) | BRM340 : Cement | 3.23 | 8.1362085 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.45 | 1.1335275 | 1 Cum |
| iii) | BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken) | 0.9 | 2.267055 | 1 Cum. |

| S/N | Material Name | Qty | Unit | Royalty Rate | Amount |
|------------------------------|---------------|-----------|--------|--------------|---------------|
| 1 | BRM028 | 2.3308425 | 1 Cum | 170.25 | 396.825935625 |
| 2 | BRM056 | 2.267055 | 1 Cum. | 279.5 | 633.6418725 |
| Total: 1030.467808125 | | | | | |