

BILLING DPR							
State	Odisha	District	Khordha	Block	Balipatna	Gram Panchayat	Mukundadaspur
Work Code	OD/362/3457/275275/407670/00036307 (Repair And Maintenance Of Bhagabati Primary School)						
Project Category	Building						
Financial Year	2023-24	Execution Level	PS				
Executing Agency	Panchayat Samiti, Balipatna	Bill Status	Final Bill				
Proposal Date	-	Date of Commencement	30-10-2025				
Date of Completion	13-11-2025	Scheme Name	5th SFC Grant in Aid				
Scheme Component Name	Maintenance of Primary School Building	Project Sub-Category	Elementary School				
Project Type	Upgradation or Improvement	Name of Executant					

Administrative Approval Details

Approval No.	OD/362/3457/275275/407670/00036307/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/362/3457/275275/407670/00036307/TS
Fund Sanction No.	15220
Fund Sanction Amount (in Rs.)	150000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.	-	4.035887316	Cum
i)	BRM340 : Cement	3.23	13.03591603068	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.8161492922	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	3.6322985844	1 Cum.

2	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	0.4875	Qntl
i)	BRM341 : Steel	1	0.4875	1 Qntl.
3	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.149960832	Cum
i)	BRM029 : Sand for filling and road blinding	1	3.149960832	1 Cum
4	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	3.0002534216832	Cum
i)	BRM340 : Cement	0.672	2.0161702993711	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	0.8400709580713	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1050.0886975891	1000 Nos
5	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	59.02685008	Sqm
i)	BRM340 : Cement	0.043	2.53815455344	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.06248330144	1 Cum
6	Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	150.224151	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.125	18.778018875	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	12.618828684	1 Ltr
7	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.496794216	Cum
i)	BRM340 : Cement	2.29	14.87765875464	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	3.11846122368	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	6.23692244736	1 Cum.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	6.8371647753913	1 Cum	118.25	808.49473469002
2	BRM056	3.6322985844	1 Cum.	158.5	575.7193256274
3	BRM029	3.149960832	1 Cum	118.25	372.482868384
4	BRM044	6.23692244736	1 Cum.	158.5	988.55220790656
Total: 2745.249136608					