

BILLING DPR							
State	Odisha	District	Kandhamal	Block	G.Udayagiri	Gram Panchayat	Mallikapadi
Work Code	OD/359/3425/118918/415830/00065798 (Repair of AWC at Sirki)						
Project Category	Building						
Financial Year	2023-24		Execution Level		PS		
Executing Agency	Panchayat Samiti, G.Udayagiri		Bill Status		Final Bill		
Proposal Date	-		Date of Commencement		04-12-2025		
Date of Completion	06-12-2025		Scheme Name		SFC Devolution of Fund		
Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI		Project Sub-Category		AWC		
Project Type	Repair and Maintenance		Name of Executant				

Administrative Approval Details

Approval No.	OD/359/3425/118918/415830/00065798/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3425/118918/415830/00065798/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	100000

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	4.7413685316	Cum
i)	BRM340 : Cement	0.672	3.1861996532352	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.327583188848	1 Cum
iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1659.47898606	1000 Nos

2	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	22.58936445	Sqm
i)	BRM340 : Cement	0.0358	0.80869924731	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.33884046675	1 Cum
3	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	12.1238415	Sqm
i)	BRM340 : Cement	0.043	0.5213251845	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	0.218229147	1 Cum
4	Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	6.14646248	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	6.14646248	1 Sqm.
ii)	BRM340 : Cement	0.1375	0.845138591	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.0921969372	1 Cum
5	Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	16.483314775	Sqm
i)	BRM174 : White Cement.	0.0076	0.12527319229	1Qntl
ii)	BRM340 : Cement	0.1074	1.770308006835	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.346149610275	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	16.483314775	1 Sqm.

6	Painting(AR0901ci) :.Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	139.53566085	Sqm
i)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	11.7209955114	1 Ltr
7	Painting(AR0918Ai) :.Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	363.6409226	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	27.273069195	1 Ltr
8	Painting(AR0904) :.Painting one coat of enamel on old wood work inner surface paint - Painting one coat of enamel on old wood work inner surface paint including all costs of labour, Paint, Primer and brushes and required for the work etc. complete and as per direction of Engineer-in-charge.	-	12.30500235	Sqm
i)	BRM141 : Enamel paint	0.075	0.92287517625	1 Litre
9	Iron Work(AR1701) :.Labour for hoisting joints, trusses and placing in position - Labour for hoisting joints, trusses and placing in position with all cost of labour and machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	2	Qntl

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	2.322999350073	1 Cum	40.25	93.500723840438
					Total: 93.500723840438