

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Gajapati	<b>Block</b>	Rayagad	<b>Gram Panchayat</b>	Dambala

<b>Work Code</b>	OD/353/3363/117548/414749/00034803 (Improvement of Govt. UP School Dambalo)						
<b>Project Category</b>	Building						

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Rayagad	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	19-11-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Primary School Building
<b>Project Sub-Category</b>	Elementary School	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>	Janemejay Mohanta		

### Administrative Approval Details

<b>Approval No.</b>	OD/353/3363/117548/414749/00034803/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/353/3363/117548/414749/00034803/TS
<b>Fund Sanction No.</b>	3809
<b>Fund Sanction Amount (in Rs.)</b>	600000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p><b>R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b>  Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	Cum	8.97475	7151.849906716	24272.503943926
---	---	-----	---------	----------------	-----------------

2	<p><b>R.C.C. Work (AR0409) :</b>  <b>Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b>  Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	Qntl	9.5	8698.2542997	24272.503943926
3	<p><b>Plastering (AR1017) : 20mm thick cement Plaster in CM (1:4) over masonry work in inside. -</b> 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	40.8	296.389457888	24272.503943926

4	<p><b>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth -</b> Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	15.9201	5319.80548544	24272.503943926
5	<p><b>R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	Sqm	30.3475	1047.9038224181	24272.503943926

6	<p><b>R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</p>	Sqm	8.004	499.57698698128	24272.503943926
7	<p><b>R.C.C. Work (AR0410a) : Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	Sqm	50.206	663.29946175911	24272.503943926

8	<p><b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b>  16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	81.9	263.23625556	24272.503943926
9	<p><b>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside -</b>  12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	Sqm	86.96	185.786330216	24272.503943926

10	<p><b>Other Building Items. (AR1901B)</b>  <b>: Vitrified Tile</b>  <b>600mmx600mm</b>  <b>Plain Ivory -</b>  Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	Sqm	82.3075	1050.771215501	24272.503943926
----	---	-----	---------	----------------	-----------------

11	<p><b>Flooring (AR0817aa) :</b>  <b>Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>          Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	Sqm	10.41	1576.880989161	24272.503943926
12	<p><b>Iron Work (AR1704) : Iron Doors and windows fixing -</b>          Supplying, fitting &amp; fixing of Mild steel and put up for frames &amp; shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T &amp; P required for the work etc. as per direction of Engineer-in-charge.</p>	Qntl	0.07065	16028.215421087	24272.503943926

13	<b>miscellaneous (ARM105) : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.</b>	Sqm	7.065	16.22	24272.503943926
14	<b>Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</b>	Sqm	42.705	66.13194368351	24272.503943926

15	<p><b>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) -</b>  6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	Sqm	47.85	202.337677744	24272.503943926
16	<p><b>Other Building Items. (AR1902) : cement based wall putty (water based) -</b>  Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc.complete. and as per the direction of Engineer in Charge.</p>	Sqm	129.75	79.21834	24272.503943926

17	<p><b>Painting (AR0920)</b>  <b>: Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b>          Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	Sqm	129.75	94.7901564	24272.503943926
18	<p><b>Painting (AR0922)</b>  <b>: Finishing wall two coats with distemper of approved shades on new work (Inside) -</b>          Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	Sqm	187.1125	78.9105728	24272.503943926

19	<b>Painting (AR0917g) : Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work (Outside) -</b> Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	Sqm	192.4455	126.12663815951	24272.503943926
<b>Total Amount (in Rs.): 528690.47690212</b>					

## LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<b>R.C.C. Work (AR0404A) :</b> <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	8.97475	Cum
i	Un-Skilled	1.3333	11.966034175	-
ii	Skilled	0.1	0.897475	-
iii	Semi-Skilled	0.0573	0.514253175	-

2	<p><b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b>  Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	9.5	Qntl
i	Un-Skilled	0.8	7.6	-
ii	Highly-Skilled	0.3	2.85	-
iii	Semi-Skilled	0.044	0.418	-
3	<p><b>Plastering (AR1017) : 20mm thick cement Plaster in CM (1:4) over masonry work in inside. -</b> 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	40.8	Sqm
i	Un-Skilled	0.24	9.792	-

	ii	Skilled	0.16	6.528	-
4		<b>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth</b> - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	15.9201	Cum
	i	Un-Skilled	2.96	47.123496	-
	ii	Skilled	1.05	16.716105	-
	iii	Highly-Skilled	0.35	5.572035	-

5	<p><b>R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</b></p>	-	30.3475	Sqm
i	Semi-Skilled	0.6547619047619	19.870386904762	-
ii	Skilled	0.6547619047619	19.870386904762	-
6	<p><b>R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</b></p>	-	8.004	Sqm
i	Semi-Skilled	0.16025641025641	1.2826923076923	-
ii	Skilled	0.16025641025641	1.2826923076923	-

7	<p><b>R.C.C. Work (AR0410a) : Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	-	50.206	Sqm
i	Semi-Skilled	0.305555555555556	15.3407222222222	-
ii	Skilled	0.305555555555556	15.3407222222222	-
8	<p><b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp. and as per direction of Engineer-in-charge.</p>	-	81.9	Sqm
i	Un-Skilled	0.24	19.656	-
ii	Skilled	0.16	13.104	-

9	<p><b>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</b></p>	-	86.96	Sqm
i	Un-Skilled	0.12	10.4352	-
ii	Skilled	0.14	12.1744	-
10	<p><b>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</b></p>	-	82.3075	Sqm
i	Un-Skilled	0.216	17.77842	-
ii	Highly-Skilled	0.216	17.77842	-

11	<p><b>Flooring (AR0817aa)</b>  <b>: Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>          Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	10.41	Sqm	
	i	Highly-Skilled	0.325	3.38325	-
	ii	Un-Skilled	0.325	3.38325	-
	iii	Semi-Skilled	0.76	7.9116	-
12	<p><b>Iron Work (AR1704) :</b>  <b>Iron Doors and windows fixing -</b>          Supplying, fitting &amp; fixing of Mild steel and put up for frames &amp; shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T &amp; P required for the work etc. as per direction of Engineer-in-charge.</p>	-	0.07065	Qntl	

	i	Un-Skilled	6.3976377952756	0.45199311023622	-
	ii	Semi-Skilled	1.9685039370079	0.13907480314961	-
	iii	Skilled	3.9370078740157	0.27814960629921	-
	iv	Highly-Skilled	3.4448818897638	0.24338090551181	-
13		<b>miscellaneous (ARM105) : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.</b>	-	7.065	Sqm
14		<b>Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</b>	-	42.705	Sqm
	i	Highly-Skilled	0.053763440860215	2.2959677419355	-
	ii	Un-Skilled	0.053763440860215	2.2959677419355	-

15	<p><b>Plastering (AR1027) :</b>  <b>6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) -</b> 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	47.85	Sqm
i	Un-Skilled	0.17	8.1345	-
ii	Skilled	0.14	6.699	-
16	<p><b>Other Building Items. (AR1902) :</b>  <b>cement based wall putty (water based) -</b> Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	129.75	Sqm
i	Un-Skilled	0.057	7.39575	-
ii	Skilled	0.05	6.4875	-

17	<p><b>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	129.75	Sqm
i	Highly-Skilled	0.054	7.0065	-
ii	Un-Skilled	0.064	8.304	-
18	<p><b>Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) -</b> Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	187.1125	Sqm
i	Highly-Skilled	0.052	9.72985	-
ii	Un-Skilled	0.062	11.600975	-

19	<b>Painting (AR0917g) : Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work (Outside) -</b> Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	192.4455	Sqm
i	Highly-Skilled	0.089763440860215	17.274570258065	-
ii	Un-Skilled	0.096763440860215	18.621688758065	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	184.53927478524	462	85257.144950779
1	Skilled	99.378431040976	562	55850.678245028
2	Semi-Skilled	45.476729412826	512	23284.085459367
3	Highly-Skilled	66.133973905512	612	40473.992030173
<b>Total:</b>				<b>204865.90068535</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	---------------------------	---	------------------------------	------

1	<b>R.C.C. Work (AR0404A)</b> <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	<b>8.97475</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	31.171999175	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	4.0386375	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.23091	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.846365	1 Cum.

2	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	9.5	Qntl
i)	<b>BRM162</b> : Binding Wire.	0.8	7.6	1 Kg.
ii)	<b>BRM341</b> : Steel	1.05	9.975	1 Qntl.
3	<b>Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. -</b> 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	40.8	Sqm
i)	<b>BRM340</b> : Cement	0.0744	3.03552	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	0.8568	1 Cum

4	<p><b>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth</b>  - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	15.9201	Cum
i)	<p><b>BRM006</b> : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm<sup>2</sup> with dimensional tolerance <math>\pm 2</math> %</p>	400	6368.04	1000 Nos
ii)	<p><b>BRM340</b> : Cement</p>	0.672	10.6983072	1 Qntl.
iii)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.28	4.457628	1 Cum
5	<p><b>R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	-	30.3475	Sqm
i)	<p><b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.</p>	0.55238095238095	16.763380952381	1Mtr

ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.15751797619048	1Cum.
6	<b>R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</b>	-	<b>8.004</b>	Sqm
i)	<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	2.1549230769231	1Mtr.
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.042380153846154	1Cum.
7	<b>R.C.C. Work (AR0410a) :.Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</b>	-	<b>50.206</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.62222222222222	31.239288888889	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00502222222222	0.25214568888889	1Cum.

8	<b>Plastering (AR1014)</b> <b>::16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	<b>81.9</b>	Sqm
i)	<b>BRM340</b> : Cement	0.043	3.5217	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1.4742	1 Cum
9	<b>Plastering (AR1004)</b> <b>::12mm thick cement plaster (1:6) over Brick work in inside</b> - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	<b>86.96</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0358	3.113168	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1.3044	1 Cum

10	<p><b>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory -</b>  Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	<b>82.3075</b>	Sqm
i)	<b>BRM174</b> : White Cement.	0.0076	0.625537	1Qntl
ii)	<b>BRM340</b> : Cement	0.1074	8.8398255	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	1.7284575	1 Cum
iv)	<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	82.3075	1 Sqm.

11	<p><b>Flooring (AR0817aa)</b>  <b>:.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>  Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	10.41	Sqm
i)	<p><b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	10.41	1 Sqm.
ii)	<p><b>BRMMR0027</b> : Wax Polish</p>	1	10.41	1 Sqm
iii)	<p><b>BRM340</b> : Cement</p>	0.1375	1.431375	1 Qntl.
iv)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.015	0.15615	1 Cum
12	<p><b>Iron Work(AR1704)</b>  <b>:.Iron Doors and windows fixing -</b>  Supplying, fitting &amp; fixing of Mild steel and put up for frames &amp; shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T &amp; P required for the work etc. as per direction of Engineer-in-charge.</p>	-	0.07065	Qntl
i)	<p><b>BRM341</b> : Steel</p>	1	0.07065	1 Qntl.

13	<b>miscellaneous(ARM105) :.Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.</b>	-	7.065	Sqm
i)	<b>BRMM105</b> : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works)	1	7.065	Sqm
14	<b>Painting(AR0901b) :.Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</b>	-	42.705	Sqm
i)	<b>BRM137</b> : Red oxide Primer	0.054	2.30607	1 Litre
15	<b>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</b>	-	47.85	Sqm
i)	<b>BRM340</b> : Cement	0.0372	1.78002	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	0.358875	1 Cum

16	<p><b>Other Building Items. (AR1902) :.cement based wall putty (water based) -</b>  Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	129.75	Sqm
i)	<b>BRMMR0038</b> : Cement based putty	0.8	103.8	kg
17	<p><b>Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b>  Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	129.75	Sqm
i)	<b>BRM140</b> : Plastic Emulsion paint	0.125	16.21875	1 Litre
18	<p><b>Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) -</b>  Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	187.1125	Sqm
i)	<b>BRM142</b> : Distemper	0.25	46.778125	1 Kg.

19	<b>Painting(AR0917g)</b> :.Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work <b>(Outside)</b> - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	<b>192.4455</b>	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.075	14.4334125	1 Ltr
ii)	<b>BRM252</b> : Wall cement primer (I.S.I.) Oil bound	0.084	16.165422	1 Ltr

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM340</b>	63.591914875	1 Qntl.	807.512	51351.234364541
2	<b>BRM028</b>	14.375148	1 Cum	1030.79	14817.75880692
3	<b>BRM060</b>	3.23091	1 Cum.	2372.58	7665.5924478
4	<b>BRM052</b>	4.846365	1 Cum.	2336.2	11322.077913
5	<b>BRM162</b>	7.6	1 Kg.	90.1	684.76
6	<b>BRM341</b>	10.04565	1 Qntl.	6436.342	64657.2390123
7	<b>BRM006</b>	6368.04	1000 Nos	5.36398	34158.0391992
8	<b>BRM084</b>	48.00266984127	1Mtr	297.726	14291.642881162
9	<b>BRM104</b>	0.45204381892552	1Cum.	58620.646	26499.100685721
10	<b>BRM094</b>	2.1549230769231	1Mtr.	287.666	619.89810184615
11	<b>BRM174</b>	0.625537	1Qntl	2071.692	1295.919998604
12	<b>BRM131</b>	92.7175	1 Sqm.	668.8630561	62015.310403952
13	<b>BRMMR0027</b>	10.41	1 Sqm	8.5	88.485
14	<b>BRMM105</b>	7.065	Sqm	16.22	114.5943
15	<b>BRM137</b>	2.30607	1 Litre	143.24512	330.3332738784
16	<b>BRMMR0038</b>	103.8	kg	30	3114
17	<b>BRM140</b>	16.21875	1 Litre	249.88512	4052.82429

18	<b>BRM142</b>	46.778125	1 Kg.	70.64512	3304.646254
19	<b>BRM255</b>	14.4334125	1 Ltr	195.33512	2819.352362697
20	<b>BRM252</b>	16.165422	1 Ltr	126.04512	2037.5725558406
<b>Total: 305240.38185146</b>					

## ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p><b>R.C.C. Work (AR0404A)</b>  <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b>  Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	-	<b>8.97475</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	31.171999175	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	4.0386375	1 Cum
iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	3.23091	1 Cum.

iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	4.846365	1 Cum.
2	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	9.5	Qntl
i)	<b>BRM341</b> : Steel	1.05	9.975	1 Qntl.
3	<b>Plastering (AR1017) :.20mm thick cement Plaster in CM (1:4) over masonry work in inside. -</b> 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	40.8	Sqm
i)	<b>BRM340</b> : Cement	0.0744	3.03552	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	0.8568	1 Cum

4	<p><b>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth</b>  - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	15.9201	Cum
i)	<p><b>BRM006</b> : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm<sup>2</sup> with dimensional tolerance ± 2 %</p>	400	6368.04	1000 Nos
ii)	<p><b>BRM340</b> : Cement</p>	0.672	10.6983072	1 Qntl.
iii)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.28	4.457628	1 Cum
5	<p><b>R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	-	30.3475	Sqm
i)	<p><b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.</p>	0.0056666666666667	0.17196916666667	1Mtr

ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.15751797619048	1Cum.
6	<b>R.C.C. Work (AR0410e) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	<b>8.004</b>	Sqm
i)	<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.0035384615384615	0.028321846153846	1Mtr.
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.042380153846154	1Cum.
7	<b>R.C.C. Work (AR0410a) :.Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	<b>50.206</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0076666666666667	0.384912666666667	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.252145688888889	1Cum.

8	<b>Plastering (AR1014)</b> <b>::16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	<b>81.9</b>	Sqm
i)	<b>BRM340</b> : Cement	0.043	3.5217	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	1.4742	1 Cum
9	<b>Plastering (AR1004)</b> <b>::12mm thick cement plaster (1:6) over Brick work in inside</b> - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	<b>86.96</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0358	3.113168	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	1.3044	1 Cum

10	<p><b>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory -</b>  Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	<b>82.3075</b>	Sqm
i)	<b>BRM174</b> : White Cement.	0.0076	0.625537	1Qntl
ii)	<b>BRM340</b> : Cement	0.1074	8.8398255	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	1.7284575	1 Cum
iv)	<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	82.3075	1 Sqm.

11	<p><b>Flooring (AR0817aa)</b>  <b>:.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>  Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	10.41	Sqm
i)	<p><b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	10.41	1 Sqm.
ii)	<p><b>BRM340</b> : Cement</p>	0.1375	1.431375	1 Qntl.
iii)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.015	0.15615	1 Cum
12	<p><b>Iron Work(AR1704)</b>  <b>:.Iron Doors and windows fixing -</b>  Supplying, fitting &amp; fixing of Mild steel and put up for frames &amp; shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T &amp; P required for the work etc. as per direction of Engineer-in-charge.</p>	-	0.07065	Qntl
i)	<p><b>BRM341</b> : Steel</p>	1	0.07065	1 Qntl.

13	<b>miscellaneous(ARM105) :.Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.</b> - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.	-	<b>7.065</b>	Sqm
14	<b>Painting(AR0901b) :.Priming one coat in inner surface with primer of approved quality over iron work.</b> - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	<b>42.705</b>	Sqm
i)	<b>BRM137 : Red oxide Primer</b>	0.054	2.30607	1 Litre
15	<b>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)</b> - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	<b>47.85</b>	Sqm
i)	<b>BRM340 : Cement</b>	0.0372	1.78002	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.0075	0.358875	1 Cum

16	<p><b>Other Building Items. (AR1902) :.cement based wall putty (water based) -</b>  Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&amp;P,etc.complete. and as per the direction of Engineer in Charge.</p>	-	129.75	Sqm
17	<p><b>Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b>  Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	129.75	Sqm
i)	<b>BRM140</b> : Plastic Emulsion paint	0.125	16.21875	1 Litre
18	<p><b>Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) -</b>  Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	187.1125	Sqm
i)	<b>BRM142</b> : Distemper	0.25	46.778125	1 Kg.

19	<b>Painting(AR0917g)</b> :.Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work <b>(Outside)</b> - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	<b>192.4455</b>	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.075	14.4334125	1 Ltr
ii)	<b>BRM252</b> : Wall cement primer (I.S.I.) Oil bound	0.084	16.165422	1 Ltr

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM028</b>	14.375148	1 Cum	40.25	578.599707
2	<b>BRM060</b>	3.23091	1 Cum.	149.5	483.021045
3	<b>BRM052</b>	4.846365	1 Cum.	149.5	724.5315675
4	<b>BRM006</b>	6368.04	1000 Nos	0.04025	256.31361
<b>Total:</b>					<b>2042.4659295</b>

#### ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for PH Work @ Rs. 10000	Rs. 10000
2	Provision for Contingency @ 1%	Rs. 5286.9047690212
3	Display Citizen Board @ Rs. 3000	Rs. 3000
4	Any Other Lumpsum @ Rs. 21022	Rs. 21022

Total Addition Component Amount (in Rs.): 39308.904769021

Total Net Amount (in Rs.): 567999.38167115