

| ESTIMATION DPR | | | | | | | |
|----------------|--------|-----------------|--------|--------------|-------------|-----------------------|----------|
| State | Odisha | District | Ganjam | Block | Bhanjanagar | Gram Panchayat | Lalsingi |

| | | | | | | | |
|-------------------------|--|--|--|--|--|--|--|
| Work Code | OD/354/3367/117649/410674/00050483 (OPEN SPACE DEVELOPMENT WITH OPEN YOGA CENTRE AT LANDAISAH) | | | | | | |
| Project Category | Other Infrastructure | | | | | | |

| | | | |
|-----------------------------|------------------------------------|------------------------------|-----------------------|
| Financial Year | 2022-23 | Execution Level | PS |
| Executing Agency | Panchayat Samiti, Bhanjanagar | Proposal Date | 22-12-2023 |
| Date of Commencement | 31-10-2025 | Date of Completion | - |
| Scheme Name | Infrastructure Development Fund | Scheme Component Name | Self/Personal Deposit |
| Project Sub-Category | Rural Park | Project Type | New Work |
| Name of Executant | MADHU BEHERA | | |

Administrative Approval Details

| | |
|---------------------|---------------------------------------|
| Approval No. | OD/354/3367/117649/410674/00050483/AS |
|---------------------|---------------------------------------|

Technical Sanction Details

| | |
|--------------------------------------|---------------------------------------|
| Technical Sanction No. | OD/354/3367/117649/410674/00050483/TS |
| Fund Sanction No. | 16355 |
| Fund Sanction Amount (in Rs.) | 1000000 |

ACTIVITY STATEMENT

| S/N | ACTIVITY TAKEN | UNIT | QUANTITY | UNIT PRICE (IN RS.) | TOTAL (IN RS.) |
|-----|----------------|------|----------|---------------------|----------------|
|-----|----------------|------|----------|---------------------|----------------|

| | | | | | |
|---|--|-----|----------|------------|-----------------|
| 1 | <p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p> | Cum | 19.27125 | 240.77592 | 141777.97481134 |
| 2 | <p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p> | Cum | 20.77407 | 630.485632 | 141777.97481134 |

| | | | | | |
|---|---|-----|---------|----------------|-----------------|
| 3 | <p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p> | Cum | 5.48422 | 5540.86445006 | 141777.97481134 |
| 4 | <p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p> | Sqm | 13.7598 | 191.3725184908 | 141777.97481134 |

| | | | | | |
|---|--|-----|--------|----------------|-----------------|
| 5 | <p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p> | Sqm | 35.148 | 171.2996320812 | 141777.97481134 |
| 6 | <p>Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p> | Sqm | 3.291 | 1534.518708136 | 141777.97481134 |

| | | | | | |
|---|---|-----|-----------|-----------------|-----------------|
| 7 | <p>R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p> | Cum | 12.929197 | 5845.4636362062 | 141777.97481134 |
|---|---|-----|-----------|-----------------|-----------------|

| | | | | | |
|---|---|-----|---------|----------------|-----------------|
| 8 | <p>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p> | Cum | 5.63091 | 5048.667184608 | 141777.97481134 |
|---|---|-----|---------|----------------|-----------------|

| | | | | | |
|----|---|-----|----------|-----------------|-----------------|
| 9 | <p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p> | Cum | 5.520636 | 5081.997184608 | 141777.97481134 |
| 10 | <p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p> | Sqm | 29.8372 | 1010.9520347466 | 141777.97481134 |

| | | | | | |
|----|--|-----|---------|----------------|-----------------|
| 11 | <p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p> | Sqm | 98.3372 | 71.83248932951 | 141777.97481134 |
| 12 | <p>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p> | Sqm | 63.1872 | 94.7526285875 | 141777.97481134 |

| | | | | | |
|----|--|-----|--------|-----------------|-----------------|
| 13 | <p>Painting (AR0901ci) : Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p> | Sqm | 35.15 | 68.98780412951 | 141777.97481134 |
| 14 | <p>Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p> | Sqm | 68.229 | 164.22772665202 | 141777.97481134 |

| | | | | | |
|----|--|-----|---------|-----------------|-----------------|
| 15 | <p>Plastering (AR1014i) : 16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p> | Sqm | 33.3488 | 243.376681312 | 141777.97481134 |
| 16 | <p>Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p> | Sqm | 35.15 | 156.85349521701 | 141777.97481134 |

| | | | | | |
|---|--|------|-----------|-----------------|-----------------|
| 17 | Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge. | Qntl | 8.6887512 | 16317.416801087 | 141777.97481134 |
| Total Amount (in Rs.): 406143.55893591 | | | | | |

LABOUR STATEMENT

| SI.No. | Activity Name | Qty/unit(B=Analysis Basic Qty/HeaderUnit) | Quantity(Measurement Qty) | Unit |
|--------|--|---|---------------------------|------|
| 1 | Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | - | 19.27125 | Cum |
| i | Un-Skilled | 0.516 | 9.943965 | - |

| | | | | |
|----|--|--------|-------------|-----|
| 2 | Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | - | 20.77407 | Cum |
| i | Un-Skilled | 0.1236 | 2.567675052 | - |
| 3 | Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. | - | 5.48422 | Cum |
| i | Skilled | 0.18 | 0.9871596 | - |
| ii | Un-Skilled | 3.9 | 21.388458 | - |

| | | | | |
|----|--|------|----------|-----|
| 4 | <p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p> | - | 13.7598 | Sqm |
| i | Un-Skilled | 0.17 | 2.339166 | - |
| ii | Skilled | 0.14 | 1.926372 | - |
| 5 | <p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p> | - | 35.148 | Sqm |
| i | Un-Skilled | 0.12 | 4.21776 | - |
| ii | Skilled | 0.14 | 4.92072 | - |

| | | | | |
|-----|---|-------|----------|-----|
| 6 | Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles. | - | 3.291 | Sqm |
| i | Highly-Skilled | 0.325 | 1.069575 | - |
| ii | Un-Skilled | 0.325 | 1.069575 | - |
| iii | Semi-Skilled | 0.76 | 2.50116 | - |

| | | | | |
|-----|--|--------|---------------|-----|
| 7 | R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering) | - | 12.929197 | Cum |
| i | Un-Skilled | 1.3333 | 17.2384983601 | - |
| ii | Skilled | 0.1 | 1.2929197 | - |
| iii | Semi-Skilled | 0.0573 | 0.7408429881 | - |

| | | | | |
|-----|--|------|------------|-----|
| 8 | Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge. | - | 5.63091 | Cum |
| i | Un-Skilled | 2.96 | 16.6674936 | - |
| ii | Skilled | 1.05 | 5.9124555 | - |
| iii | Highly-Skilled | 0.35 | 1.9708185 | - |

| | | | | |
|-----|---|------|-------------|-----|
| 9 | Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge. | - | 5.520636 | Cum |
| i | Un-Skilled | 2.96 | 16.34108256 | - |
| ii | Skilled | 1.05 | 5.7966678 | - |
| iii | Highly-Skilled | 0.35 | 1.9322226 | - |

| | | | | |
|----|--|-------------------|-----------------|-----|
| 10 | <p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p> | - | 29.8372 | Sqm |
| i | Un-Skilled | 0.216 | 6.4448352 | - |
| ii | Highly-Skilled | 0.216 | 6.4448352 | - |
| 11 | <p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p> | - | 98.3372 | Sqm |
| i | Highly-Skilled | 0.053763440860215 | 5.2869462365591 | - |
| ii | Un-Skilled | 0.053763440860215 | 5.2869462365591 | - |

| | | | | |
|----|---|-------------------|-----------------|-----|
| 12 | <p>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p> | - | 63.1872 | Sqm |
| i | Highly-Skilled | 0.054 | 3.4121088 | - |
| ii | Un-Skilled | 0.064 | 4.0439808 | - |
| 13 | <p>Painting (AR0901ci) : Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p> | - | 35.15 | Sqm |
| i | Highly-Skilled | 0.053763440860215 | 1.8897849462366 | - |
| ii | Un-Skilled | 0.053763440860215 | 1.8897849462366 | - |

| | | | | |
|----|---|------------------|-----------------|-----|
| 14 | Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside) | - | 68.229 | Sqm |
| i | Highly-Skilled | 0.13440860215054 | 9.170564516129 | - |
| ii | Un-Skilled | 0.11827956989247 | 8.0700967741935 | - |
| 15 | Plastering (AR1014i) : 16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge. | - | 33.3488 | Sqm |
| i | Un-Skilled | 0.24 | 8.003712 | - |
| ii | Skilled | 0.16 | 5.335808 | - |

| | | | | |
|----|--|------------------|-----------------|------|
| 16 | Painting (AR0918ca) : Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside) | - | 35.15 | Sqm |
| | i Un-Skilled | 0.11776344086022 | 4.1393849462366 | - |
| | ii Highly-Skilled | 0.10776344086022 | 3.7878849462366 | - |
| 17 | Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge. | - | 8.6887512 | Qntl |
| | i Un-Skilled | 6.3976377952756 | 55.587483070866 | - |
| | ii Semi-Skilled | 1.9685039370079 | 17.103840944882 | - |
| | iii Skilled | 3.9370078740157 | 34.207681889764 | - |
| | iv Highly-Skilled | 3.4448818897638 | 29.931721653543 | - |

| SI.No. | Labour Type | Qty Unit | Rate | Amount |
|---------------|----------------|-----------------|------|------------------------|
| 0 | Un-Skilled | 185.23989754619 | 462 | 85580.832666341 |
| 1 | Skilled | 60.379784489764 | 562 | 33933.438883247 |
| 2 | Highly-Skilled | 64.896462398705 | 612 | 39716.634988007 |
| 3 | Semi-Skilled | 20.345843932982 | 512 | 10417.072093687 |
| Total: | | | | 169647.97863128 |

MATERIAL STATEMENT

| SI.No. | Activity Name/Material | Qty/unit (B=Analysis Basic Qty/Header Unit) | Quantity (Meaurement Qty) | Unit |
|--------|---|---|---------------------------|-------|
| 1 | Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | - | 19.27125 | Cum |
| 2 | Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | - | 20.77407 | Cum |
| i) | BRM029 : Sand for filling and road blinding | 1 | 20.77407 | 1 Cum |

| | | | | |
|------|---|--------|------------|---------|
| 3 | <p>Concrete (AR0303) :Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p> | - | 5.48422 | Cum |
| i) | BRM340 : Cement | 2.29 | 12.5588638 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.48 | 2.6324256 | 1 Cum |
| iii) | BRM044 : Granite Stone broken metal 40mm. size (Crusher broken) | 0.96 | 5.2648512 | 1 Cum. |
| 4 | <p>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p> | - | 13.7598 | Sqm |
| i) | BRM340 : Cement | 0.0372 | 0.51186456 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.0075 | 0.1031985 | 1 Cum |

| | | | | |
|-----|---|--------|-----------|---------|
| 5 | Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge. | - | 35.148 | Sqm |
| i) | BRM340 : Cement | 0.0358 | 1.2582984 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.015 | 0.52722 | 1 Cum |
| 6 | Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles. | - | 3.291 | Sqm |
| i) | BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory) | 1 | 3.291 | 1 Sqm. |
| ii) | BRMMR0027 : Wax Polish | 1 | 3.291 | 1 Sqm |

| | | | | |
|------|---|--------|------------------|---------|
| iii) | BRM340 : Cement | 0.1375 | 0.4525125 | 1 Qntl. |
| iv) | BRM028 : Screened and washed sharp sand for mortar | 0.015 | 0.049365 | 1 Cum |
| 7 | <p>R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p> | - | 12.929197 | Cum |
| i) | BRM340 : Cement | 3.4733 | 44.9069799401 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.45 | 5.81813865 | 1 Cum |
| iii) | BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken) | 0.36 | 4.65451092 | 1 Cum. |
| iv) | BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken) | 0.54 | 6.98176638 | 1 Cum. |

| | | | | |
|------|--|-------|------------|----------|
| 8 | <p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p> | - | 5.63091 | Cum |
| i) | <p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p> | 400 | 2252.364 | 1000 Nos |
| ii) | <p>BRM340 : Cement</p> | 0.672 | 3.78397152 | 1 Qntl. |
| iii) | <p>BRM028 : Screened and washed sharp sand for mortar</p> | 0.28 | 1.5766548 | 1 Cum |
| 9 | <p>Masonry Brick Work (AR0603ci) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p> | - | 5.520636 | Cum |

| | | | | |
|------|--|--------|----------------|----------|
| i) | BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK | 1 | 5.520636 | 1 Cum |
| ii) | BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 % | 400 | 2208.2544 | 1000 Nos |
| iii) | BRM340 : Cement | 0.672 | 3.709867392 | 1 Qntl. |
| iv) | BRM028 : Screened and washed sharp sand for mortar | 0.28 | 1.54577808 | 1 Cum |
| 10 | Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only) | - | 29.8372 | Sqm |
| i) | BRM174 : White Cement. | 0.0076 | 0.22676272 | 1Qntl |
| ii) | BRM340 : Cement | 0.1074 | 3.20451528 | 1 Qntl. |
| iii) | BRM028 : Screened and washed sharp sand for mortar | 0.021 | 0.6265812 | 1 Cum |
| iv) | BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory) | 1 | 29.8372 | 1 Sqm. |

| | | | | |
|----|---|-------|-----------|---------|
| 11 | Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge. | - | 98.3372 | Sqm |
| i) | BRM253 : Wall cement primer (I.S.I.) Water bound | 0.084 | 8.2603248 | 1 Ltr |
| 12 | Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside) | - | 63.1872 | Sqm |
| i) | BRM140 : Plastic Emulsion paint | 0.125 | 7.8984 | 1 Litre |
| 13 | Painting(AR0901ci) :.Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge. | - | 35.15 | Sqm |

| | | | | |
|-----|---|-------|-----------|---------|
| i) | BRM252 : Wall cement primer (I.S.I.) Oil bound | 0.084 | 2.9526 | 1 Ltr |
| 14 | Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside) | - | 68.229 | Sqm |
| i) | BRM141 : Enamel paint | 0.125 | 8.528625 | 1 Litre |
| 15 | Plastering (AR1014i) :.16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge. | - | 33.3488 | Sqm |
| i) | BRM340 : Cement | 0.043 | 1.4339984 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.018 | 0.6002784 | 1 Cum |
| 16 | Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside) | - | 35.15 | Sqm |

| | | | | |
|-----|--|-------|------------------|---------|
| i) | BRM255 : Weather Coat (I.S.I.) | 0.125 | 4.39375 | 1 Ltr |
| ii) | BRM252 : Wall cement primer (I.S.I.) Oil bound | 0.084 | 2.9526 | 1 Ltr |
| 17 | Iron Work(AR1704) .:Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge. | - | 8.6887512 | Qntl |
| i) | BRM341 : Steel | 1 | 8.6887512 | 1 Qntl. |

| Sl.No. | Material Name | Qty | Unit | Rate | Amount |
|---------------|------------------|---------------|----------|-------------|------------------------|
| 1 | BRM029 | 20.77407 | 1 Cum | 351.89 | 7310.1874923 |
| 2 | BRM340 | 71.8208717921 | 1 Qntl. | 593.017 | 42590.997927536 |
| 3 | BRM028 | 13.47964023 | 1 Cum | 355.26 | 4788.7769881098 |
| 4 | BRM044 | 5.2648512 | 1 Cum. | 1401.46 | 7378.478362752 |
| 5 | BRM131 | 33.1282 | 1 Sqm. | 660.6811111 | 21887.175984743 |
| 6 | BRMMR0027 | 3.291 | 1 Sqm | 8.5 | 27.9735 |
| 7 | BRM060 | 4.65451092 | 1 Cum. | 1813.98 | 8443.1897186616 |
| 8 | BRM052 | 6.98176638 | 1 Cum. | 1788.5 | 12486.88917063 |
| 9 | BRM006 | 4460.6184 | 1000 Nos | 5.36398 | 23926.667885232 |
| 10 | BRMMR0025 | 5.520636 | 1 Cum | 33 | 182.180988 |
| 11 | BRM174 | 0.22676272 | 1Qntl | 2041.967 | 463.04199107024 |
| 12 | BRM253 | 8.2603248 | 1 Ltr | 159.27787 | 1315.6869396522 |
| 13 | BRM140 | 7.8984 | 1 Litre | 249.58787 | 1971.344832408 |
| 14 | BRM252 | 5.9052 | 1 Ltr | 125.74787 | 742.566321924 |
| 15 | BRM141 | 8.528625 | 1 Litre | 205.58787 | 1753.3818477788 |
| 16 | BRM255 | 4.39375 | 1 Ltr | 195.03787 | 856.9476413125 |
| 17 | BRM341 | 8.6887512 | 1 Qntl. | 6674.467 | 57992.78315561 |
| Total: | | | | | 194118.27074772 |

ROYALTY STATEMENT

| Sl.No. | Activity Name/Material | Qty/unit (B=Analysis Basic Qty/Header Unit) | Quantity (Meaurement Qty) | Unit |
|--------|---|---|---------------------------|---------|
| 1 | Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | - | 19.27125 | Cum |
| 2 | Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | - | 20.77407 | Cum |
| i) | BRM029 : Sand for filling and road blinding | 1 | 20.77407 | 1 Cum |
| 3 | Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. | - | 5.48422 | Cum |
| i) | BRM340 : Cement | 2.29 | 12.5588638 | 1 Qntl. |

| | | | | |
|------|--|--------|----------------|---------|
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.48 | 2.6324256 | 1 Cum |
| iii) | BRM044 : Granite Stone broken metal 40mm. size (Crusher broken) | 0.96 | 5.2648512 | 1 Cum. |
| 4 | Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge. | - | 13.7598 | Sqm |
| i) | BRM340 : Cement | 0.0372 | 0.51186456 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.0075 | 0.1031985 | 1 Cum |
| 5 | Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge. | - | 35.148 | Sqm |
| i) | BRM340 : Cement | 0.0358 | 1.2582984 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.015 | 0.52722 | 1 Cum |

| | | | | |
|------|--|--------|-----------|---------|
| 6 | <p>Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p> | - | 3.291 | Sqm |
| i) | <p>BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p> | 1 | 3.291 | 1 Sqm. |
| ii) | <p>BRM340 : Cement</p> | 0.1375 | 0.4525125 | 1 Qntl. |
| iii) | <p>BRM028 : Screened and washed sharp sand for mortar</p> | 0.015 | 0.049365 | 1 Cum |

| | | | | |
|------|--|--------|------------------|---------|
| 7 | R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering) | - | 12.929197 | Cum |
| i) | BRM340 : Cement | 3.4733 | 44.9069799401 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.45 | 5.81813865 | 1 Cum |
| iii) | BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken) | 0.36 | 4.65451092 | 1 Cum. |
| iv) | BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken) | 0.54 | 6.98176638 | 1 Cum. |

| | | | | |
|------|---|-------|------------|----------|
| 8 | <p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p> | - | 5.63091 | Cum |
| i) | <p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %</p> | 400 | 2252.364 | 1000 Nos |
| ii) | <p>BRM340 : Cement</p> | 0.672 | 3.78397152 | 1 Qntl. |
| iii) | <p>BRM028 : Screened and washed sharp sand for mortar</p> | 0.28 | 1.5766548 | 1 Cum |
| 9 | <p>Masonry Brick Work (AR0603ci) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p> | - | 5.520636 | Cum |

| | | | | |
|------|--|--------|----------------|----------|
| i) | BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance \pm 2 % | 400 | 2208.2544 | 1000 Nos |
| ii) | BRM340 : Cement | 0.672 | 3.709867392 | 1 Qntl. |
| iii) | BRM028 : Screened and washed sharp sand for mortar | 0.28 | 1.54577808 | 1 Cum |
| 10 | Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only) | - | 29.8372 | Sqm |
| i) | BRM174 : White Cement. | 0.0076 | 0.22676272 | 1Qntl |
| ii) | BRM340 : Cement | 0.1074 | 3.20451528 | 1 Qntl. |
| iii) | BRM028 : Screened and washed sharp sand for mortar | 0.021 | 0.6265812 | 1 Cum |
| iv) | BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory) | 1 | 29.8372 | 1 Sqm. |

| | | | | |
|----|---|-------|-----------|---------|
| 11 | Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge. | - | 98.3372 | Sqm |
| i) | BRM253 : Wall cement primer (I.S.I.) Water bound | 0.084 | 8.2603248 | 1 Ltr |
| 12 | Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside) | - | 63.1872 | Sqm |
| i) | BRM140 : Plastic Emulsion paint | 0.125 | 7.8984 | 1 Litre |
| 13 | Painting(AR0901ci) :.Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge. | - | 35.15 | Sqm |

| | | | | |
|-----|---|-------|-----------|---------|
| i) | BRM252 : Wall cement primer (I.S.I.) Oil bound | 0.084 | 2.9526 | 1 Ltr |
| 14 | Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside) | - | 68.229 | Sqm |
| i) | BRM141 : Enamel paint | 0.125 | 8.528625 | 1 Litre |
| 15 | Plastering (AR1014i) :.16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge. | - | 33.3488 | Sqm |
| i) | BRM340 : Cement | 0.043 | 1.4339984 | 1 Qntl. |
| ii) | BRM028 : Screened and washed sharp sand for mortar | 0.018 | 0.6002784 | 1 Cum |
| 16 | Painting(AR0918ca) :.Finishing wall two coats with weather coat with one coat oilbound Primer - Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside) | - | 35.15 | Sqm |

| | | | | |
|-----|---|-------|------------------|---------|
| i) | BRM255 : Weather Coat (I.S.I.) | 0.125 | 4.39375 | 1 Ltr |
| ii) | BRM252 : Wall cement primer (I.S.I.) Oil bound | 0.084 | 2.9526 | 1 Ltr |
| 17 | Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge. | - | 8.6887512 | Qntl |
| i) | BRM341 : Steel | 1 | 8.6887512 | 1 Qntl. |

| S/N | Material Name | Qty | Unit | Royalty Rate | Amount |
|-------------------------------|---------------|-------------|----------|--------------|-----------------|
| 1 | BRM029 | 20.77407 | 1 Cum | 215.25 | 4471.6185675 |
| 2 | BRM028 | 13.47964023 | 1 Cum | 215.25 | 2901.4925595075 |
| 3 | BRM044 | 5.2648512 | 1 Cum. | 251.5 | 1324.1100768 |
| 4 | BRM060 | 4.65451092 | 1 Cum. | 251.5 | 1170.60949638 |
| 5 | BRM052 | 6.98176638 | 1 Cum. | 251.5 | 1755.91424457 |
| 6 | BRM006 | 4460.6184 | 1000 Nos | 0.04025 | 179.5398906 |
| Total: 11803.284835357 | | | | | |

ADDITION COMPONENT

| SI.No. | Item Name | Amount (in Rs.) |
|---|--|-----------------|
| 1 | Provision for EI Work @ Rs. 6000 | Rs. 6000 |
| 2 | Provision for Contingency @ Rs. 10000 | Rs. 10000 |
| 3 | Display Citizen Board @ Rs. 5000 | Rs. 5000 |
| 4 | Any Other Lumpsum @ Rs. 572856 | Rs. 572856 |
| Total Addition Component Amount (in Rs.): 593856 | | |

Total Net Amount (in Rs.): 999999.55893591