

ESTIMATION DPR

State	Odisha	District	Cuttack	Block	Cuttacksadar	Gram Panchayat	Jharkata
--------------	--------	-----------------	---------	--------------	--------------	-----------------------	----------

Work Code	OD/350/3337/275413/400054/00065505 (IMPROVEMENT OF ROAD FROM JHINKIRIA CHANDULI MAIN ROAD TO GOBINDAPUR VILLAGE ROAD)
Project Category	Road

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Cuttacksadar	Proposal Date	-
Date of Commencement	25-11-2025	Date of Completion	05-12-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	SAMAPEEKA NAYAK		

Administrative Approval Details

Approval No.	OD/350/3337/275413/400054/00065505/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/350/3337/275413/400054/00065505/TS
Fund Sanction No.	19514
Fund Sanction Amount (in Rs.)	200000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	2.6654320672	240.77592	95344.295436693
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	12.666977930112	588.227232	95344.295436693

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	15.348402589715	6060.21693386	95344.295436693
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	12.671201664	7524.48725582	95344.295436693
Total Amount (in Rs.): 196451.7779424					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	2.6654320672	Cum
i	Un-Skilled	0.516	1.3753629466752	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	12.666977930112	Cum
i	Un-Skilled	0.1236	1.5656384721618	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	15.348402589715	Cum
	i Skilled	0.18	2.7627124661487	-
	ii Un-Skilled	3.9	59.858770099889	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	12.671201664	Cum
	i Un-Skilled	4.6	58.2875276544	-

ii	Skilled	0.68	8.61641713152	-
----	---------	------	---------------	---

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	121.08729917313	462	55942.332217984
1	Skilled	11.379129597669	562	6395.0708338898
Total: 62337.403051874				

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.6654320672	Cum
2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.666977930112	Cum
i)	BRM029 : Sand for filling and road blinding	1	12.666977930112	1 Cum

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	15.348402589715	Cum
i)	BRM340 : Cement	2.29	35.147841930447	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.3672332430632	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	14.734466486126	1 Cum.
4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	12.671201664	Cum
i)	BRM340 : Cement	3.23	40.92798137472	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.7020407488	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	11.4040814976	1 Cum.
------	--	-----	---------------	--------

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	12.666977930112	1 Cum	413.05	5232.0952340328
2	BRM340	76.075823305167	1 Qntl.	563.767	42889.038677284
3	BRM028	13.069273991863	1 Cum	417.99	5462.8258358589
4	BRM044	14.734466486126	1 Cum.	2167.11	31931.209666749
5	BRM056	11.4040814976	1 Cum.	2595.71	29601.688384135
Total: 115116.85779806					

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.6654320672	Cum
2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.666977930112	Cum

i)	BRM029 : Sand for filling and road blinding	1	12.666977930112	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.348402589715	Cum
i)	BRM340 : Cement	2.29	35.147841930447	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.3672332430632	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	14.734466486126	1 Cum.
4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	12.671201664	Cum
i)	BRM340 : Cement	3.23	40.92798137472	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	5.7020407488	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	11.4040814976	1 Cum.
------	--	-----	---------------	--------

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	12.666977930112	1 Cum	112.25	1421.8682726551
2	BRM028	13.069273991863	1 Cum	112.25	1467.0260055866
3	BRM044	14.734466486126	1 Cum.	259.5	3823.5940531498
4	BRM056	11.4040814976	1 Cum.	259.5	2959.3591486272
Total: 9671.8474800187					

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 2000	Rs. 2000
2	Display Citizen Board @ Rs. 1500	Rs. 1500
Total Addition Component Amount (in Rs.): 3500		

Total Net Amount (in Rs.): 199951.7779424