

ESTIMATION DPR							
State	Odisha	District	Dhenkanal	Block	Bhuban	Gram Panchayat	Arakhapal

Work Code	OD/352/3349/117238/402422/00068493 (Construction of Community Centre at Khurusia Village.)						
Project Category	Building						

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhuban	Proposal Date	-
Date of Commencement	11-12-2025	Date of Completion	08-01-2026
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO ZILLA PARISHAD
Project Sub-Category	Community Centre	Project Type	New Work
Name of Executant	Binati Sahu		

Administrative Approval Details

Approval No.	OD/352/3349/117238/402422/00068493/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/352/3349/117238/402422/00068493/TS
Fund Sanction No.	185
Fund Sanction Amount (in Rs.)	210721

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p>R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)</p>	Cum	0.549375	13421.98431959	20236.639227635
---	---	-----	----------	----------------	-----------------

2	<p>R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips -</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	Cum	1.1225	14813.45347838	20236.639227635
---	---	-----	--------	----------------	-----------------

3	<p>R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	Cum	3.8659375	13059.58449545	20236.639227635
---	--	-----	-----------	----------------	-----------------

4	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	Qntl	5.9	8175.9788355	20236.639227635
---	---	------	-----	--------------	-----------------

5	<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	5.68125	5203.452298488	20236.639227635
6	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	64.265	247.899891572	20236.639227635

7	<p>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	Sqm	19.1625	376.3617684632	20236.639227635
8	<p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	Sqm	83.43	71.84762054351	20236.639227635

9	Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	Sqm	83.43	78.88055055	20236.639227635
10	Iron Work (AR1702) : Iron work wrought and put up in window grating including drilling holes in choukathas - Iron work wrought and put up in window grating including drilling holes in choukathas including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	Qntl	2.3088	8765.0031304724	20236.639227635
Total Amount (in Rs.): 208244.93956269					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.549375	Cum
i	Un-Skilled	1.3333	0.7324816875	-
ii	Skilled	2.34375	1.28759765625	-
iii	Semi-Skilled	2.30105	1.26413934375	-

2	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	1.1225	Cum
i	Un-Skilled	1.3333	1.49662925	-
ii	Skilled	5.33875	5.992746875	-
iii	Semi-Skilled	5.29605	5.944816125	-

3	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	3.8659375	Cum
i	Un-Skilled	1.3333	5.15445446875	-
ii	Skilled	3.15525	12.197999296875	-
iii	Semi-Skilled	3.11255	12.032923765625	-

4	R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	5.9	Qntl
i	Un-Skilled	0.8	4.72	-
ii	Highly-Skilled	0.3	1.77	-
iii	Semi-Skilled	0.044	0.2596	-

5	<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	5.68125	Cum
i	Un-Skilled	2.96	16.8165	-
ii	Skilled	1.05	5.9653125	-
iii	Highly-Skilled	0.35	1.9884375	-
6	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	64.265	Sqm

	i	Un-Skilled	0.24	15.4236	-
	ii	Skilled	0.16	10.2824	-
7		Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	19.1625	Sqm
	i	Un-Skilled	0.36	6.8985	-
	ii	Highly-Skilled	0.13	2.491125	-
8		Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	83.43	Sqm
	i	Highly-Skilled	0.053763440860215	4.4854838709677	-
	ii	Un-Skilled	0.053763440860215	4.4854838709677	-

9	Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	83.43	Sqm
i	Highly-Skilled	0.052	4.33836	-
ii	Un-Skilled	0.062	5.17266	-
10	Iron Work (AR1702) : Iron work wrought and put up in window grating including drilling holes in choukathas - Iron work wrought and put up in window grating including drilling holes in choukathas including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	2.3088	Qntl
i	Semi-Skilled	1.4763779527559	3.4086614173228	-
ii	Skilled	1.4763779527559	3.4086614173228	-
SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	60.900309277218	462	28135.942886075

1	Skilled	39.134717745448	562	21993.711372942
2	Semi-Skilled	22.910140651698	512	11729.992013669
3	Highly-Skilled	15.073406370968	612	9224.9246990323
				Total: 71084.570971718

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>R.C.C. Work (AR0404Ad) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)</p>	-	0.549375	Cum
i)	BRM340 : Cement	3.4733	1.9081441875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.24721875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.197775	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.2966625	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	2.0708690625	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.0407270915625	1Cum.
2	R.C.C. Work (AR0404Ac) :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	1.1225	Cum
i)	BRM340 : Cement	3.4733	3.89877925	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.505125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.4041	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.60615	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	4.961001	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.0466163025	1Cum.
3	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	3.8659375	Cum
i)	BRM340 : Cement	3.4733	13.42756071875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.739671875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.3917375	1 Cum.

iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.08760625	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	24.05231675	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.194136556625	1Cum.
4	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	5.9	Qntl
i)	BRM162 : Binding Wire.	0.8	4.72	1 Kg.
ii)	BRM341 : Steel	1.05	6.195	1 Qntl.

5	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	5.68125	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	5.68125	1 Cum
ii)	BRM340 : Cement	0.672	3.8178	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.59075	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1988.4375	1000 Nos
6	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	64.265	Sqm
i)	BRM340 : Cement	0.043	2.763395	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.15677	1 Cum
7	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	19.1625	Sqm
i)	BRM340 : Cement	0.0858	1.6441425	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.22995	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	0.4407375	1 Cum.
8	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	83.43	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	7.00812	1 Ltr

9	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	83.43	Sqm
i)	BRM142 : Distemper	0.25	20.8575	1 Kg.
10	Iron Work(AR1702) :.Iron work wrought and put up in window grating including drilling holes in choukathas - Iron work wrought and put up in window grating including drilling holes in choukathas including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	2.3088	Qntl
i)	BRM341 : Steel	1	2.3088	1 Qntl.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	27.45982165625	1 Qntl.	581.502	15967.941212753
2	BRM028	5.469485625	1 Cum	548.19	2998.3173247687
3	BRM060	1.9936125	1 Cum.	2401.91	4788.477799875
4	BRM052	2.99041875	1 Cum.	2382.2	7123.77554625
5	BRM094	2.0708690625	1Mtr.	240.106	497.22808712062
6	BRM104	0.2814799506875	1Cum.	58573.086	16487.149358895
7	BRM084	29.01331775	1Mtr	250.166	7258.1456482465
8	BRM162	4.72	1 Kg.	90.1	425.272
9	BRM341	8.5038	1 Qntl.	6017.172	51168.8272536
10	BRMMR0025	5.68125	1 Cum	33	187.48125
11	BRM005	1988.4375	1000 Nos	6.43005	12785.752546875
12	BRM057	0.4407375	1 Cum.	2085.1	918.98176125
13	BRM253	7.00812	1 Ltr	159.45622	1117.4883245064
14	BRM142	20.8575	1 Kg.	70.52622	1471.00063365

ROYALTY STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	R.C.C. Work (AR0404Ad) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	0.549375	Cum
i)	BRM340 : Cement	3.4733	1.9081441875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.24721875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.197775	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.2966625	1 Cum.
v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	0.02721713625	1Mtr.

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.0407270915625	1Cum.
2	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	1.1225	Cum
i)	BRM340 : Cement	3.4733	3.89877925	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.505125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.4041	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.60615	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	0.0508930275	1Mtr

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.0466163025	1Cum.
3	R.C.C. Work (AR0404Ag) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	3.8659375	Cum
i)	BRM340 : Cement	3.4733	13.42756071875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.739671875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.3917375	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.08760625	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	0.2963589028125	1Mtr

vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.194136556625	1Cum.
4	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	5.9	Qntl
i)	BRM341 : Steel	1.05	6.195	1 Qntl.
5	Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	5.68125	Cum
i)	BRM340 : Cement	0.672	3.8178	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.59075	1 Cum

iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance \pm 2 %	350	1988.4375	1000 Nos
6	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	64.265	Sqm
i)	BRM340 : Cement	0.043	2.763395	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	1.15677	1 Cum
7	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	19.1625	Sqm
i)	BRM340 : Cement	0.0858	1.6441425	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.22995	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	0.4407375	1 Cum.

8	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	83.43	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	7.00812	1 Ltr
9	Painting(AR0922) :.Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	83.43	Sqm
i)	BRM142 : Distemper	0.25	20.8575	1 Kg.
10	Iron Work(AR1702) :.Iron work wrought and put up in window grating including drilling holes in choukathas - Iron work wrought and put up in window grating including drilling holes in choukathas including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	2.3088	Qntl
i)	BRM341 : Steel	1	2.3088	1 Qntl.

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	5.469485625	1 Cum	311.25	1702.3774007812

2	BRM060	1.9936125	1 Cum.	446.5	890.14798125
3	BRM052	2.99041875	1 Cum.	446.5	1335.221971875
4	BRM057	0.4407375	1 Cum.	446.5	196.78929375
Total: 4124.5366476563					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 2082.4493956269
2	Display Citizen Board @ Rs. 393	Rs. 393
Total Addition Component Amount (in Rs.): 2475.4493956269		

Total Net Amount (in Rs.): 210720.38895831