

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Binka	Gram Panchayat	Kaintara

Work Code	OD/372/3567/121431/419101/00072832 (Const. of Kalyan Mandap at Mahadev Mandir Katapali)						
Project Category	Building						

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Binka	Proposal Date	-
Date of Commencement	06-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Kalyan Mandap	Project Type	New Work
Name of Executant	SAROJ KUMAR SAHU		

Administrative Approval Details

Approval No.	OD/372/3567/121431/419101/00072832/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/372/3567/121431/419101/00072832/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	1000000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	27.53055	240.77592	28562.280775968
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	66.71535	646.807232	28562.280775968

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	14.8067	5517.97046898	28562.280775968
4	<p>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	18.15705	5012.243620864	28562.280775968

5	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	Qntl	21	8471.7722229	28562.280775968
---	---	------	----	--------------	-----------------

6	<p>R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)</p>	Cum	5.80175	14067.344838342	28562.280775968
---	---	-----	---------	-----------------	-----------------

7	<p>R.C.C. Work (AR0404Ba) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9). -</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9).</p>	Cum	5.796	6007.6553178867	28562.280775968
---	--	-----	-------	-----------------	-----------------

8	<p>R.C.C. Work (AR0404Bb) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Plinth band)(Nominal mix as per IS-456, Table-9). -</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)(Nominal mix as per IS-456, Table-9)..</p>	Cum	3.43875	6765.0295642148	28562.280775968
---	--	-----	---------	-----------------	-----------------

9	<p>R.C.C. Work (AR0404Bd) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Lintels)(Nominal mix as per IS-456, Table-9). -</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)(Nominal mix as per IS-456, Table-9).</p>	Cum	1.20075	12677.6437499	28562.280775968
---	--	-----	---------	---------------	-----------------

10	<p>R.C.C. Work (AR0404Bg) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9). -</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).</p>	Cum	4.644248	12315.397673304	28562.280775968
----	--	-----	----------	-----------------	-----------------

11	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	20.83025	5045.573620864	28562.280775968
12	<p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	Sqm	116.59	71.84257680551	28562.280775968

13	<p>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	Sqm	116.59	94.7676397125	28562.280775968
14	<p>Plastering (AR1004i) : 12mm thick cement plaster (1:6) over Brick work in outside. - 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	Sqm	100.525	167.6911927996	28562.280775968

15	<p>Plastering (AR1014i) : 16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	116.59	241.510045166	28562.280775968
16	<p>Painting (AR0917g) : Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work (Outside) - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	Sqm	100.525	126.09799693301	28562.280775968

17	<p>Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	Qntl	2.1	15812.518205087	28562.280775968
18	<p>Painting (AR0901bi) : Priming one coat in outer surface with primer of approved quality over iron work - Priming one coat in outer surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	Sqm	13.77	66.12221647451	28562.280775968
19	<p>Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	Sqm	13.77	164.24273777702	28562.280775968

20	<p>Flooring (AR0817b) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	Sqm	16.056	873.266923766	28562.280775968
----	--	-----	--------	---------------	-----------------

21	<p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	Sqm	23.827	1003.0937151218	28562.280775968
----	---	-----	--------	-----------------	-----------------

22	<p>Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge</p>	Sqm	5.822	1320.191923766	28562.280775968
23	<p>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	Sqm	80	357.0285096996	28562.280775968
Total Amount (in Rs.): 905280.84673699					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	27.53055	Cum
i	Un-Skilled	0.516	14.2057638	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	66.71535	Cum
i	Un-Skilled	0.1236	8.24601726	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	14.8067	Cum
i	Skilled	0.18	2.665206	-
ii	Un-Skilled	3.9	57.74613	-
4	<p>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	18.15705	Cum
i	Un-Skilled	2.96	53.744868	-

	ii	Skilled	1.05	19.0649025	-
	iii	Highly-Skilled	0.35	6.3549675	-
5		R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	21	Qntl
	i	Un-Skilled	0.8	16.8	-
	ii	Highly-Skilled	0.3	6.3	-
	iii	Semi-Skilled	0.044	0.924	-

6	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	5.80175	Cum
i	Un-Skilled	1.3333	7.735473275	-
ii	Skilled	5.33875	30.9740928125	-
iii	Semi-Skilled	5.29605	30.7263580875	-

7	<p>R.C.C. Work (AR0404Ba) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9).</p>	-	5.796	Cum
i	Un-Skilled	1.3333	7.7278068	-
ii	Skilled	0.175	1.0143	-
iii	Semi-Skilled	0.1323	0.7668108	-

8	R.C.C. Work (AR0404Bb) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Plinth band)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)(Nominal mix as per IS-456, Table-9)..	-	3.43875	Cum
i	Un-Skilled	1.3333	4.584885375	-
ii	Skilled	0.35	1.2035625	-
iii	Semi-Skilled	0.3073	1.056727875	-

9	R.C.C. Work (AR0404Bd) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Lintels)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)(Nominal mix as per IS-456, Table-9).	-	1.20075	Cum
i	Un-Skilled	1.3333	1.600959975	-
ii	Skilled	2.34375	2.8142578125	-
iii	Semi-Skilled	2.30105	2.7629857875	-

10	R.C.C. Work (AR0404Bg) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).	-	4.644248	Cum
i	Un-Skilled	1.3333	6.1921758584	-
ii	Skilled	3.15525	14.653763502	-
iii	Semi-Skilled	3.11255	14.4554541124	-

11	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	20.83025	Cum
	i Un-Skilled	2.96	61.65754	-
	ii Skilled	1.05	21.8717625	-
	iii Highly-Skilled	0.35	7.2905875	-
12	<p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	116.59	Sqm

	i	Highly-Skilled	0.053763440860215	6.2682795698925	-
	ii	Un-Skilled	0.053763440860215	6.2682795698925	-
13		Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	116.59	Sqm
	i	Highly-Skilled	0.054	6.29586	-
	ii	Un-Skilled	0.064	7.46176	-
14		Plastering (AR1004i) : 12mm thick cement plaster (1:6) over Brick work in outside. - 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	100.525	Sqm
	i	Un-Skilled	0.12	12.063	-

	ii	Skilled	0.14	14.0735	-
15		Plastering (AR1014i) : 16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	116.59	Sqm
	i	Un-Skilled	0.24	27.9816	-
	ii	Skilled	0.16	18.6544	-
16		Painting (AR0917g) : Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work (Outside) - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	100.525	Sqm

	i	Highly-Skilled	0.089763440860215	9.0234698924731	-
	ii	Un-Skilled	0.096763440860215	9.7271448924731	-
17		Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.1	Qntl
	i	Un-Skilled	6.3976377952756	13.435039370079	-
	ii	Semi-Skilled	1.9685039370079	4.1338582677165	-
	iii	Skilled	3.9370078740157	8.2677165354331	-
	iv	Highly-Skilled	3.4448818897638	7.2342519685039	-
18		Painting (AR0901bi) : Priming one coat in outer surface with primer of approved quality over iron work - Priming one coat in outer surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	13.77	Sqm

	i	Highly-Skilled	0.053763440860215	0.74032258064516	-
	ii	Un-Skilled	0.053763440860215	0.74032258064516	-
19		Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in- charge.(Outside)	-	13.77	Sqm
	i	Highly-Skilled	0.13440860215054	1.8508064516129	-
	ii	Un-Skilled	0.11827956989247	1.6287096774194	-

20	<p>Flooring (AR0817b) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	16.056	Sqm
i	Un-Skilled	0.325	5.2182	-
ii	Highly-Skilled	0.325	5.2182	-

21	Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	23.827	Sqm
i	Un-Skilled	0.216	5.146632	-
ii	Highly-Skilled	0.216	5.146632	-

22	<p>Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge</p>	-	5.822	Sqm
i	Highly-Skilled	0.325	1.89215	-
ii	Un-Skilled	0.325	1.89215	-
iii	Semi-Skilled	0.76	4.42472	-
23	<p>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	-	80	Sqm

i	Un-Skilled	0.36	28.8	-
ii	Highly-Skilled	0.13	10.4	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	360.60445843391	462	166599.25979647
1	Skilled	135.25746416243	562	76014.694859287
2	Highly-Skilled	74.015527463128	612	45297.502807434
3	Semi-Skilled	59.250914930117	512	30336.46844422
Total: 318247.92590741				

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	27.53055	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	66.71535	Cum
i)	BRM029 : Sand for filling and road blinding	1	66.71535	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.8067	Cum
i)	BRM340 : Cement	2.29	33.907343	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.107216	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	14.214432	1 Cum.

4	<p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	18.15705	Cum
i)	<p>BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %</p>	400	7262.82	1000 Nos
ii)	<p>BRM340 : Cement</p>	0.672	12.2015376	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	5.083974	1 Cum
5	<p>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	21	Qntl
i)	<p>BRM162 : Binding Wire.</p>	0.8	16.8	1 Kg.

ii)	BRM341 : Steel	1.05	22.05	1 Qntl.
6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	5.80175	Cum
i)	BRM340 : Cement	3.4733	20.151218275	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.6107875	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.08863	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.132945	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	25.6414143	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.24094087575	1Cum.

7	<p>R.C.C. Work (AR0404Ba) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9).</p>	-	5.796	Cum
i)	<p>BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)</p>	0.36	2.08656	1 Cum.
ii)	<p>BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)</p>	0.54	3.12984	1 Cum.
iii)	<p>BRM340 : Cement</p>	3.4733	20.1312468	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	2.6082	1 Cum

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.02321298	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1.095444	1Mtr.
8	R.C.C. Work (AR0404Bb) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Plinth band)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)(Nominal mix as per IS-456, Table-9)..	-	3.43875	Cum
i)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.23795	1 Cum.
ii)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.856925	1 Cum.
iii)	BRM340 : Cement	3.4733	11.943810375	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.5474375	1 Cum

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0459073125	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	2.1664125	1Mtr.
9	R.C.C. Work (AR0404Bd) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Lintels)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)(Nominal mix as per IS-456, Table-9).	-	1.20075	Cum
i)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.43227	1 Cum.
ii)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.648405	1 Cum.
iii)	BRM340 : Cement	3.4733	4.170564975	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.5403375	1 Cum

v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	4.526227125	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.089015800125	1Cum.
10	R.C.C. Work (AR0404Bg) :Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).	-	4.644248	Cum
i)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.67192928	1 Cum.
ii)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.50789392	1 Cum.
iii)	BRM340 : Cement	3.4733	16.1308665784	1 Qntl.

iv)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.0899116	1 Cum
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	28.8946533568	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.2332211306656	1Cum.
11	Masonry Brick Work (AR0603ci) :Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	20.83025	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	20.83025	1 Cum
ii)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	400	8332.1	1000 Nos
iii)	BRM340 : Cement	0.672	13.997928	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.83247	1 Cum

12	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	116.59	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	9.79356	1 Ltr
13	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	116.59	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	14.57375	1 Litre
14	Plastering (AR1004i) :.12mm thick cement plaster (1:6) over Brick work in outside. - 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	100.525	Sqm
i)	BRM340 : Cement	0.0358	3.598795	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.507875	1 Cum
15	Plastering (AR1014i) :.16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	116.59	Sqm
i)	BRM340 : Cement	0.043	5.01337	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.09862	1 Cum
16	Painting(AR0917g) :.Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work (Outside) - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	100.525	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	7.539375	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	8.4441	1 Ltr

17	Iron Work(AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.1	Qntl
i)	BRM341 : Steel	1	2.1	1 Qntl.
18	Painting(AR0901bi) : Priming one coat in outer surface with primer of approved quality over iron work - Priming one coat in outer surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	13.77	Sqm
i)	BRM137 : Red oxide Primer	0.054	0.74358	1 Litre
19	Painting(AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	13.77	Sqm
i)	BRM141 : Enamel paint	0.125	1.72125	1 Litre

20	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	16.056	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	16.056	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	2.2077	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.24084	1 Cum

21	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	23.827	Sqm
i)	BRM174 : White Cement.	0.0076	0.1810852	1Qntl
ii)	BRM340 : Cement	0.1074	2.5590198	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.500367	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	23.827	1 Sqm.

22	Flooring (AR0817a) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge	-	5.822	Sqm
i)	BRMMR0027 : Wax Polish	1	5.822	1 Sqm
ii)	BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	1	5.822	1 Sqm.
iii)	BRM340 : Cement	0.1375	0.800525	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.08733	1 Cum
23	Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	80	Sqm
i)	BRM340 : Cement	0.0858	6.864	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.012	0.96	1 Cum
iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1.84	1 Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	66.71535	1 Cum	413.05	27556.7753175
2	BRM340	153.6779254034	1 Qntl.	552.117	84848.195139949
3	BRM028	32.8153661	1 Cum	417.99	13716.494876139
4	BRM044	14.214432	1 Cum.	1596.76	22697.03644032
5	BRM006	15594.92	1000 Nos	5.4818	85488.232456
6	BRM162	16.8	1 Kg.	90.1	1513.68
7	BRM341	24.15	1 Qntl.	6252.637	151001.18355
8	BRM060	7.51733928	1 Cum.	2020.18	15186.37846667
9	BRM052	11.27600892	1 Cum.	1981.51	22343.524435069
10	BRM084	54.5360676568	1Mtr	297.726	16236.805279188
11	BRM104	0.6322980990406	1Cum.	58620.646	37065.723030332
12	BRM092	3.2618565	1Mtr.	276.666	902.444790429
13	BRM094	4.526227125	1Mtr.	287.666	1302.0416521403
14	BRMMR0025	20.83025	1 Cum	33	687.39825
15	BRM253	9.79356	1 Ltr	159.39677	1561.0618308012
16	BRM140	14.57375	1 Litre	249.70677	3639.1640392875
17	BRM255	7.539375	1 Ltr	195.15677	1471.3600728187
18	BRM252	8.4441	1 Ltr	125.86677	1062.831592557
19	BRM137	0.74358	1 Litre	143.06677	106.3815888366
20	BRM141	1.72125	1 Litre	205.70677	354.0727778625
21	BRM129	16.056	1 Sqm.	418.0738891	6712.5943633896
22	BRM174	0.1810852	1Qntl	2053.857	371.9231056164
23	BRM131	23.827	1 Sqm.	663.9538891	15820.029315586
24	BRMMR0027	5.822	1 Sqm	8.5	49.487
25	BRM130	5.822	1 Sqm.	462.9538891	2695.3175423402
26	BRM057	1.84	1 Cum.	1686.7	3103.528
Total: 517493.66491283					

ROYALTY STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	27.53055	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	66.71535	Cum
i)	BRM029 : Sand for filling and road blinding	1	66.71535	1 Cum

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	14.8067	Cum
i)	BRM340 : Cement	2.29	33.907343	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	7.107216	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	14.214432	1 Cum.
4	<p>Masonry Brick Work (AR0603c) :.Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	18.15705	Cum
i)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	7262.82	1000 Nos

ii)	BRM340 : Cement	0.672	12.2015376	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.083974	1 Cum
5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	21	Qntl
i)	BRM341 : Steel	1.05	22.05	1 Qntl.
6	R.C.C. Work (AR0404Ac) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	5.80175	Cum
i)	BRM340 : Cement	3.4733	20.151218275	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.6107875	1 Cum

iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	2.08863	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	3.132945	1 Cum.
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	0.26304554325	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.24094087575	1Cum.

7	<p>R.C.C. Work (AR0404Ba) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9).</p>	-	5.796	Cum
i)	<p>BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)</p>	0.36	2.08656	1 Cum.
ii)	<p>BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)</p>	0.54	3.12984	1 Cum.
iii)	<p>BRM340 : Cement</p>	3.4733	20.1312468	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.45	2.6082	1 Cum

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.02321298	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	0.005338116	1Mtr.
8	R.C.C. Work (AR0404Bb) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Plinth band)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)(Nominal mix as per IS-456, Table-9)..	-	3.43875	Cum
i)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.23795	1 Cum.
ii)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.856925	1 Cum.
iii)	BRM340 : Cement	3.4733	11.943810375	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.5474375	1 Cum

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0459073125	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	0.0105569625	1Mtr.
9	R.C.C. Work (AR0404Bd) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Lintels)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)(Nominal mix as per IS-456, Table-9).	-	1.20075	Cum
i)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.43227	1 Cum.
ii)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.648405	1 Cum.
iii)	BRM340 : Cement	3.4733	4.170564975	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.5403375	1 Cum

v)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	0.0594875565	1Mtr.
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	0.089015800125	1Cum.
10	R.C.C. Work (AR0404Bg) :.Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).	-	4.644248	Cum
i)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.67192928	1 Cum.
ii)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.50789392	1 Cum.
iii)	BRM340 : Cement	3.4733	16.1308665784	1 Qntl.

iv)	BRM028 : Screened and washed sharp sand for mortar	0.45	2.0899116	1 Cum
v)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	0.356023407432	1Mtr
vi)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.2332211306656	1Cum.
11	Masonry Brick Work (AR0603ci) :Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	20.83025	Cum
i)	BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	8332.1	1000 Nos
ii)	BRM340 : Cement	0.672	13.997928	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.83247	1 Cum

12	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	116.59	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	9.79356	1 Ltr
13	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	116.59	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	14.57375	1 Litre
14	Plastering (AR1004i) :.12mm thick cement plaster (1:6) over Brick work in outside. - 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	100.525	Sqm
i)	BRM340 : Cement	0.0358	3.598795	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.507875	1 Cum
15	Plastering (AR1014i) :.16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	116.59	Sqm
i)	BRM340 : Cement	0.043	5.01337	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.09862	1 Cum
16	Painting(AR0917g) :.Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work (Outside) - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	100.525	Sqm
i)	BRM255 : Weather Coat (I.S.I.)	0.075	7.539375	1 Ltr
ii)	BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	8.4441	1 Ltr

17	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	2.1	Qntl
i)	BRM341 : Steel	1	2.1	1 Qntl.
18	Painting(AR0901bi) :.Priming one coat in outer surface with primer of approved quality over iron work - Priming one coat in outer surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	13.77	Sqm
i)	BRM137 : Red oxide Primer	0.054	0.74358	1 Litre
19	Painting(AR0903i) :.Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	13.77	Sqm
i)	BRM141 : Enamel paint	0.125	1.72125	1 Litre

20	<p>Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	16.056	Sqm
i)	<p>BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753</p>	1	16.056	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	2.2077	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.24084	1 Cum

21	<p>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	23.827	Sqm
i)	BRM174 : White Cement.	0.0076	0.1810852	1Qntl
ii)	BRM340 : Cement	0.1074	2.5590198	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.500367	1 Cum
iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	23.827	1 Sqm.

22	<p>Flooring (AR0817a) :.Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge</p>	-	5.822	Sqm
i)	<p>BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755</p>	1	5.822	1 Sqm.
ii)	<p>BRM340 : Cement</p>	0.1375	0.800525	1 Qntl.
iii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.015	0.08733	1 Cum
23	<p>Flooring (AR0802ii) :.2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	-	80	Sqm
i)	<p>BRM340 : Cement</p>	0.0858	6.864	1 Qntl.
ii)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.012	0.96	1 Cum

iii)	BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1.84	1 Cum.
------	--	-------	------	--------

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	66.71535	1 Cum	170.25	11358.2883375
2	BRM028	32.8153661	1 Cum	170.25	5586.816078525
3	BRM044	14.214432	1 Cum.	279.5	3972.933744
4	BRM060	7.51733928	1 Cum.	279.5	2101.09632876
5	BRM052	11.27600892	1 Cum.	279.5	3151.64449314
6	BRM057	1.84	1 Cum.	279.5	514.28
Total: 26685.058981925					

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for PH Work @ Rs. 45000	Rs. 45000
2	Provision for Contingency @ 1%	Rs. 9052.8084673699
3	Display Citizen Board @ Rs. 3000	Rs. 3000
4	Any Other Lumpsum @ Rs. 666	Rs. 666
Total Addition Component Amount (in Rs.): 57718.80846737		

Total Net Amount (in Rs.): 962999.65520436