

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Gajapati	<b>Block</b>	Gosani	<b>Gram Panchayat</b>	Badakathuru

<b>Work Code</b>	OD/353/3357/117439/414726/00013345 (Renovation of Chintala Tank at Adagam of GP-Badakatturu)
<b>Project Category</b>	Water Body

<b>Financial Year</b>	2021-22	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Gosani	<b>Proposal Date</b>	04-12-2021
<b>Date of Commencement</b>	04-07-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Capital Assets
<b>Project Sub-Category</b>	Tank	<b>Project Type</b>	Renovation or Rejuvenation
<b>Name of Executant</b>	HARIHAR BISWAL		

### Administrative Approval Details

<b>Approval No.</b>	OD/353/3357/117439/414726/00013345/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/353/3357/117439/414726/00013345/TS
<b>Fund Sanction No.</b>	4465
<b>Fund Sanction Amount (in Rs.)</b>	115000

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	<b>Earth Work (AR0102a) : Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</b>	-	468	Cum
i	Un-Skilled	0.43	201.24	-

2	<p><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	1.8	Cum
i	Skilled	0.18	0.324	-
ii	Un-Skilled	3.9	7.02	-
3	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	0.3	Cum
i	Un-Skilled	4.6	1.38	-
ii	Skilled	0.68	0.204	-

4	<b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24	Sqm
i	Semi-Skilled	0.05	1.2	-
ii	Skilled	0.05	1.2	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	209.64	452	94757.28
1	Skilled	1.728	552	953.856
2	Semi-Skilled	1.2	502	602.4
<b>Total:</b>				<b>96313.536</b>