

ESTIMATION DPR

State	Odisha	District	Puri	Block	Sadar	Gram Panchayat	Beladal
--------------	--------	-----------------	------	--------------	-------	-----------------------	---------

Work Code	OD/369/3545/275375/409845/00013585 (Improvement of Road from Anada Pradhan House to Sagar Pradhan House at Beladal)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Sadar	Proposal Date	03-06-2023
Date of Commencement	03-03-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	SUNILPURTY		

Administrative Approval Details

Approval No.	OD/369/3545/275375/409845/00013585/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/369/3545/275375/409845/00013585/TS
Fund Sanction No.	11939
Fund Sanction Amount (in Rs.)	100000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0122Ai1) : Earthwork in all kinds of soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth - Earthwork in all kinds of soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.</p>	-	2.618171328	Cum
i	Un-Skilled	0.503534	1.3183382814732	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	13.540244256	Cum
i	Un-Skilled	0.1236	1.6735741900416	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	6.44773536	Cum
i	Skilled	0.18	1.1605923648	-
ii	Un-Skilled	3.9	25.146167904	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	6.44773536	Cum
i	Un-Skilled	4.6	29.659582656	-
ii	Skilled	0.68	4.3844600448	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	57.797663031515	452	26124.543690245
1	Skilled	5.5450524096	552	3060.8689300992
				Total: 29185.412620344