

## ESTIMATION DPR

<b>State</b>	Odisha	<b>District</b>	Mayurbhanj	<b>Block</b>	Baripada	<b>Gram Panchayat</b>	Badjode
--------------	--------	-----------------	------------	--------------	----------	-----------------------	---------

<b>Work Code</b>	OD/365/3490/120097/390469/00014273 (Construction of Boundary wall of Banasthali High School,Badjode)
<b>Project Category</b>	Other Infrastructure

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Baripada	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	10-02-2025	<b>Date of Completion</b>	21-06-2025
<b>Scheme Name</b>	SFC Devolution of Fund	<b>Scheme Component Name</b>	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
<b>Project Sub-Category</b>	Boundary Wall	<b>Project Type</b>	New Work
<b>Name of Executant</b>	ASHOK KUMAR DAS		

## Administrative Approval Details

<b>Approval No.</b>	OD/365/3490/120097/390469/00014273/AS
---------------------	---------------------------------------

## Technical Sanction Details

<b>Technical Sanction No.</b>	OD/365/3490/120097/390469/00014273/TS
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	200000

## LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Earth Work (AR0103a1) :</b>  <b>Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m</b>  - Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per specification approved by the dept.</p>	-	11.7656304	Cum
i	Un-Skilled	0.7006	8.24300065824	-
2	<p><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	2.84303078928	Cum
i	Un-Skilled	0.1236	0.35139860555501	-

3	<p><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	2.36645904528	Cum
	i Skilled	0.18	0.4259626281504	-
	ii Un-Skilled	3.9	9.229190276592	-
4	<p><b>Plastering (AR1014) :</b>  <b>16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	71.06707888	Sqm
	i Un-Skilled	0.24	17.0560989312	-
	ii Skilled	0.16	11.3707326208	-

5		<b>Painting (AR0901a) : Priming one coat in inner surface with primer of approved quality over woodwork -</b> Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	12.237926384	Sqm
	i	Highly-Skilled	0.053763440860215	0.65795303139785	-
	ii	Un-Skilled	0.053763440860215	0.65795303139785	-
6		<b>R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	6.0422458632	Cum
	i	Un-Skilled	1.3333	8.0561264094046	-
	ii	Skilled	0.1	0.60422458632	-

	iii	Semi-Skilled	0.0573	0.34622068796136	-
7		<p><b>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	12.0840386576	Cum
	i	Un-Skilled	2.82	34.076989014432	-
	ii	Skilled	1.05	12.68824059048	-
	iii	Highly-Skilled	0.35	4.22941353016	-
8		<p><b>Painting (AR0918cb) : Finishing wall two coats with weather coat with one coat waterbound Primer -</b>  Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	-	12.237926384	Sqm

	i	Un-Skilled	0.11776344086022	1.4411803199738	-
	ii	Highly-Skilled	0.10776344086022	1.3188010561338	-
9		<b>Plastering (AR1004) : Fourth Floor - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</b>	-	60.66194288	Sqm
	i	Un-Skilled	0.1350610572	8.1930661371788	-
	ii	Skilled	0.1575712334	9.5585771600419	-
10		<b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</b>	-	4.5315	Qntl
	i	Un-Skilled	0.8	3.6252	-

ii	Highly-Skilled	0.3	1.35945	-
iii	Semi-Skilled	0.044	0.199386	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	90.930203383974	452	41100.451929556
1	Skilled	34.647737585792	552	19125.551147357
2	Highly-Skilled	7.5656176176917	602	4554.5018058504
3	Semi-Skilled	0.54560668796136	502	273.8945573566
<b>Total:</b>				<b>65054.399440121</b>