

ESTIMATION DPR							
State	Odisha	District	Balasore	Block	Baleshwar	Gram Panchayat	Dubula Gadi

Work Code	OD/346/3299/275531/392606/00014678 (Construction of CC Road from Rajkrushna Parida house to Asish Parida house.)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Baleshwar	Proposal Date	20-09-2024
Date of Commencement	27-05-2025	Date of Completion	22-07-2025
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	MAMATA HANSDA		

Administrative Approval Details

Approval No.	OD/346/3299/275531/392606/00014678/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3299/275531/392606/00014678/TS
Fund Sanction No.	0
Fund Sanction Amount (in Rs.)	151003

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0101a1) : Earthwork in ordinary soil within 50m to 75m lead and 1.5m, initial lift - Earthwork in ordinary soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	1.63741896	Cum

	i	Un-Skilled	0.35	0.573096636	-
2		<p>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	10.479481344	Cum
	i	Un-Skilled	3.9	40.8699772416	-
	ii	Skilled	0.18	1.88630664192	-
3		<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	7.204643424	Cum
	i	Un-Skilled	4.6	33.1413597504	-

	ii	Skilled	0.68	4.89915752832	-
4		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.771867888	Cum
	i	Un-Skilled	0.1236	1.5786028709568	-
5		R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	42.690414948	Sqm
	i	Semi-Skilled	0.05	2.1345207474	-
	ii	Skilled	0.05	2.1345207474	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	76.163036498957	452	34425.692497528

1	Skilled	8.91998491764	552	4923.8316745373
2	Semi-Skilled	2.1345207474	502	1071.5294151948
				Total: 40421.053587261