

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Balangir	Gram Panchayat	Jhankarpali

Work Code	OD/345/3285/115786/420133/00015155 (Impvt. Of road from Harijanpada to Haripali Khaliabandh)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Balangir	Proposal Date	23-05-2023
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/345/3285/115786/420133/00015155/TS
Fund Sanction No.	13738
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	22.408216512	Cum

	i	Un-Skilled	0.516	11.562639720192	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	19.259954688	Cum
	i	Un-Skilled	0.1236	2.3805303994368	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	27.593588928	Cum
	i	Skilled	0.18	4.96684600704	-
	ii	Un-Skilled	3.9	107.6149968192	-

4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	64.40407572	Sqm
i	Semi-Skilled	0.05	3.220203786	-
ii	Skilled	0.05	3.220203786	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.</p>	-	18.5191872	Cum
i	Un-Skilled	4.6	85.18826112	-
ii	Skilled	0.68	12.593047296	-
SI.No.	Labour Type	Qty Unit	Rate	Amount

0	Un-Skilled	206.74642805883	462	95516.849763179
1	Skilled	20.78009708904	562	11678.41456404
2	Semi-Skilled	3.220203786	512	1648.744338432
				Total: 108844.00866565