

ESTIMATION DPR							
State	Odisha	District	Jharsuguda	Block	Jharsuguda	Gram Panchayat	Chandinimal

Work Code	OD/357/3404/118516/381090/00015367 (Construction of Market Complex near Chandinimal BNRGSK)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Jharsuguda	Proposal Date	-
Date of Commencement	10-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	ROSY PATEL		

Administrative Approval Details

Approval No.	OD/357/3404/118516/381090/00015367/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/357/3404/118516/381090/00015367/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	39.258	Cum

	i	Un-Skilled	0.516	20.257128	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	23.2488	Cum
	i	Un-Skilled	0.1236	2.87355168	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.0818	Cum
	i	Skilled	0.18	1.814724	-
	ii	Un-Skilled	3.9	39.31902	-

4	Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	11.92572	Cum
i	Un-Skilled	2.96	35.3001312	-
ii	Skilled	1.05	12.522006	-
iii	Highly-Skilled	0.35	4.174002	-

5	Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	22.228695	Cum
i	Un-Skilled	2.96	65.7969372	-
ii	Skilled	1.05	23.34012975	-
iii	Highly-Skilled	0.35	7.78004325	-

6	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	6.345	Cum
i	Un-Skilled	1.3333	8.4597885	-
ii	Skilled	0.175	1.110375	-
iii	Semi-Skilled	0.1323	0.8394435	-

7	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	2.958375	Cum
i	Un-Skilled	1.3333	3.9444013875	-
ii	Skilled	0.35	1.03543125	-
iii	Semi-Skilled	0.3073	0.9091086375	-

8	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.363965	Cum
i	Un-Skilled	1.3333	5.8184745345	-
ii	Skilled	5.33875	23.29811814375	-
iii	Semi-Skilled	5.29605	23.11177683825	-

9	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	2.044585	Cum
i	Un-Skilled	1.3333	2.7260451805	-
ii	Skilled	2.34375	4.79199609375	-
iii	Semi-Skilled	2.30105	4.70469231425	-

10	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	7.89525	Cum
i	Un-Skilled	1.3333	10.526736825	-
ii	Skilled	3.15525	24.9114875625	-
iii	Semi-Skilled	3.11255	24.5743603875	-

11	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	22	Qntl
i	Un-Skilled	0.8	17.6	-
ii	Highly-Skilled	0.3	6.6	-
iii	Semi-Skilled	0.044	0.968	-
12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	52.668	Sqm
i	Un-Skilled	0.17	8.95356	-

	ii	Skilled	0.14	7.37352	-
13		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	92.268	Sqm
	i	Un-Skilled	0.12	11.07216	-
	ii	Skilled	0.14	12.91752	-
14		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	164.106	Sqm
	i	Un-Skilled	0.24	39.38544	-
	ii	Skilled	0.16	26.25696	-

15	<p>Painting (AR0922a) : Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with distemper of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	216.774	Sqm
	i Highly-Skilled	0.10576344086022	22.926764129032	-
	ii Un-Skilled	0.11576344086022	25.094504129032	-
16	<p>Painting (AR0917g) : First Floor - Finishing wall with one coat weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	92.268	Sqm
	i Highly-Skilled	0.06825	6.297291	-
	ii Un-Skilled	0.0756	6.9754608	-

17	Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	53.46	Sqm
i	Highly-Skilled	0.13440860215054	7.1854838709677	-
ii	Un-Skilled	0.11827956989247	6.3232258064516	-
18	Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	53.496	Sqm
i	Un-Skilled	0.216	11.555136	-
ii	Highly-Skilled	0.216	11.555136	-

19	<p>Flooring (AR0817ab) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	4.23	Sqm
i	Highly-Skilled	0.325	1.37475	-
ii	Un-Skilled	0.325	1.37475	-
iii	Semi-Skilled	0.76	3.2148	-
20	<p>Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	-	4.4	Qntl

i	Un-Skilled	6.3976377952756	28.149606299213	-
ii	Semi-Skilled	1.9685039370079	8.6614173228346	-
iii	Skilled	3.9370078740157	17.322834645669	-
iv	Highly-Skilled	3.4448818897638	15.157480314961	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	351.5060575422	462	162395.79858449
1	Skilled	156.69510244567	562	88062.647574466
2	Highly-Skilled	83.050950564961	612	50827.181745756
3	Semi-Skilled	66.983599000335	512	34295.602688171
Total:				335581.23059289