

ESTIMATION DPR							
State	Odisha	District	Khordha	Block	Bhubaneswar	Gram Panchayat	Tamando

Work Code	OD/362/3460/119615/407771/00015471 (Provision of Facility Centre at Tamando GP Hqrs)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Bhubaneswar	Proposal Date	-
Date of Commencement	02-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	Suchismita Mohanty		

Administrative Approval Details

Approval No.	OD/362/3460/119615/407771/00015471/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/362/3460/119615/407771/00015471/TS
Fund Sanction No.	18989
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.8122752	Cum

	i	Un-Skilled	0.516	0.9351340032	-
2		R.C.C. Work (AR0409) : First floor - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	13	Qntl
	i	Un-Skilled	0.84	10.92	-
	ii	Highly-Skilled	0.315	4.095	-
	iii	Semi-Skilled	0.0462	0.6006	-
3		R.C.C. Work (AR0410a) : First floor - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	14.492868	Sqm
	i	Semi-Skilled	0.36666666666667	5.3140516	-
	ii	Skilled	0.36666666666667	5.3140516	-

4	<p>Plastering (AR1014) : First Floor - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	96.5726685	Sqm
i	Un-Skilled	0.2472	23.8727636532	-
ii	Skilled	0.1648	15.9151757688	-
5	<p>Plastering (AR1027) : First Floor - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	77.295296	Sqm
i	Un-Skilled	0.1751	13.5344063296	-
ii	Skilled	0.1442	11.1459816832	-

6	<p>Masonry Brick Work (AR0603bi) : First floor - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	38.08228597456	Cum
i	Un-Skilled	3.404	129.6321014574	-
ii	Skilled	1.2075	45.984360314281	-
iii	Highly-Skilled	0.4025	15.32812010476	-
7	<p>Painting (AR0901d) : First Floor - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	96.5726685	Sqm
i	Highly-Skilled	0.055376344086022	5.3478413201613	-
ii	Un-Skilled	0.055376344086022	5.3478413201613	-

8	Painting (AR0920) : First Floor - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	100.985561	Sqm
i	Highly-Skilled	0.05562	5.61681690282	-
ii	Un-Skilled	0.06592	6.65696818112	-
9	Painting (AR0918g) : First Floor - Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	100.985561	Sqm
i	Un-Skilled	0.090051612903226	9.0939126479871	-
ii	Highly-Skilled	0.079551612903226	8.0335642574871	-

10	<p>Other Building Items. (AR1902) : First Floor - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	96.5726685	Sqm
i	Un-Skilled	0.05871	5.669781367635	-
ii	Skilled	0.0515	4.97349242775	-
11	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	15.700607	Sqm
i	Semi-Skilled	0.05	0.78503035	-
ii	Skilled	0.05	0.78503035	-

12	R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	11.14836	Sqm
i	Semi-Skilled	0.16025641025641	1.7865961538462	-
ii	Skilled	0.16025641025641	1.7865961538462	-
13	R.C.C. Work (AR0404A) : First floor - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	17.07901032624	Cum
i	Un-Skilled	1.533295	26.187161138172	-
ii	Skilled	0.115	1.9640861875176	-
iii	Semi-Skilled	0.065895	1.1254213854476	-

14	R.C.C. Work (AR0410e) : First floor - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	10.46459392	Sqm
i	Semi-Skilled	0.19230769230769	2.0124219076923	-
ii	Skilled	0.19230769230769	2.0124219076923	-
15	R.C.C. Work (AR0410d) : First floor - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	51.125914445	Sqm
i	Semi-Skilled	0.78571428571429	40.170361349643	-
ii	Skilled	0.78571428571429	40.170361349643	-

16	<p>Other Building Items. (AR1901B) : First floor - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	77.295296	Sqm
	i Un-Skilled	0.2268	17.5305731328	-
	ii Highly-Skilled	0.2268	17.5305731328	-
17	<p>Plastering (AR1004) : First Floor - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	100.985561	Sqm
	i Un-Skilled	0.1236	12.4818153396	-
	ii Skilled	0.1442	14.5621178962	-

18	Painting (AR0903i) : First Floor - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	14.492868	Sqm
	i Highly-Skilled	0.14112903225806	2.0453644354839	-
	ii Un-Skilled	0.1241935483871	1.7999207032258	-
19	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.0388096	Cum
	i Un-Skilled	0.1236	0.25199686656	-
20	Painting (AR0918c) : First Floor - Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	46.4515	Sqm

	i	Un-Skilled	0.044890322580645	2.0852228193548	-
	ii	Highly-Skilled	0.0231	1.07302965	-
	iii	Skilled	0.0084677419354839	0.39333931451613	-
21		Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in- charge.	-	1.2	Qntl
	i	Un-Skilled	6.3976377952756	7.6771653543307	-
	ii	Semi-Skilled	1.9685039370079	2.3622047244094	-
	iii	Skilled	3.9370078740157	4.7244094488189	-
	iv	Highly-Skilled	3.4448818897638	4.1338582677165	-

22	<p>Flooring (AR0817ac) : First floor - Fixing Vitrified industrial Tile of premium grade having thickness 8mm to 10mm confirming to IS 4457 of size 300mmx300mm in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	13.9075791	Sqm
i	Highly-Skilled	0.34125	4.745961367875	-
ii	Un-Skilled	0.34125	4.745961367875	-
iii	Semi-Skilled	0.798	11.0982481218	-
23	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	0.2265344	Cum
i	Skilled	0.18	0.040776192	-

	ii	Un-Skilled	3.9	0.88348416	-
24		R.C.C. Work (AR0404Ae) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Stairs excluding landing but including railing)	-	0.013592064	Cum
	i	Un-Skilled	1.3333	0.0181222989312	-
	ii	Skilled	5.05	0.0686399232	-
	iii	Semi-Skilled	5.0073	0.0680595420672	-

25	<p>Other Building Items. (AR1911) : Stainless steel of 304 grade in hand railing using 50mm dia of 2mm - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	-	4.571999853696	Rmt
i	Semi-Skilled	0.27300613496933	1.2481840091379	-
ii	Highly-Skilled	0.27300613496933	1.2481840091379	-
26	<p>Other Building Items. (AR1907) : aluminum sliding window (sliding type) - Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778, as windows frame, section No. 4095, 4096 and 9777, 3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of Engineer-in-charge.</p>	-	2.601284	Sqm

	i	Un-Skilled	1.006711409396	2.6187422818792	-
	ii	Semi-Skilled	1.006711409396	2.6187422818792	-
	iii	Skilled	0.33557046979866	0.87291409395973	-
	iv	Highly-Skilled	0.33557046979866	0.87291409395973	-
27		Flooring (AR0816j) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Enginer-in-charge.	-	27.9266418	Sqm
	i	Un-Skilled	0.216	6.0321546288	-
	ii	Highly-Skilled	0.216	6.0321546288	-
	iii	Semi-Skilled	0.55	15.35965299	-

28	Roofing (AR1132) : Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-	55.7418	Sqm
i	Un-Skilled	0.21505376344086	11.987483870968	-
ii	Highly-Skilled	0.16129032258065	8.9906129032258	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	299.9627129228	462	138582.77337033
1	Highly-Skilled	85.093995074228	612	52077.524985427
2	Semi-Skilled	84.549574415923	512	43289.382100952
3	Skilled	150.71375461142	562	84701.130091621
Total:				318650.81054834