

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Ghatgaon	Gram Panchayat	Tara

Work Code	OD/361/3447/119354/386677/00017148 (CONST OF CC ROAD AT MAJHISAH I HANUMAN MANDIRA TO TALA SAHI, NAKJHARI)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Ghatgaon	Proposal Date	-
Date of Commencement	31-05-2025	Date of Completion	06-06-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	JAYARAM MAJHI		

### Administrative Approval Details

Approval No.	OD/361/3447/119354/386677/00017148/AS
--------------	---------------------------------------

### Technical Sanction Details

Technical Sanction No.	OD/361/3447/119354/386677/00017148/TS
Fund Sanction No.	18204
Fund Sanction Amount (in Rs.)	240000

### LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b></p> <p>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	4.014	Cum

	i	Un-Skilled	0.516	2.071224	-
2		<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.387	Cum
	i	Un-Skilled	0.1236	1.9018332	-
3		<b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.739	Cum
	i	Skilled	0.18	3.73302	-
	ii	Un-Skilled	3.9	80.8821	-

4	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	12.20925	Cum
i	Un-Skilled	4.6	56.16255	-
ii	Skilled	0.68	8.30229	-
5	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	60.21	Sqm
i	Semi-Skilled	0.05	3.0105	-
ii	Skilled	0.05	3.0105	-
<b>SI.No.</b>	<b>Labour Type</b>	<b>Qty Unit</b>	<b>Rate</b>	<b>Amount</b>

0	Un-Skilled	141.0177072	462	65150.1807264
1	Skilled	15.04581	562	8455.74522
2	Semi-Skilled	3.0105	512	1541.376
				<b>Total: 75147.3019464</b>