

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Digapahandi	Gram Panchayat	Gada Gobindapur

Work Code	OD/354/3372/117733/413040/00017426 (Provision of Facility Center at G.Gpur GP office.)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Digapahandi	Proposal Date	07-01-2023
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	1000000
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	45.32528592	Cum

	i	Un-Skilled	0.516	23.38784753472	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	50.98758404	Cum
	i	Un-Skilled	0.1236	6.302065387344	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	26.14377867888	Cum
	i	Skilled	0.18	4.7058801621984	-
	ii	Un-Skilled	3.9	101.96073684763	-

4	<p>R.C.C. Work (AR0404Ba) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc)(Nominal mix as per IS-456, Table-9).</p>	-	7.2871515	Cum
i	Un-Skilled	1.3333	9.71595909495	-
ii	Skilled	0.175	1.2752515125	-
iii	Semi-Skilled	0.1323	0.96409014345	-

5	R.C.C. Work (AR0404Bb) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Plinth band)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)(Nominal mix as per IS-456, Table-9)..	-	2.976024888	Cum
i	Un-Skilled	1.3333	3.9679339831704	-
ii	Skilled	0.35	1.0416087108	-
iii	Semi-Skilled	0.3073	0.9145324480824	-

6	R.C.C. Work (AR0404Bd) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Lintels)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)(Nominal mix as per IS-456, Table-9).	-	1.56032222448	Cum
i	Un-Skilled	1.3333	2.0803776218992	-
ii	Skilled	2.34375	3.657005213625	-
iii	Semi-Skilled	2.30105	3.5903794546397	-

7	R.C.C. Work (AR0404Bg) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9). - Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).	-	10.1329120288	Cum
i	Un-Skilled	1.3333	13.510211607999	-
ii	Skilled	3.15525	31.971870678871	-
iii	Semi-Skilled	3.11255	31.539195335241	-

8	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.933653762	Cum
i	Un-Skilled	1.3333	6.5780405608746	-
ii	Skilled	5.33875	26.339544021877	-
iii	Semi-Skilled	5.29605	26.12887700624	-

9	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	24.201	Qntl
i	Un-Skilled	0.8	19.3608	-
ii	Highly-Skilled	0.3	7.2603	-
iii	Semi-Skilled	0.044	1.064844	-
10	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	19.274638506224	Cum

	i	Un-Skilled	2.96	57.052929978423	-
	ii	Skilled	1.05	20.238370431535	-
	iii	Highly-Skilled	0.35	6.7461234771784	-
11		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	98.47718	Sqm
	i	Un-Skilled	0.12	11.8172616	-
	ii	Skilled	0.14	13.7868052	-
12		Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	63.026210702534	Sqm

	i	Un-Skilled	0.17	10.714455819431	-
	ii	Skilled	0.14	8.8236694983548	-
13		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	113.9641101	Sqm
	i	Un-Skilled	0.24	27.351386424	-
	ii	Skilled	0.16	18.234257616	-
14		miscellaneous (ARM105) : Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer- in-Charge. - Labour for fitting and fixing of M.S. window grills including cost of screws complete. (Iron works) and as directed by Engineer-in-Charge.	-	38.09023	Sqm

15	<p>Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge</p>	-	26.328896006	Sqm
i	Highly-Skilled	0.325	8.55689120195	-
ii	Un-Skilled	0.325	8.55689120195	-
iii	Semi-Skilled	0.76	20.00996096456	-

16	<p>Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge.</p>	-	11.9522310784	Sqm
	i Un-Skilled	0.216	2.5816819129344	-
	ii Highly-Skilled	0.216	2.5816819129344	-
	iii Semi-Skilled	0.55	6.57372709312	-
17	<p>Flooring (AR0802i) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	-	41.70601476	Sqm

i	Un-Skilled	0.36	15.0141653136	-
ii	Highly-Skilled	0.13	5.4217819188	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	319.95274488893	462	147818.16813868
1	Skilled	130.07426304576	562	73101.735831718
2	Semi-Skilled	90.785606445334	512	46482.230500011
3	Highly-Skilled	30.566778510863	612	18706.868448648
Total:				286109.00291906