

ESTIMATION DPR							
State	Odisha	District	Jharsuguda	Block	Kolabira	Gram Panchayat	Samasingha

Work Code	OD/357/3406/118547/381258/00017463 (Repair & Renovation of Hanuman Mandir at Colonypada, GP- Samasingha)						
Project Category	Religious Structures						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kolabira	Proposal Date	09-04-2025
Date of Commencement	-	Date of Completion	-
Scheme Name	Chief Minister Special Assistant	Scheme Component Name	Special Problem Fund (SPF) 16 th Phase
Project Sub-Category	Religious Structures	Project Type	Repair and Maintenance
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	1960
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	0.6	Cum
i	Skilled	0.18	0.108	-
ii	Un-Skilled	3.9	2.34	-
2	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	1.96	Qntl
i	Un-Skilled	0.8	1.568	-

	ii	Highly-Skilled	0.3	0.588	-
	iii	Semi-Skilled	0.044	0.08624	-
3		R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	1.9602845	Cum
	i	Un-Skilled	1.3333	2.61364732385	-
	ii	Skilled	0.1	0.19602845	-
	iii	Semi-Skilled	0.0573	0.11232430185	-

4	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	4.8852	Cum
i	Un-Skilled	2.96	14.460192	-
ii	Skilled	1.05	5.12946	-
iii	Highly-Skilled	0.35	1.70982	-
5	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	18.84	Sqm
i	Un-Skilled	0.12	2.2608	-

	ii	Skilled	0.14	2.6376	-
6		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	24.36	Sqm
	i	Un-Skilled	0.24	5.8464	-
	ii	Skilled	0.16	3.8976	-

7	miscellaneous (ARM286) : Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	100	Sqm
---	---	---	-----	-----

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Skilled	11.96868845	562	6726.4029089
1	Un-Skilled	29.08903932385	462	13439.136167619
2	Highly-Skilled	2.29782	612	1406.26584
3	Semi-Skilled	0.19856430185	512	101.6649225472
Total:				21673.469839066