

ESTIMATION DPR							
State	Odisha	District	Kendujhar	Block	Hatadihi	Gram Panchayat	Samana

Work Code	OD/361/3449/119408/387210/00017583 (Renovation of Hanuman Tank at Chapundia Village)
Project Category	Water Body

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Hatadihi	Proposal Date	07-12-2024
Date of Commencement	08-10-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	New Work
Name of Executant	KSHETRAMOHAN MARNDI		

Administrative Approval Details

Approval No.	OD/361/3449/119408/387210/00017583/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3449/119408/387210/00017583/TS
Fund Sanction No.	28960
Fund Sanction Amount (in Rs.)	500000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	55.35	Cum

	i	Un-Skilled	0.516	28.5606	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.76	Cum
	i	Un-Skilled	0.1236	1.824336	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	68.429	Cum
	i	Skilled	0.18	12.31722	-
	ii	Un-Skilled	3.9	266.8731	-

4	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	188.6	Sqm
i	Semi-Skilled	0.05	9.43	-
ii	Skilled	0.05	9.43	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	297.258036	462	137333.212632
1	Skilled	21.74722	562	12221.93764
2	Semi-Skilled	9.43	512	4828.16
Total:				154383.310272