

ESTIMATION DPR

State	Odisha	District	Bargarh	Block	Bijepur	Gram Panchayat	T.Gendapali
--------------	--------	-----------------	---------	--------------	---------	-----------------------	-------------

Work Code	OD/347/3316/116477/380355/00022045 (Provision Of Facility Centre At T.Gandpali GP Hqrs)						
Project Category	Building						

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Bijepur	Proposal Date	-
Date of Commencement	19-09-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	ASHISH TIWARI		

Administrative Approval Details

Approval No.	OD/347/3316/116477/380355/00022045/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/347/3316/116477/380355/00022045/TS
Fund Sanction No.	12951
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	18.9050036	Cum

	i	Un-Skilled	0.516	9.7549818576	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	38.8022597284	Cum
	i	Un-Skilled	0.1236	4.7959593024302	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.5700207724	Cum
	i	Skilled	0.18	1.902603739032	-
	ii	Un-Skilled	3.9	41.22308101236	-

4	Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	9.5471861	Cum
i	Un-Skilled	2.96	28.259670856	-
ii	Skilled	1.05	10.024545405	-
iii	Highly-Skilled	0.35	3.341515135	-

5	Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	21.280542993536	Cum
i	Un-Skilled	2.96	62.990407260867	-
ii	Skilled	1.05	22.344570143213	-
iii	Highly-Skilled	0.35	7.4481900477376	-

6	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	4.0776192	Cum
i	Un-Skilled	1.3333	5.43668967936	-
ii	Skilled	0.175	0.71358336	-
iii	Semi-Skilled	0.1323	0.53946902016	-

7	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	2.9620439423064	Cum
i	Un-Skilled	1.3333	3.9492931882771	-
ii	Skilled	0.35	1.0367153798072	-
iii	Semi-Skilled	0.3073	0.91023610347076	-

8	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.30886940908	Cum
i	Un-Skilled	1.3333	5.7450155831264	-
ii	Skilled	5.33875	23.003976557726	-
iii	Semi-Skilled	5.29605	22.819987833958	-

9	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.86961424228	Cum
i	Un-Skilled	1.3333	2.4927566692319	-
ii	Skilled	2.34375	4.3819083803437	-
iii	Semi-Skilled	2.30105	4.3020758521984	-

10	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	9.817823916	Cum
i	Un-Skilled	1.3333	13.090104627203	-
ii	Skilled	3.15525	30.977688910959	-
iii	Semi-Skilled	3.11255	30.558467829746	-

11	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	23.02	Qntl
i	Un-Skilled	0.8	18.416	-
ii	Highly-Skilled	0.3	6.906	-
iii	Semi-Skilled	0.044	1.01288	-
12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	54.9521245	Sqm
i	Un-Skilled	0.17	9.341861165	-

	ii	Skilled	0.14	7.69329743	-
13		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	109.8577975	Sqm
	i	Un-Skilled	0.12	13.1829357	-
	ii	Skilled	0.14	15.38009165	-
14		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	141.8164295	Sqm
	i	Un-Skilled	0.24	34.03594308	-
	ii	Skilled	0.16	22.69062872	-

15	Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	45.08954202	Sqm
i	Un-Skilled	0.216	9.73934107632	-
ii	Highly-Skilled	0.216	9.73934107632	-

16	<p>Flooring (AR0817b) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	28.54723384	Sqm
i	Un-Skilled	0.325	9.277850998	-
ii	Highly-Skilled	0.325	9.277850998	-

17	Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge	-	11.79496488	Sqm
i	Highly-Skilled	0.325	3.833363586	-
ii	Un-Skilled	0.325	3.833363586	-
iii	Semi-Skilled	0.76	8.9641733088	-

18	Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	306.6263515	Sqm
i	Highly-Skilled	0.053763440860215	16.485287715054	-
ii	Un-Skilled	0.053763440860215	16.485287715054	-
19	Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	306.6263515	Sqm
i	Highly-Skilled	0.054	16.557822981	-
ii	Un-Skilled	0.064	19.624086496	-

20	Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	29.5896055	Sqm
i	Highly-Skilled	0.13440860215054	3.9770975134409	-
ii	Un-Skilled	0.11827956989247	3.499845811828	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	315.17447566466	462	145610.60775707
1	Skilled	140.14960967608	562	78764.080637957
2	Highly-Skilled	77.566469052552	612	47470.679060162
3	Semi-Skilled	69.107289948333	512	35382.932453547
Total:				307228.29990874