

ESTIMATION DPR							
State	Odisha	District	Puri	Block	Gop	Gram Panchayat	Baniasahi

Work Code	OD/369/3539/120931/409512/00025905 (Imp. of Road with CC/ Gr-II Metalling from Rajib Gandhi Seva Kendra to Bania Sahi Batya Ashray Stali (MCS) Bania Sahi)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Gop	Proposal Date	15-01-2025
Date of Commencement	23-12-2025	Date of Completion	22-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	BHABANI SANKAR POTHAL		

Administrative Approval Details

Approval No.	OD/369/3539/120931/409512/00025905/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/369/3539/120931/409512/00025905/TS
Fund Sanction No.	1130
Fund Sanction Amount (in Rs.)	186532

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	14.03	Cum

	i	Un-Skilled	0.516	7.23948	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.03	Cum
	i	Un-Skilled	0.1236	1.734108	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.03	Cum
	i	Skilled	0.18	2.5254	-
	ii	Un-Skilled	3.9	54.717	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	10.5225	Cum
i	Un-Skilled	4.6	48.4035	-
ii	Skilled	0.68	7.1553	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	6	Sqm
i	Semi-Skilled	0.05	0.3	-
ii	Skilled	0.05	0.3	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	112.094088	462	51787.468656
1	Skilled	9.9807	562	5609.1534
2	Semi-Skilled	0.3	512	153.6
				Total: 57550.222056