

ESTIMATION DPR

State	Odisha	District	Puri	Block	Brahmagiri	Gram Panchayat	Bhubanpur
--------------	--------	-----------------	------	--------------	------------	-----------------------	-----------

Work Code	OD/369/3537/275131/410034/00026214 (Const. of CC Road from Jogendra pradhan ghar to RI office goudakera)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Brahmagiri	Proposal Date	-
Date of Commencement	29-11-2025	Date of Completion	04-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	SUDEEP BESHRA		

Administrative Approval Details

Approval No.	OD/369/3537/275131/410034/00026214/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/369/3537/275131/410034/00026214/TS
Fund Sanction No.	5600
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	5.45	Cum

	i	Un-Skilled	0.516	2.8122	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.94125	Cum
	i	Un-Skilled	0.1236	1.9703385	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	22.75375	Cum
	i	Skilled	0.18	4.095675	-
	ii	Un-Skilled	3.9	88.739625	-

4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	32.7	Sqm
i	Semi-Skilled	0.05	1.635	-
ii	Skilled	0.05	1.635	-
5	<p>Earth Work (AR0110) : Fine dressing of earth work in ordinary or hard soil in road formation - Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.</p>	-	166.225	Sqm
i	Un-Skilled	0.01	1.66225	-

6	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	16.6225	Cum
i	Un-Skilled	4.6	76.4635	-
ii	Skilled	0.68	11.3033	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	171.6479135	462	79301.336037
1	Skilled	17.033975	562	9573.09395
2	Semi-Skilled	1.635	512	837.12
Total:				89711.549987