

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Laxmipur	Gram Panchayat	Laxmipur

Work Code	OD/363/3475/119862/428538/00035554 (Const. of Paver Block road at Sulachona Nagar Laxmipur)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Laxmipur	Proposal Date	-
Date of Commencement	04-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	RANJIT KHOSLA		

Administrative Approval Details

Approval No.	OD/363/3475/119862/428538/00035554/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3475/119862/428538/00035554/TS
Fund Sanction No.	34188
Fund Sanction Amount (in Rs.)	500000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	30.9375	Cum
i	Un-Skilled	0.1236	3.823875	-

2	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	50	Sqm
i	Semi-Skilled	0.05	2.5	-
ii	Skilled	0.05	2.5	-
3	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	5.315	Cum
i	Un-Skilled	4.6	24.449	-
ii	Skilled	0.68	3.6142	-

4	<p>Earth Work (AR0103aa) : Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m - Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department</p>	-	92.19	Cum
i	Un-Skilled	0.80472	74.1871368	-
5	<p>Concrete (AR0309a) : Cement Concrete (1:3:6) with 12mm size hard broken granite Hand Broken chips - Cement Concrete (1:3:6) with 12mm size hard granite (Hand Broken) chips including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	13.44	Cum
i	Skilled	0.68	9.1392	-

	ii	Un-Skilled	4.6	61.824	-
6		miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	400	Sqm

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	164.2840118	462	75899.2134516
1	Semi-Skilled	2.5	512	1280
2	Skilled	15.2534	562	8572.4108
				Total: 85751.6242516