

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Balangir	<b>Block</b>	Turekela	<b>Gram Panchayat</b>	Buromal

<b>Work Code</b>	OD/345/3297/116027/421208/00038032 (Repair & Maintenance of Primary School Kukudahad)
<b>Project Category</b>	Building

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Turekela	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Primary School Building
<b>Project Sub-Category</b>	Elementary School	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/345/3297/116027/421208/00038032/TS
<b>Fund Sanction No.</b>	34989
<b>Fund Sanction Amount (in Rs.)</b>	266878

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Dismantling (AR1612) : Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.</b>	-	52.153421625	Sqm
i	Un-Skilled	0.21505376344086	11.215789596774	-

2	<b>Dismantling (AR1613) : Removing old lime or cement plaster</b> - Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	19.50963	Sqm
i	Un-Skilled	0.10752688172043	2.0978096774194	-
3	<b>Dismantling (AR1621) : Removing old grading plaster from roof</b> - Removing old grading plaster from roof slab, cleaning the surface, lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	62.430816	Sqm
i	Un-Skilled	0.16666666666667	10.405136	-
4	<b>Dismantling (AR1623) : Dismantling and removing cement concrete</b> - Dismantling and removing cement concrete including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	5.245793388	Cum
i	Un-Skilled	1.6	8.3932694208	-

5	<p><b>Flooring (AR0816c) :</b>  <b>Fixing Kota Tiles of minimum 16 mm thick Up to 0.10 Sqm. in floor, treads or steps and landing on a 25mm thick bed of cement mortar 1:1 -</b>          Fixing Kota Tiles of minimum 16 mm thick Up to 0.10 Sqm. in floor, treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the kota tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	52.153421625	Sqm
i	Un-Skilled	0.216	11.265139071	-
ii	Highly-Skilled	0.216	11.265139071	-
iii	Semi-Skilled	0.55	28.68438189375	-
6	<p><b>Concrete (AR0318) :</b>  <b>4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) -</b>          4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (Old Work)</p>	-	62.430816	Sqm

	i	Un-Skilled	1.008	62.930262528	-
	ii	Highly-Skilled	0.165	10.30108464	-
7		<b>Other Building Items. (AR1902) : cement based wall putty (water based) -</b> Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.	-	177.630536	Sqm
	i	Un-Skilled	0.057	10.124940552	-
	ii	Skilled	0.05	8.8815268	-
8		<b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	19.50963	Sqm
	i	Un-Skilled	0.24	4.6823112	-

	ii	Skilled	0.16	3.1215408	-
9		<b>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	177.630536	Sqm
	i	Highly-Skilled	0.054	9.592048944	-
	ii	Un-Skilled	0.064	11.368354304	-
10		<b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) -</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	177.630536	Sqm
	i	Highly-Skilled	0.053763440860215	9.5500288172043	-
	ii	Un-Skilled	0.053763440860215	9.5500288172043	-

11	<b>Painting (AR0918cb) : Finishing wall two coats with weather coat with one coat waterbound Primer -</b> Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	289.950263	Sqm
i	Un-Skilled	0.11776344086022	34.145540649204	-
ii	Highly-Skilled	0.10776344086022	31.246038019204	-
12	<b>Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. -</b> Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	79.0140015	Sqm
i	Highly-Skilled	0.053763440860215	4.2480645967742	-
ii	Un-Skilled	0.053763440860215	4.2480645967742	-

13	<b>Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) -</b> Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	79.0140015	Sqm
i	Highly-Skilled	0.13440860215054	10.620161491935	-
ii	Un-Skilled	0.11827956989247	9.3457421129032	-
14	<b>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.682784612	Cum
i	Un-Skilled	3.9	18.2628599868	-
ii	Skilled	0.18	0.84290123016	-

15	<b>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</b>	-	33.456692875	Sqm
i	Un-Skilled	0.17	5.68763778875	-
ii	Skilled	0.14	4.6839370025	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	213.72288630163	462	98739.973471353
1	Highly-Skilled	86.822565580118	612	53135.410135032
2	Semi-Skilled	28.68438189375	512	14686.4035296
3	Skilled	17.52990583266	562	9851.8070779549
<b>Total:</b>				<b>176413.59421394</b>