

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Cuttack	<b>Block</b>	Cuttacksadar	<b>Gram Panchayat</b>	Jasapada

<b>Work Code</b>	OD/350/3337/116961/399950/00038605 (Improvement of Kalyan Mandap Jasapada , Jasapada GP)
<b>Project Category</b>	Building

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Cuttacksadar	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	03-02-2026	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance of Capital Assets
<b>Project Sub-Category</b>	Kalyan Mandap	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>	Samata Debata		

### Administrative Approval Details

<b>Approval No.</b>	OD/350/3337/116961/399950/00038605/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/350/3337/116961/399950/00038605/TS
<b>Fund Sanction No.</b>	1313
<b>Fund Sanction Amount (in Rs.)</b>	1000000

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</b>	-	15.2141304	Cum
i	Un-Skilled	0.1236	1.88046651744	-

2	<p><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	19.49184	Cum
i	Skilled	0.18	3.5085312	-
ii	Un-Skilled	3.9	76.018176	-
3	<p><b>Plastering (AR1014) :</b>  <b>16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	191.6914	Sqm
i	Un-Skilled	0.24	46.005936	-
ii	Skilled	0.16	30.670624	-

4	<p><b>Plastering (AR1004i) : 12mm thick cement plaster (1:6) over Brick work in outside.</b></p> <p>- 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	38.4109	Sqm
i	Un-Skilled	0.12	4.609308	-
ii	Skilled	0.14	5.377526	-
5	<p><b>R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b></p> <p>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	-	3.7104608	Cum
i	Un-Skilled	1.3333	4.94715738464	-

	ii	Skilled	0.1	0.37104608	-
	iii	Semi-Skilled	0.0573	0.21260940384	-
6		<b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</b>	-	36.6531	Sqm
	i	Semi-Skilled	0.05	1.832655	-
	ii	Skilled	0.05	1.832655	-
7		<b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</b>	-	3.52	Qntl

	i	Un-Skilled	0.8	2.816	-
	ii	Highly-Skilled	0.3	1.056	-
	iii	Semi-Skilled	0.044	0.15488	-
8		<b>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	7.045125	Cum
	i	Un-Skilled	2.96	20.85357	-
	ii	Skilled	1.05	7.39738125	-
	iii	Highly-Skilled	0.35	2.46579375	-

9	<b>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory</b> - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	178.2379	Sqm
i	Un-Skilled	0.216	38.4993864	-
ii	Highly-Skilled	0.216	38.4993864	-

10	<p><b>Flooring (AR0817b) :</b>  <b>Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) -</b> Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	168.9968	Sqm
i	Un-Skilled	0.325	54.92396	-
ii	Highly-Skilled	0.325	54.92396	-

11	<p><b>Other Building Items. (AR1911) :</b>  <b>Stainless steel of 304 grade in hand railing using 50mm dia of 2mm</b> - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&amp;P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	-	72.17848	Rmt	
	i	Semi-Skilled	0.27300613496933	19.705167852761	-
	ii	Highly-Skilled	0.27300613496933	19.705167852761	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	250.55396030208	462	115755.92965956
1	Skilled	49.15776353	562	27626.66310386
2	Semi-Skilled	21.905312256601	512	11215.51987538
3	Highly-Skilled	116.65030800276	612	71389.98849769
<b>Total:</b>				<b>225988.10113649</b>