

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Dhenkanal	<b>Block</b>	Bhuban	<b>Gram Panchayat</b>	Ektali

<b>Work Code</b>	OD/352/3349/117245/402582/00041686 (REPAIR AND MAINTENANCE OF CC ROAD FROM RD ROAD TO CHANDAR)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Bhuban	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	MAINTENANCE OF ROADS AND BRIDGES
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/352/3349/117245/402582/00041686/TS
<b>Fund Sanction No.</b>	32004
<b>Fund Sanction Amount (in Rs.)</b>	270000

### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	32.508	Cum
i	Un-Skilled	4.6	149.5368	-
ii	Skilled	0.68	22.10544	-
2	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	17.2	Sqm
i	Semi-Skilled	0.05	0.86	-
ii	Skilled	0.05	0.86	-

3	<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	36.12	Cum
i	Un-Skilled	0.1236	4.464432	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	154.001232	462	71148.569184
1	Skilled	22.96544	562	12906.57728
2	Semi-Skilled	0.86	512	440.32
<b>Total:</b>				<b>84495.466464</b>