

ESTIMATION DPR							
State	Odisha	District	Gajapati	Block	Gumma	Gram Panchayat	Jhami

Work Code	OD/353/3358/117466/414626/00041744 (Improvement of Road from RD Road to Nukalama Temple at Jhami)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Gumma	Proposal Date	-
Date of Commencement	10-11-2025	Date of Completion	-
Scheme Name	Kandhamal O Gajapati Bikas Yojana	Scheme Component Name	Self/Personal Deposit
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	PRASANT KUMAR MISHRA		

Administrative Approval Details

Approval No.	OD/353/3358/117466/414626/00041744/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/353/3358/117466/414626/00041744/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.742	Cum
i	Un-Skilled	0.1236	0.7097112	-

2	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	13.968	Cum
i	Skilled	0.18	2.51424	-
ii	Un-Skilled	3.9	54.4752	-
3	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	11.484	Cum
i	Un-Skilled	4.6	52.8264	-
ii	Skilled	0.68	7.80912	-

4	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	14.4	Sqm
i	Semi-Skilled	0.05	0.72	-
ii	Skilled	0.05	0.72	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	108.0113112	462	49901.2257744
1	Skilled	11.04336	562	6206.36832
2	Semi-Skilled	0.72	512	368.64
Total: 56476.2340944				