

ESTIMATION DPR

State	Odisha	District	Jagatsinghpur	Block	Naugaon	Gram Panchayat	Naugaon
--------------	--------	-----------------	---------------	--------------	---------	-----------------------	---------

Work Code	OD/355/3391/118183/398161/00043840 (Improvement of road with Culvert near Sangram Lenka house)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Naugaon	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	OD/355/3391/118183/398161/00043840/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	172711

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.57	Cum
i	Un-Skilled	0.1236	0.441252	-

2	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	15.806	Cum
i	Skilled	0.18	2.84508	-
ii	Un-Skilled	3.9	61.6434	-
3	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	39.48	Sqm
i	Semi-Skilled	0.05	1.974	-
ii	Skilled	0.05	1.974	-

4	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	0.5948	Qntl
i	Un-Skilled	0.8	0.47584	-
ii	Highly-Skilled	0.3	0.17844	-
iii	Semi-Skilled	0.044	0.0261712	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	1.8	Cum

	i	Un-Skilled	4.6	8.28	-
	ii	Skilled	0.68	1.224	-
6		Earth Work (AR0122Bi) : Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift - Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.	-	35.3	Cum
	i	Un-Skilled	0.32	11.296	-
7		miscellaneous (ARM262) : Laying and fixing in position R.C.C. spun pipes with collars jointed with cement mortar 1:3 complete excluding cost of spun pipes and collars 900mm dia R.C.C. pipe. (Other miscellaneous items) and as directed by Engineer-in-Charge. - Laying and fixing in position R.C.C. spun pipes with collars jointed with cement mortar 1:3 complete excluding cost of spun pipes and collars 900mm dia R.C.C. pipe. (Other miscellaneous items) and as directed by Engineer-in-Charge.	-	244	Rmt

8	Earth Work (AR0122Bii) : Earthwork in hard soil or gravelly soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift - Earthwork in hard soil or gravelly soil within 5 Km.mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.	-	17.85	Cum
i	Un-Skilled	0.43	7.6755	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	89.811992	462	41493.140304
1	Skilled	6.04308	562	3396.21096
2	Semi-Skilled	2.0001712	512	1024.0876544
3	Highly-Skilled	0.17844	612	109.20528
Total:				46022.6441984