

ESTIMATION DPR							
State	Odisha	District	Dhenkanal	Block	Parajang	Gram Panchayat	Barihapur

Work Code	OD/352/3356/117413/402276/00046342 (const of cc road from santri sahi to berenapati)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Parajang	Proposal Date	-
Date of Commencement	27-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Sabyasachi samal		

Administrative Approval Details

Approval No.	OD/352/3356/117413/402276/00046342/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/352/3356/117413/402276/00046342/TS
Fund Sanction No.	35809
Fund Sanction Amount (in Rs.)	400000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	4.833	Cum

	i	Un-Skilled	0.516	2.493828	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.795	Cum
	i	Un-Skilled	0.1236	2.323062	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	28.103	Cum
	i	Skilled	0.18	5.05854	-
	ii	Un-Skilled	3.9	109.6017	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	22.86725	Cum
i	Un-Skilled	4.6	105.18935	-
ii	Skilled	0.68	15.54973	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	54.416	Sqm
i	Semi-Skilled	0.05	2.7208	-
ii	Skilled	0.05	2.7208	-
SI.No.	Labour Type	Qty Unit	Rate	Amount

0	Un-Skilled	219.60794	462	101458.86828
1	Skilled	23.32907	562	13110.93734
2	Semi-Skilled	2.7208	512	1393.0496
				Total: 115962.85522