

## ESTIMATION DPR

<b>State</b>	Odisha	<b>District</b>	Jajpur	<b>Block</b>	Binjharpur	<b>Gram Panchayat</b>	Kapila
--------------	--------	-----------------	--------	--------------	------------	-----------------------	--------

<b>Work Code</b>	OD/356/3396/118316/401937/00047164 (Impvt. of road with CC/GR-II metaling from Samal sahi to Barik sahi, Guhali)
<b>Project Category</b>	Road

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Binjharpur	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	21-08-2025	<b>Date of Completion</b>	-
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	Upgradation or Improvement
<b>Name of Executant</b>	SISIRA SEKHAR NAYAK		

## Administrative Approval Details

<b>Approval No.</b>	OD/356/3396/118316/401937/00047164/AS
---------------------	---------------------------------------

## Technical Sanction Details

<b>Technical Sanction No.</b>	OD/356/3396/118316/401937/00047164/TS
<b>Fund Sanction No.</b>	1130
<b>Fund Sanction Amount (in Rs.)</b>	400000

## LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	46.7935	Cum
i	Un-Skilled	4.6	215.2501	-
ii	Skilled	0.68	31.81958	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	215.2501	462	99445.5462
1	Skilled	31.81958	562	17882.60396
<b>Total: 117328.15016</b>				