

ESTIMATION DPR

State	Odisha	District	Koraput	Block	Bandhugaon	Gram Panchayat	Kumbhariput
--------------	--------	-----------------	---------	--------------	------------	-----------------------	-------------

Work Code	OD/363/3466/119711/428733/00047825 (Construction of CC Road at ST Street RD Road to Trinath Temple Giringikhal)
Project Category	Road

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Bandhugaon	Proposal Date	08-06-2021
Date of Commencement	08-08-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Manoj Kumar Sahoo		

Administrative Approval Details

Approval No.	OD/363/3466/119711/428733/00047825/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3466/119711/428733/00047825/TS
Fund Sanction No.	9114
Fund Sanction Amount (in Rs.)	420000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	45.6413	Cum
i	Un-Skilled	0.516	23.5509108	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	24.0092	Cum
i	Un-Skilled	0.1236	2.96753712	-

3	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	42.382	Sqm
i	Semi-Skilled	0.05	2.1191	-
ii	Skilled	0.05	2.1191	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.</p>	-	20.7	Cum
i	Un-Skilled	4.6	95.22	-
ii	Skilled	0.68	14.076	-

5	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	37.122	Cum
i	Skilled	0.18	6.68196	-
ii	Un-Skilled	3.9	144.7758	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	266.51424792	462	123129.58253904
1	Semi-Skilled	2.1191	512	1084.9792
2	Skilled	22.87706	562	12856.90772
Total:				137071.46945904