

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Gopabandhu nagar	Gram Panchayat	Jaypur

Work Code	OD/365/3494/120153/391066/00048820 (CONST OF CC ROAD FROM MAYADHAR SETHI HOUSE TO SABARSAHI LAXMI MANDAP IN JAIDA VILLAGE UNDER JAYPUR GP)						
Project Category	Road						

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Gopabandhunagar	Proposal Date	-
Date of Commencement	12-08-2025	Date of Completion	09-12-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	GANGADHAR PATRA		

Administrative Approval Details

Approval No.	OD/365/3494/120153/391066/00048820/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3494/120153/391066/00048820/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	159826

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	--	------------------------------	------

1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	2.0115	Cum
i	Un-Skilled	0.516	1.037934	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	8.0233	Cum
i	Un-Skilled	0.1236	0.99167988	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	11.34655	Cum
i	Skilled	0.18	2.042379	-
ii	Un-Skilled	3.9	44.251545	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	8.6925	Cum
i	Un-Skilled	4.6	39.9855	-
ii	Skilled	0.68	5.9109	-

5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	28.5	Sqm
i	Semi-Skilled	0.05	1.425	-
ii	Skilled	0.05	1.425	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	86.26665888	462	39855.19640256
1	Skilled	9.378279	562	5270.592798
2	Semi-Skilled	1.425	512	729.6
Total: 45855.38920056				