

ESTIMATION DPR

State	Odisha	District	Kendujhar	Block	Telkoi	Gram Panchayat	Sirigida
--------------	--------	-----------------	-----------	--------------	--------	-----------------------	----------

Work Code	OD/361/3455/119532/386413/00049700 (Improvement of Kundheihota Nua Pokhari)
Project Category	Water Body

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Telkoi	Proposal Date	-
Date of Commencement	25-11-2025	Date of Completion	06-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	New Work
Name of Executant	Madhusmita Majhi		

Administrative Approval Details

Approval No.	OD/361/3455/119532/386413/00049700/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/361/3455/119532/386413/00049700/TS
Fund Sanction No.	26956
Fund Sanction Amount (in Rs.)	500000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>miscellaneous (ARM306) : Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) requiring blasting in canal, - Excavation, loading & carriage by mechanical means in medium hard rock (can not be scapped or peeled with knife hanheld specimen can be broken with single moderate blow with pick, crushing strength between 100 to 250 kg/sqcm) requiring blasting in canal, foundation of structures and other deep cutting sections in dry, wet or submerged conditions by mechanical drilling and appropriate blasting & disposal of excavated materials with 1 Km lead, loading into and transportation by transport vehicle and depositing the excavated materials neatly in approved specified dump yard within 1 Km lead & dressing to pro section as direction by the Engineer-in-charge and trimming of bed and slope to the design finished section manually, if necessary including all cost of drilling conveyance and storage of explosive, fuse coil, detonators, all accessories, machine charges etc. complete as specification and direction of the Engineer-in-charge. (Special Items for Irrigation works).</p>	-	1228.94912	Cum
---	--	---	------------	-----

2	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	5.00706718976	Cum
i	Un-Skilled	0.516	2.5836466699162	-
3	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	4.06694942976	Cum
i	Un-Skilled	0.1236	0.50267494951834	-

4	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	8.108798848	Cum
	i Skilled	0.18	1.45958379264	-
	ii Un-Skilled	3.9	31.6243155072	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	86.6970796	Sqm
	i Semi-Skilled	0.05	4.33485398	-
	ii Skilled	0.05	4.33485398	-

6	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	4.530688	Cum
i	Un-Skilled	4.6	20.8411648	-
ii	Skilled	0.68	3.08086784	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	55.551801926634	462	25664.932490105
1	Skilled	8.87530561264	562	4987.9217543037
2	Semi-Skilled	4.33485398	512	2219.44523776
Total:				32872.299482169